

CONTRACT NO. - 60445



PROPOSED TYPICAL CROSS SECTION
STA. 3+450 TO STA. 3+500



PROPOSED TYPICAL CROSS SECTION STA. 3+550 TO STA. 3+650.5

## LEGEND

- 1) EXISTING HMA PAVEMENT (+/-) 270MM
- (2) EXISTING AGGREGATE SHOULDER
- (3) EXISTING P.C.C. SIDEWALK
- (4) EXISTING CURB AND GUTTER B-15.30 (B-6.12)
- (5) PROPOSED HMA SURFACE REMOVAL ±50MM (2")
- (6) PROPSED HMA SURFACE COURSE, MIX D N70, 50MM (2")
- (7) PROPOSED HMA BASE COURSE WIDENING, 225MM (9")
- (8) PROPOSED AGGREGATE SUBGRADE 300MM (12")
- (9) PROPOSED HMA SHOULDER, 200MM (8")
- (10) PROPOSED AGGREGATE WEDGE SHOULDER TYPE B, 150MM (6")
- (11) PROPOSED P.C.C. SIDEWALK 125MM (5")
- (12) PROPOSED COMBINATION CURB AND GUTTER B-15.30 (B-6.12)

# # FROM STA. 3+623 TO STA. 3+650.5 VARIES FROM 4.25M TO 0.0M

NOTE: THE ADDITIONAL THICKNESS OF AGGREGATE REQUIRED UNDER THE SHOULDER WILL NOT BE PAID FOR SEPARATELY. IT IS INCLUDED IN THE COST OF AGGREGATE SUBGRADE, 300 MM (SQ.M.).

TO DRAIN THE AGGREGATE SUB GRADE 300 mm, PROVIDE 100 mm DIAMETER TRAVERSE PIPE UNDER DRAIN AT 90 METER SPACING.

REVISIONS	T	
NAME DATE	] ILLINOIS DEPART	MENT OF TRANSPORTATION
	COU	RT STREET
	TYPICAL	CROSS SECTION
	SCALE: NONE	DRAWN BY
	DATE: 5/7/2011	CHECKED BY

5/7/2011
c\pw.work\pwidof\bauerdI\d0!98247\P!02397-shf-typical.dgn
bauerdI