

				CONSTRUCTION CODE							
				100% LAKE COUNTY						100% VILLAGE OF LIBERTYVILLE 0043	100% IDOT 0043
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN	SN-049-0199 BRIDGE 0010 URBAN	BOX CULVERT 0040 URBAN	RETAINING WALL 0040 URBAN	TRAFFIC SIGNALS 0021 URBAN	LIGHTING URBAN 0021		
				ROADWAY 0003 URBAN							
50104400	CONCRETE HEADWALL REMOVAL	EACH	7	7							
50105220	PIPE CULVERT REMOVAL	FOOT	1528	1528							
50200100	STRUCTURE EXCAVATION	CU YD	3159		1572		1587				
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	7925			3325	4600				
50300100	FLOOR DRAINS	EACH	8		8						
50300225	CONCRETE STRUCTURES	CU YD	1254.6		532.4		722.2				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	617.5		467.3		150.2				
50300260	BRIDGE DECK GROOVING	SQ YD	529		529						
50300285	FORM LINER TEXTURED SURFACE	SQ FT	9154			926	8228				
50300300	PROTECTIVE COAT	SQ YD	1544		1272		272				
50500305	ERECTING STRUCTURAL STEEL	L SUM	1		1						
50500505	STUD SHEAR CONNECTORS	EACH	6997		3597		3400				
50800105	REINFORCEMENT BARS	POUND	70540			70540					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	278010		157220	1930	118860				
50800515	BAR SPLICERS	EACH	841		713	128					
50901750	PARAPET RAILING	FOOT	638		130		508				
51200958	FURNISHING METAL SHELL PILES 14" X 0.250"	FOOT	2535		2535						
51202305	DRIVING PILES	FOOT	2535		2535						
51203200	TEST PILE METAL SHELLS	EACH	2		2						
51204650	PILE SHOES	EACH	149		149						
51500100	NAME PLATES	EACH	3		1	2					
52000110	PREFORMED JOINT STRIP SEAL	FOOT	190		190						
52100210	ERECTING ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	11		11						
52100520	ANCHOR BOLTS, 1"	EACH	22		22						
54003000	CONCRETE BOX CULVERTS	CU YD	386			386					
54010402	PRECAST CONCRETE BOX CULVERTS 4' X 2'	FOOT	184			184					
54010503	PRECAST CONCRETE BOX CULVERTS 5' X 3'	FOOT	99			99					
54010706	PRECAST CONCRETE BOX CULVERTS 7' X 6'	FOOT	222			222					
54010803	PRECAST CONCRETE BOX CULVERTS 8' X 3'	FOOT	116			116					
54010805	PRECAST CONCRETE BOX CULVERTS 8' X 5'	FOOT	107			107					
54213857	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	7	7							
54213883	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	10	10							
54213886	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	1	1							

* SPECIALITY ITEM

FILE NAME = \\102901\cadd sheets\st-sq-003.dgn
 USER NAME = IDOT
 PLOT SCALE = 50.0000' / IN.
 PLOT DATE = 8/12/2011

DESIGNED - EJM
 DRAWN - BK
 CHECKED - GFL
 DATE - 12/17/10

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 330	SECTION 128R-3	COUNTY LAKE	TOTAL SHEETS 518	SHEET NO. 7
CONTRACT NO. 60953				
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT				

Rev. 9-12-11