

				CONSTRUCTION CODE							
				100% LAKE COUNTY							
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN	SN-049-0199	BOX CULVERT	RETAINING WALL	TRAFFIC SIGNALS	LIGHTING URBAN	100% VILLAGE OF LIBERTYVILLE	100% IDOT
				0003 URBAN	BRIDGE 0010 URBAN	0040 URBAN	0040 URBAN	0021 URBAN	0021	0043	0043
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	9	9							
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2	2							
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2							
5421A042	PIPE CULVERTS, CLASS A, TYPE 1 42" (TEMPORARY)	FOOT	32	32							
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	9	9							
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	2	2							
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	2	2							
542A1057	PIPE CULVERTS, CLASS A, TYPE 2 12"	FOOT	72	72							
542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT	368	368							
542A1068	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	461	461							
542A1075	PIPE CULVERTS, CLASS A, TYPE 2 30"	FOOT	123	123							
550A0040	STORM SEWERS, CLASS A, TYPE 1 10"	FOOT	158	158							
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	672	672							
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	537	537							
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	174	174							
550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	92	92							
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	162	162							
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	147	147							
550A0180	STORM SEWERS, CLASS A, TYPE 1 42"	FOOT	105	105							
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	6685	6685							
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	2000	2000							
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	814	814							
550A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	1195	1195							
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	2754	2754							
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	592	592							
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	1366	1366							
550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	128	128							
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	100	100							
550A2330	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 15"	FOOT	100	100							
550A2340	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 18"	FOOT	100	100							
55100500	STORM SEWER REMOVAL 12"	FOOT	3076	3076							
55100900	STORM SEWER REMOVAL 18"	FOOT	512	512							
55101200	STORM SEWER REMOVAL 24"	FOOT	1285	1285							
56103000	DUCTILE IRON WATER MAIN 6"	FOOT	463							387	76

* SPECIALITY ITEM

FILE NAME =	USER NAME = IDOT	DESIGNED - EJM	REVISED -
11\102901\cadd sheets\sh-t-soq004.dgn		DRAWN - BK	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED - GFL	REVISED -
	PLOT DATE = 8/12/2011	DATE - 12/17/10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	128R-3	LAKE	518	8
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60953	

Rev. 9-12-11