

				CONSTRUCTION CODE								
				100% LAKE COUNTY							100% VILLAGE OF LIBERTYVILLE 0043	100% IDOT 0043
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003 URBAN	SN-049-0199 BRIDGE 0010 URBAN	BOX CULVERT 0040 URBAN	RETAINING WALL 0040 URBAN	TRAFFIC SIGNALS 0021 URBAN	LIGHTING URBAN 0021			
81803110	UNIT DUCT, 600V, 4-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/2" DIA. POLYETHYLENE	FOOT	3529						3529			
81700110	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 10	FOOT	960						960			
81701115	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE) 1/C NO. 2	FOOT	255						255			
81800320	AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	4118						4118			
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	19,036					10,507	2529			
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	46						46			
82500330	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240VOLT, 60AMP	EACH	1						1			
82500350	LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 100AMP	EACH	1						1			
83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	17						17			
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	119						119			
<del>83800505</del>	<del>BREAKAWAY DEVICE, COUPLING WITH ALUMINUM SKIRT</del>	<del>EACH</del>	<del>18</del>						<del>18</del>			
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	17						17			
84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	18						18			
84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	9						9			
84200804	REMOVAL OF POLE FOUNDATION	EACH	9						9			
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1						1			
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1						1			
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1						1			
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	3					3				
X8570225	FULL-ACTUATED CONTROLLER AND CABINET, TYPE IV, SPECIAL	EACH	2					2				
86200120	UNINTERRUPTIBLE POWER SUPPLY	EACH	2					2				
87200400	SPAN WIRE	FOOT	3043					3043				
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	27837					27837				
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	3692					3692				
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	5949					5949				
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	5386					5386				
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	3133					3133				
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	9785					9785				
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	64					64				
87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1					1				
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	6					6				
87702940	STEEL COMBINATION MAST ARM AND ASSEMBLY AND POLE, 42 FT.	EACH	1					1				
87703030	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 60 FT.	EACH	1					1				
87703050	STEEL COMBINATION MAST ARM AND ASSEMBLY AND POLE, 64 FT.	EACH	2					2				
87703070	STEEL COMBINATION MAST ARM AND ASSEMBLY AND POLE, 66 FT.	EACH	1					1				
87703090	STEEL COMBINATION MAST ARM AND ASSEMBLY AND POLE, 70 FT.	EACH	1					1				

\* SPECIALITY ITEM

FILE NAME =	USER NAME = IDOT	DESIGNED - EJM	REVISED -
11\182901\cadd sheets\sh-t-soq808.dgn		DRAWN - BK	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED - GFL	REVISED -
	PLOT DATE = 8/12/2011	DATE - 12/17/10	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF	SHEETS

F.A.P. RTE. 330		SECTION 128R-3	COUNTY LAKE	TOTAL SHEETS 518	SHEET NO. 12
CONTRACT NO. 60953					
FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT					

Rev. 9-12-11