



SCHEDULE OF PERMANENT INTERCONNECT QUANTITIES		
ITEM	UNIT	QTY
CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FT	14,702
CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FT	1,542
CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., GALVANIZED STEEL	FT	231
HANDHOLE	EA	23
TRENCH AND BACKFILL FOR ELECTRICAL WORK	EA	14,702
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EA	1
DRILL EXISTING HANDHOLE	EA	2
ELECTRIC CABLE IN CONDUIT, TRACER NO. 14 1C	FT	27,837
REMOVE ELECTRIC CABLE FROM CONDUIT	FT	17,111
RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM - LEVEL II	LSUM	1
FIBER OPTIC CABLE 24 FIBERS, SINGLE MODE	FT	27,837

NOTE:
THE TRAFFIC SIGNAL CONTROLLER EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.

RESTORATION OF WORK AREA. RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

SPAAN Tech, Inc.
311 South Wacker Drive, Suite 2400
Chicago, IL 60605
phone: 312.277.8800
fax: 312.277.8808
web: www.SpaanTech.com

39-SCM-03.dgn
HDR - PDF.plt
9/1/2011 1:59:35 PM
HDR Fullerton Parkway.tbl

USER NAME = Toby Mickey	DESIGNED - TM	REVISED - 09/02/11 TM
	DRAWN - TM	REVISED -
PLOT SCALE = 100.000000' / 1in.	CHECKED - YK	REVISED -
	DATE - 04/13/11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INTERCONNECT SCHEMATIC - SHEET 3 OF 3
ILL RTE 137 (BUCKLEY ROAD)
SCALE: N.T.S. SHEET NO. 39 OF 41 SHEETS STA. - TO STA. -

F.A.P. RTE. 330	SECTION 128R-3	COUNTY LAKE	TOTAL SHEETS 518	SHEET NO. 226
CONTRACT NO. 60953				
ILLINOIS FED. AID PROJECT				