

CONSTRUCTION CODE

100% LAKE COUNTY

CODE NO.	ITEM	UNIT	URBAN		ROADWAY 0003 URBAN	SN-049-0199 BRIDGE 0010 URBAN	BOX CULVERT 0040 URBAN	RETAINING WALL 0040 URBAN	TRAFFIC SIGNALS 0021 URBAN	LIGHTING URBAN 0021	100% VILLAGE OF LIBERTYVILLE 0043	100% IDOT 0043
			TOTAL QUANTITY									
* X2501820	SEEDING, CLASS 5 (MODIFIED)	ACRE	0.56		0.56							
* X2510635	HEAVY DUTY EROSION CONTROL BLANKET, SPECIAL	SQ YD	5490		5490							
* X2520701	SODDING, TYPE 1	SQ YD	782		782							
* X2520702	SODDING, TYPE 2	SQ YD	350		350							
* X2520703	SODDING, TYPE 3	SQ YD	1053		1053							
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	11		11							
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	33		33							
X4023000	TEMPORARY ACCESS (ROAD)	EACH	8		8							
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	554		554							
X4402600	ISLAND PAVEMENT REMOVAL	SQ YD	90		90							
X5539700	STORM SEWERS TO BE CLEANED	FOOT	600		600							
X5610004	DUCTILE IRON WATER MAIN FITTINGS	POUND	2385								777	1608
X5610706	WATER MAIN REMOVAL, 6"	FOOT	496								373	123
X5610708	WATER MAIN REMOVAL, 8"	FOOT	935									935
X5610710	WATER MAIN REMOVAL, 10"	FOOT	27								27	
X5610712	WATER MAIN REMOVAL, 12"	FOOT	250									250
X6020096	MANHOLES, TYPE A, 6"-DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	3		3							
X6022820	MANHOLES, SANITARY, 5"-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6								4	2
X6023508	INLETS, TYPE A, WITH SPECIAL FRAME AND GRATE	EACH	2		2							
X6026054	SANITARY MANHOLES TO BE REMOVED	EACH	3								3	
X6026622	VALVE VAULTS TO BE REMOVED	EACH	5								2	3
X6700410	ENGINEER'S FIELD OFFICE, TYPE A(SPECIAL)	CAL MO	27		27							
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1		1							
X7030025	WET REFLECTIVE TEMPORARY TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	1161.6		1161.6							
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	86695		86695							
X7030040	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH	FOOT	6515		6515							
X7030055	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH	FOOT	800		800							
* X7240800	REMOVE AND RE-ERECT EXISTING SIGN	EACH	2		2							
* X8710029	FIBER OPTIC CABLE 24 FIBERS, SINGLE MODE	FOOT	27837						27837			
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	1702								1702	
* X8900030	REMOVE EXISTING TEMPORARY TRAFFIC SIGNAL EQUIPMENT	EACH	1						1			
XX000610	RELOCATE EXISTING MAILBOX	EACH	18		18							
* XX001186	PLANTER REMOVAL	EACH	3		3							

* SPECIALITY ITEM

FILE NAME = u:\02981\cadd sheets\sh-t-eoq011.dgn	USER NAME = IDDT	DESIGNED - EJM	REVISED -
		DRAWN - BK	REVISED -
		CHECKED - GFL	REVISED -
		DATE - 12/17/10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 330	SECTION 128R-3	COUNTY LAKE	TOTAL SHEETS 518	SHEET NO. 15
CONTRACT NO. 60953				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Rev. 9-22-11
Rev. 9-12-11