

STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

Pi\11306.000 - CRA IL Rte 21\World

es\Drawing Files\Sht\26-TMP INT-05.dgn

PLOT SCALE = 100.000000 '/ in.

PLOT DATE = 7/27/2011

DRAWN - TCM

CHECKED - TCM

07/08/11

DATE

REVISED -

REVISED

REVISED

NOTE: THE TRAFFIC SIGNAL CONTROLLER EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.

RESTORATION OF WORK AREA. RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANA, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

	F.A.P. SECTION	COUNTY TOTAL SHEET NO.
ILL RTE 137 (BUCKLEY RD.)	330 128R-3	LAKE 518 213
		CONTRACT NO. 60953
SCALE: 1" = 50' SHEET NO. 26 OF 41 SHEETS STA TO STA	ILLINOIS FED. AI	D PROJECT