

INCIDENTAL HOT-MIX ASPHALT SURFACING

LOCATION	QUANTITY (TON)
*JOBSITE	360
TOTAL	360

PAVEMENT REMOVAL

LOCATION	QUANTITY (SQ YD)
STATION	
STA. 74+90 TO STA. 77+05 (COMB. CONC. C&G LOCATIONS)	37
TOTAL	37

COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT

LOCATION	QUANTITY (FOOT)
STATION	
IL ROUTE 31 - MEDIAN LT & RT STA. 74+90 TO STA. 77+05	110
TOTAL	110

CURB REMOVAL

LOCATION	QUANTITY (FOOT)
STATION	
IL ROUTE 31 - MEDIAN LT & RT STA. 74+90 TO STA. 77+05	430
TOTAL	430

MEDIAN SURFACE REMOVAL

LOCATION	QUANTITY (SQ FT)
STATION	
IL ROUTE 31 STA. 74+90 TO STA. 77+05	1055
TOTAL	1055

CONCRETE MEDIAN, TYPE SM

LOCATION	QUANTITY (SQ FT)
STATION	
IL ROUTE 31 STA. 74+90 TO STA. 77+05	1055
TOTAL	1055

FRAMES AND GRATES TO BE ADJUSTED

LOCATION	QUANTITY (EACH)
STATION	
STA. 76+07.3; 0.2' LT.	1
TOTAL	1

TRAFFIC CONTROL AND PROTECTION, (SPECIAL)

LOCATION	QUANTITY (L SUM)
STATION	
JOBSITE	1
TOTAL	1

TRAFFIC CONTROL SURVEILLANCE

LOCATION	QUANTITY (CAL DAY)
STATION	
JOBSITE	30
TOTAL	30

SHORT-TERM PAVEMENT MARKING

LOCATION	QUANTITY (FOOT)
*JOBSITE	6000
TOTAL	6000

PAVEMENT MARKING TAPE, TYPE III 4"

LOCATION	QUANTITY (FOOT)
STATION	
WHITE	
STAGE I	
59+00.00 TO 76+25.00	1629
STAGE II	
58+53.30 TO 79+00.00	1885
STAGE III	
64+32.00 TO 70+00.00	568
SUBTOTAL	4082
YELLOW	
STAGE I	
59+00.00 TO 79+00.00	3593
STAGE II	
56+00.00 TO 77+45.70	3690
SUBTOTAL	7283
TOTAL	11365

PAVEMENT MARKING TAPE, TYPE III 6"

LOCATION	QUANTITY (FOOT)
STATION	
WHITE	
STAGE I	
61+50.00 TO 63+75.00	225
STAGE II	
61+35.00 TO 63+76.00	240
73+46.50 TO 76+40.50	74
TOTAL	539

PAVEMENT MARKING TAPE, TYPE III 12"

LOCATION	QUANTITY (FOOT)
STATION	
WHITE	
STAGE I	
64+28.00 TO 65+44.50	43
STAGE II	
64+32.00 TO 65+39.30	40
TOTAL	83

PAVEMENT MARKING TAPE, TYPE III 24"

LOCATION	QUANTITY (FOOT)
STATION	
WHITE	
STAGE I	
STA. 63+75.00	24
STA. 64+46.15	12
STAGE II	
STA. 63+75.00	24
STA. 64+40.50	12
TOTAL	72

TEMPORARY PAVEMENT MARKING - LINE 4"

LOCATION	QUANTITY (FOOT)
*JOBSITE	1000
TOTAL	1000

WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION	LENGTH (FT)	QUANTITY (SQ FT)
STATION		
STAGE I		
4" WHITE TAPE	1629	543
4" YELLOW TAPE	3593	1198
6" WHITE TAPE	225	113
12" WHITE TAPE	43	43
24" WHITE TAPE	36	72
STAGE II		
4" WHITE TAPE	1885	628
4" YELLOW TAPE	3690	1230
6" WHITE TAPE	314	157
12" WHITE TAPE	40	40
24" WHITE TAPE	36	72
STAGE III		
4" WHITE TAPE	568	189
TEMPORARY PAVEMENT MARKING		334
SHORT-TERM PAVEMENT MARKING		2000
TOTAL		6619

TEMPORARY CONCRETE BARRIER

LOCATION	QUANTITY (FOOT)
STATION	
STAGE I	387.5
STAGE II	587.5
TOTAL	975.0

RELOCATE TEMPORARY CONCRETE BARRIER

LOCATION	QUANTITY (FOOT)
STATION	
STAGE II	387.5
STAGE III	450
TOTAL	837.5

RAISED REFLECTIVE PAVEMENT MARKER

LOCATION	QUANTITY (EACH)
STATION TO STATION	
TWO-WAY AMBER	
STA. 56+00 TO 79+00 (MED)	115
ONE-WAY CRYSTAL	
STA. 56+00 TO 79+00 (LT)	65
STA. 56+00 TO 79+00 (RT)	66
TOTAL	246

RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)

LOCATION	QUANTITY (EACH)
IL 31 OVER SOO LINE RR BRIDGE	
NORTHBOUND	8
SOUTHBOUND	8
TOTAL	16

TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER

LOCATION	QUANTITY (EACH)
IL 31 OVER SOO LINE RR BRIDGE	
STAGE I - STA. 64+32 TO STA. 73+25	24
STAGE II - STA. 64+32 TO STA. 73+25	24
TOTAL	48

BARRIER WALL MARKERS, TYPE C

LOCATION	QUANTITY (EACH)
*JOBSITE	184
TOTAL	184

PAVEMENT MARKING REMOVAL

LOCATION	QUANTITY (SQ FT)
STATION	
WHITE - (SKIP DASH, 4")	384
WHITE - (SOLID, 4")	767
YELLOW - (SOLID, 4")	1534
TOTAL	2685

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

LOCATION	QUANTITY (EACH)
STATION TO STATION	
56+00 TO 79+00	246
TOTAL	246

DRAINAGE STRUCTURES TO BE ADJUSTED

LOCATION	QUANTITY (EACH)
STATION	
STA. 76+07.3; 0.2' LT.	1
TOTAL	1

FLEXIBLE DELINEATORS

LOCATION	QUANTITY (EACH)
*JOBSITE	120
TOTAL	120

IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3

LOCATION	QUANTITY (EACH)
STATION	
STAGE I - JOBSITE	2
STAGE II - JOBSITE	2
TOTAL	4

IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3

LOCATION	QUANTITY (EACH)
STATION	
STAGE II - JOBSITE	2
STAGE III - JOBSITE	2
TOTAL	4

RAILROAD PROTECTIVE LIABILITY INSURANCE

LOCATION	QUANTITY (L SUM)
JOBSITE	1
TOTAL	1

TEMPORARY INFORMATION SIGNING

LOCATION	QUANTITY (SQ FT)
JOBSITE	256
TOTAL	256

TEMPORARY PAVEMENT

LOCATION	QUANTITY (SQ YD)
STATION	
STA. 74+90 TO STA. 77+05 (COMB. CONC. C&G LOCATIONS)	37
TOTAL	37

*ESTIMATED QUANTITY

FILE NAME = ...\\D160C06-sht-schedules.dgn	USER NAME = Plotted by f1in	DESIGNED - SGL	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES IL ROUTE 31 (STATE STREET) OVER SOO LINE RAILROAD		F.A. RTE. 3887	SECTION R-VB-R	COUNTY KANE	TOTAL SHEETS 83	SHEET NO. 9	
	PLOT SCALE = 50.00' / IN.	CHECKED - FML	REVISED -		SCALE: NONE	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
	PLOT DATE = 8/10/2011	DATE - 07/01/2011	REVISED -		CONTRACT NO. 60C06							