

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	0004	0021	0021	0021	0021	CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	0004	0021	0021	0021	0021
				90% FED 10% STATE ROADWAY	90% FED 5% STATE 5% KANE T. SIGNALS	100% STATE LIGHTING/SIGNAL INTERCONNECT	100% KANE COUNTY	100% CITY OF ELGIN E.V.P.					90% FED 10% STATE ROADWAY	90% FED 5% STATE 5% KANE T. SIGNALS	100% STATE LIGHTING/SIGNAL INTERCONNECT	100% KANE COUNTY	100% CITY OF ELGIN E.V.P.
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	794	794					40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	117	117				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	347	347					40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	95	95				
20101000	TEMPORARY FENCE	FOOT	650	650					40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	5745	5745				
* 20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	5	5					42001300	PROTECTIVE COAT	SO YD	6825	6825				
* 20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	10	10					42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	27	27				
20200100	EARTH EXCAVATION	CU YD	17772	17772					44000100	PAVEMENT REMOVAL	SO YD	7355	7355				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	5660	5660					44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	32595	32595				
20800150	TRENCH BACKFILL	CU YD	2232	2232					44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	1095	1095				
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SO YD	5056	5056					44000300	CURB REMOVAL	FOOT	80	80				
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	11720	11720					44000400	GUTTER REMOVAL	FOOT	2173	2173				
* 21101805	COMPOST FURNISH AND PLACE, 2"	SO YD	11720	11720					44000400	GUTTER REMOVAL	FOOT	2173	2173				
* 25000210	SEEDING, CLASS 2A	ACRE	4.5	4.5					44004250	PAVED SHOULDER REMOVAL	SO YD	9800	9800				
* 25000310	SEEDING, CLASS 4	ACRE	2.42	2.42					44201839	CLASS D PATCHES, TYPE II, 16 INCH	SO YD	188	188				
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	480	480					44201843	CLASS D PATCHES, TYPE III, 16 INCH	SO YD	117	117				
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	480	480					44201845	CLASS D PATCHES, TYPE IV, 16 INCH	SO YD	249	249				
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	480	480					44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	14580	14580				
* 25100630	EROSION CONTROL BLANKET	SO YD	33495	33495					50105220	PIPE CULVERT REMOVAL	FOOT	360	360				
* 25100900	TURF REINFORCEMENT MAT	SO YD	680	680					54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1				
* 25200110	SODDING, SALT TOLERANT	SO YD	3990	3990					54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	13	13				
* 25200200	SUPPLEMENTAL WATERING	UNIT	20	20					54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1				
28000305	TEMPORARY DITCH CHECKS	FOOT	264	264					54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	1	1				
28000400	PERIMETER EROSION BARRIER	FOOT	12225	12225					54213705	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 60"	EACH	1	1				
28000510	INLET FILTERS	EACH	75	75					54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1	1				
28100105	STONE RIPRAP, CLASS A3	SO YD	585	585					54247190	GRATING FOR CONCRETE FLARED END SECTION 48"	EACH	1	1				
28200200	FILTER FABRIC	SO YD	585	585					54247210	GRATING FOR CONCRETE FLARED END SECTION 60"	EACH	1	1				
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SO YD	200	200					542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	80	80				
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	270	270					542A1060	PIPE CULVERTS, CLASS A, TYPE 2 15"	FOOT	73	73				
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	290	290					550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	1438	1438				
35600714	HOT-MIX ASPHALT BASE COURSE WIDENING, 9 1/2"	SO YD	7490	7490					550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	287	287				
35600718	HOT-MIX ASPHALT BASE COURSE WIDENING, 10 1/2"	SO YD	11200	11200					550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	78	78				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	21	21													
40600300	AGGREGATE (PRIME COAT)	TON	103	103													
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	77	77													
40600895	CONSTRUCTING TEST STRIP	EACH	2	2													
										* SPECIALTY ITEMS							