

SUMMARY OF QUANTITIES			URBAN					CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN					CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0004	0021	0021	0021	0021	TOTAL QUANTITIES	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0004	0021	0021	0021	0021	TOTAL QUANTITIES	0004	0021	0021	0021	0021	
				90% FED 10% STATE ROADWAY	90% FED 5% STATE 5% KANE T. SIGNALS	100% STATE LIGHTING/SIGNAL INTERCONNECT	100% KANE COUNTY	100% CITY OF ELGIN E.V.P.						90% FED 10% STATE ROADWAY	90% FED 5% STATE 5% KANE T. SIGNALS	100% STATE LIGHTING/SIGNAL INTERCONNECT	100% KANE COUNTY	100% CITY OF ELGIN E.V.P.		90% FED 10% STATE ROADWAY	90% FED 5% STATE 5% KANE T. SIGNALS	100% STATE LIGHTING/SIGNAL INTERCONNECT	100% KANE COUNTY	100% CITY OF ELGIN E.V.P.	
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	512		391	121				* 87700310	STEEL MAST ARM ASSEMBLY AND POLE, 54 FT	EACH	1		1										
* 81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	500			500				* 87700320	STEEL MAST ARM ASSEMBLY AND POLE, 55 FT	EACH	1		1										
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	522		522					* 87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT.	EACH	1		1										
* 81400100	HANDHOLE	EACH	7		6	1				* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16		16										
* 81400200	HEAVY-DUTY HANDHOLE	EACH	4		4					* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4										
* 81400300	DOUBLE HANDHOLE	EACH	2		2					* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	60		60										
* 81603090	UNIT DUCT, 600V, 3-1C NO. 4, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	3700			3700				* 87900200	DRILL EXISTING HANDHOLE	EACH	2			2									
* 81702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	FOOT	75			75				* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	8		8										
* 81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	3200			3200				* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	4		4										
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	5808		1352	4456				* 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	4		4										
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	20			20				* 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	12		12										
* 83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	8			8				* 88500100	INDUCTIVE LOOP DETECTOR	EACH	20		20										
* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	20			20				* 88600100	DETECTOR LOOP, TYPE I	FOOT	914		914										
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	12			12				* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1										
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2			2				* 89501250	RELOCATE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2		2										
* X8570225	FULL-ACTUATED CONTROLLER AND CABINET, TYPE IV, SPECIAL	EACH	1		1					* 89501400	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT	EACH	4											4	
* 87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1/C	FOOT	9228		9228					* 89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	1											1	
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1139				1139			* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	7167			7167									
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	3164		3164					* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1										
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1469		1469					* 89502380	REMOVE EXISTING HANDHOLE	EACH	13		12	1									
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	6984		6984					* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9		9										
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	192		192					* 89502400	REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE	EACH	4		4										
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1172		1172					* A2002374	TREE, BETULA NIGRA (RIVER BIRCH), 10' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	16	16											
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4		4					* A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	5	5											
* 87700115	STEEL MAST ARM ASSEMBLY AND POLE, 15 FT.	EACH	4			4				* C2003360	SHRUB, HAMAMELIS VIRGINIANA (COMMON WITCHHAZEL), 5' HEIGHT, BALLED AND BURLAPPED	EACH	5	5											
* 87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1		1					* C2C01424	SHRUB, CORNUS AMOMUM (SILKY DOGWOOD), 2' HEIGHT, CONTAINER	EACH	100	100											