SCHEDULE OF QUANTITIES

	LOCATION	U.S. RTE 41 (SKOKIE HIGHWAY) AT PARK AVENUE WEST	U.S. RTE 41 (SKOKIE HIGHWAY) AT IL RTE 22 (HALF DAY ROAD)	U.S. RTE 41 (SKOKIE HIGHWAY) AT OLD ELM ROAD	U.S. RTE 41 (SKOKIE HIGHWAY) AT WESTLEIGH ROAD	U.S. RTE 41 (SKOKIE HIGHWAY) AT IL RTE 60 (KENNEDY ROAD)	U.S. RTE 41 (SKOKIE HIGHWAY) AT IL RTE 137 (BUCKLEY ROAD)	U.S. RTE 41 (SKOKIE HIGHWAY) AT MARTIN LUTHER KING JR.	U.S. RTE 41 (SKOKIE HIGHWAY) AT AMHURST PARKWAY	U.S. RTE 41 (SKOKIE HIGHWAY) AT IL RTE 21 (RIVERSIDE DRIVE)	U.S. RTE 41 (SKOKIE HIGHWAY) AT STEARNS SCHOOL ROAD		U.S. RTE 41 (SKOKIE HIGHWAY) AT WADSWORTH ROAD	U.S. RTE 41 (SKOKIE HIGHWAY) AT IL RTE 173 (ROSECRANS ROAD)		IL RTE 173 (ROSECRANS ROAD) AT KILBOURNE ROAD		IL RTE 173 (ROSECRANS ROAD) AT DELANY ROAD		IL RTE 131 (GREEN BAY ROAD) AT 21ST STREET	IL RTE 131 (GREEN BAY ROAD) AT IL RTE 173 (ROSECRANS	IL RTE 131 (GREEN BAY ROAD) AT RUSSELL ROAD (STATE LINE ROAD)	
	FUNDING BREAK-DOWNS	90% FEDERAL 5% STATE 5% CITY OF HIGHLAND PARK	90% FEDERAL 10% STATE	90% FEDERAL 5% STATE 5% CITY OF LAKE FOREST	90% FEDERAL 5% STATE 5% CITY OF LAKE FOREST	90% FEDERAL 5% STATE 5% CITY OF LAKE FOREST	90% FEDERAL 10% STATE	90% FEDERAL 5% STATE 5% LAKE COUNTY	90% FEDERAL 6.67% STATE 3.33% CITY OF WAUKEGAN	90% FEDERAL 10% STATE	90% FEDERAL 5% STATE 5% LAKE COUNTY		90% FEDERAL 5% STATE 5% LAKE COUNTY	90% FEDERAL 10% STATE		90% FEDERAL 5% STATE 5% LAKE COUNTY		90% FEDERAL 5% STATE 2.5% LAKE COUNTY 2.5% VILLAGE OF WADSWORTH		90% FEDERAL 5% STATE 5% LAKE COUNTY	90% FEDERAL 10% STATE	90% FEDERAL 5% STATE 5% LAKE COUNTY	
	TYPE	TRAFFIC SIGNALS																					
ITEM	UNIT	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021 ✳✳✳	0021	0021	0021 ✳✳	0021	0021 ✳✳	0021	0021 ✳✳	0021	0021	0021	0021 ✳✳✳✳
EARTH EXCAVATION	CU YD			2																			
PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	190		265	130								40	40				40			40	40	
DETECTABLE WARNINGS	SQ FT	48		72	28																		
COMBINATION CURB AND GUTTER REMOVAL	FOOT			26																			
SIDEWALK REMOVAL	SQ FT	150		216	130																		
COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (ABUTTING EXISTING PAVEMENT)	FOOT			26																			
MOBILIZATION	L SUM																						
TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM																						
TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM																						
TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM																						
CHANGEABLE MESSAGE SIGN	CAL MO															1.00							
✳ THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	300		340	325																		
✳ THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT															88							
✳ THERMOPLASTIC PAVEMENT MARKING REMOVAL	SQ FT	150		170	185											35							
CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT															620							
CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT																					51	
CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT															52							
HANDHOLE	EACH															1							
HEAVY-DUTY HANDHOLE	EACH															5							
TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT															620						51	
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1	1	1	1	1	1	1	1	1		1	1		1		1		1	1	1	
FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH													1		1		1					
SPAN WIRE	FOOT															250							
TETHER WIRE	FOOT															250							
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT											433											274
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT		491		194						1,233			114								1,015	
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT										439											542	
ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT															726							
ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT															35							
ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 3C	FOOT																176						
ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 5C	FOOT															1,048							
ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 7C	FOOT															544							
STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH										1												
STEEL MAST ARM ASSEMBLY AND POLE, 52 FT.	EACH																					1	
STEEL MAST ARM ASSEMBLY AND POLE, 56 FT.	EACH																					1	
CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT										13											15	
CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT																					21	
DRILL EXISTING HANDHOLE	EACH										1											2	

✳-SPECIALTY ITEM
✳✳-ITEM PAID FOR BY THE NEWPORT TOWNSHIP FIRE PROTECTION DISTRICT
✳✳✳-ITEM PAID FOR BY THE VILLAGE OF GURNEE
✳✳✳✳-ITEM PAID FOR BY THE CITY OF ZION

GHA #4085.874

FILE NAME = 4085.874-TR1.dwg	USER NAME = ZACH WALLSTEN	DESIGNED - JRD	REVISED -
		DRAWN - ZCW	REVISED -
	PLOT SCALE = 1" = .0833'	CHECKED - KLB	REVISED -
	PLOT DATE = 6/30/2011	DATE - 6/30/2011	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
(SHEET 1 OF 2)

SCALE: N.A. | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VARIES	2011-042-TS	LAKE	62	4
		CONTRACT #: 60P49		
		ILLINOIS FED. AID PROJECT		