

LANDSCAPING AND EROSION CONTROL SCHEDULE OF QUANTITIES

LOCATION	TOPSOIL FURNISH & PLACE, 4" (SQ YD)	SEEDING, CLASS 2 (ACRE)	MULCH, METHOD 1 (ACRE)	PERIMETER EROSION BARRIER (LF)
LOCATION #1: 22W312 IL ROUTE 53, GLEN ELLYN, IL, 60137	611	0.13	0.13	192
LOCATION #2: 3S540 OSAGE DRIVE, GLEN ELLYN, IL, 60137	461	0.10	0.10	429
LOCATION #3: 7 LISA LANE, HAWTHORN WOODS, IL, 62234	659	0.14	0.14	205
LOCATION #4: 568 ELM GROVE DRIVE, ELGIN, IL, 60123	298	0.06	0.06	62
LOCATION #5: 1113 BIRCHDALE DRIVE, ELGIN, IL, 60123	244	0.05	0.05	145
TOTAL	2,273	0.47	0.47	1,033

EROSION CONTROL GENERAL NOTES

ALL EROSION CONTROL MEASURES SHALL BE IN ACCORDANCE WITH THE PROCEDURES AND STANDARDS FOR URBAN SOIL EROSION AND SEDIMENTATION CONTROL MANUAL.

SOIL DISTURBANCE SHALL BE CONDUCTED IN SUCH A MANNER AS TO MINIMIZE EROSION. SOIL STABILIZATION MEASURES SHALL CONSIDER THE TIME OF YEAR, SITE CONDITIONS, AND THE USE OF TEMPORARY OR PERMANENT MEASURES.

SOIL EROSION AND SEDIMENTATION CONTROL FEATURES SHALL BE CONSTRUCTED PRIOR TO THE COMMENCEMENT OF UPLAND DISTURBANCE.

TEMPORARY SOIL STABILIZATION SHALL BE APPLIED TO DISTURBED AREAS WITHIN 14 CALENDAR DAYS OF THE END OF THE ACTIVE HYDROLOGIC DISTURBANCE. PERMANENT STABILIZATION SHALL BE DONE WITHIN 14 DAYS AFTER COMPLETION OF THE FINAL GRADING OF THE SOIL.

ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION IS ACHIEVED OR AFTER TEMPORARY MEASURES ARE NO LONGER NEEDED. TRAPPED SEDIMENT AND OTHER DISTURBED SOIL AREAS SHALL BE PERMANENTLY STABILIZED.

ALL TEMPORARY AND PERMANENT EROSION CONTROL MEASURES MUST BE MAINTAINED AND REPAIRED AS NEEDED. THE GENERAL CONTRACTOR WILL BE RESPONSIBLE FOR INSPECTION AND REPAIR DURING CONSTRUCTION. THE OWNER WILL BE RESPONSIBLE IF EROSION CONTROL IS REQUIRED AFTER THE CONTRACTOR HAS COMPLETED THE PROJECT.

THE EROSION CONTROL MEASURES INDICATED ON THE PLANS ARE THE MINIMUM REQUIREMENTS. ADDITIONAL MEASURES MAY BE REQUIRED, AS DIRECTED BY THE ENGINEER OR GOVERNING AGENCY.

FILE NAME =	USER NAME = pocsechal	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	LANDSCAPING AND EROSION CONTROL GENERAL NOTES AND SCHEDULES OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pwork\pocsechal\0270297\sh	plan.dgn	DRAWN -	REVISED -			VAR.	2011-044-DM	VARIOUS	22	10	
	PLOT SCALE = 20.0000' / 1" =	CHECKED -	REVISED -			CONTRACT NO. 60P53					
	PLOT DATE = 6/30/2011	DATE -	REVISED -			SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	