

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				80% FED 20% STATE ROADWAY 0004 RURAL	80% FED 20% STATE BRIDGE 0011 S.N. 016-0199	100% ISTHA BRIDGE 0011 S.N. 016-0199
				URBAN		
20200100	EARTH EXCAVATION	CU YD	25	25		
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	154	154		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	192	192		
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	152	152		
25000210	SEEDING, CLASS 2A	ACRE	0.04	0.04		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4	4		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4	4		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4	4		
25100630	EROSION CONTROL BLANKET	SQ YD	647	647		
25200200	SUPPLEMENTAL WATERING	UNIT	1	1		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100		
28000400	PERIMETER EROSION BARRIER	FOOT	1,541	1,541		
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	566	566		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	16	16		
42001300	PROTECTIVE COAT	SQ YD	3,874	624	3,250	
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	103	103		
44000100	PAVEMENT REMOVAL	SQ YD	501	501		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	96	96		
44003100	MEDIAN REMOVAL	SQ FT	3,524	3,524		
44004250	PAVED SHOULDER REMOVAL	SQ YD	19	19		
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	87	87		
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	41	41		
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1	
50102400	CONCRETE REMOVAL	CU YD	40		40	
50157300	PROTECTIVE SHIELD	SQ YD	2,595		2,595	
50200100	STRUCTURE EXCAVATION	CU YD	220		220	
50300225	CONCRETE STRUCTURES	CU YD	71.1		71.1	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,215		1,215	
50300260	BRIDGE DECK GROOVING	SQ YD	2,520		2,520	
50401005	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 48 IN.	FOOT	3,171			3,171
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	215,830		215,830	
50800515	BAR SPLICERS	EACH	1,047		1,047	

\* SPECIALTY ITEMS  
\*\* TOLLWAY ITEMS

Rev. 9-8-11