

SUMMARY OF QUANTITIES			URBAN	100% STATE	
CODE NO.	ITEM	UNIT	TOTAL	ROADWAY 0004	BRIDGE 0011
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	201	201	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	15	15	
20101000	TEMPORARY FENCE	FOOT	580	580	
* 20101100	TREE TRUNK PROTECTION	EACH	5	5	
* 20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	3	3	
* 20101700	SUPPLEMENTAL WATERING	UNIT	26	26	
20200100	EARTH EXCAVATION	CU YD	179	179	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	324	324	
20300100	CHANNEL EXCAVATION	CU YD	1050	1050	
20400800	FURNISHED EXCAVATION	CU YD	646	646	
* 21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	551	551	
* 25000310	SEEDING, CLASS 4	ACRE	0.11	0.11	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10	10	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10	10	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10	10	
* 25000775	SELECTIVE MOWING STAKES	EACH	1	1	
* 25003310	INTERSEEDING, CLASS 4	ACRE	0.4	0.4	
* 25100105	MULCH, METHOD 1	ACRE	0.4	0.4	
* 25100630	EROSION CONTROL BLANKET	SQ YD	551	551	
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	12	12	
28000305	TEMPORARY DITCH CHECKS	FOOT	39	39	
28000400	PERIMETER EROSION BARRIER	FOOT	826	826	
28100107	STONE RIPRAP, CLASS A4	SQ YD	745		745
28200200	FILTER FABRIC	SQ YD	745		745
35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING, 9"	SQ YD	72	72	

SUMMARY OF QUANTITIES			URBAN	100% STATE	
CODE NO.	ITEM	UNIT	TOTAL	ROADWAY 0004	BRIDGE 0011
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1	
40600300	AGGREGATE (PRIME COAT)	TON	6	6	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	24	24	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	13	13	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	147	147	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	98	98	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	113	113	
44000100	PAVEMENT REMOVAL	SQ YD	599	599	
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	860	860	
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	78	78	
44201297	DOWEL BARS 1"	EACH	340	340	
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	39	39	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	39	39	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1081	1081	
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	358	358	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50200100	STRUCTURE EXCAVATION	CU YD	340		340
50300100	FLOOR DRAINS	EACH	4		4
50300225	CONCRETE STRUCTURES	CU YD	150.1		150.1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	301.5		301.5
50300260	BRIDGE DECK GROOVING	SQ YD	671		671
50300280	CONCRETE ENCASEMENT	CU YD	5.6		5.6
50300285	FORM LINER TEXTURED SURFACE	SQ FT	1411		1411
50300300	PROTECTIVE COAT	SQ YD	763		763
50400905	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 42 IN.	FOOT	496		496
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	74760		74760

* Specialty Items

LOCO INC.
CONSULTING ENGINEERS
1960 WALL ST., SUITE 222
NAPERVILLE, ILLINOIS 60563 PH: (630) 577-9100

DESIGNED - MJY	REVISED -
DRAWN - ST, TSC	REVISED -
CHECKED - MJY, SLV	REVISED -
DATE - 07/01/2011	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
119TH STREET OVER MILL CREEK

SCALE: NONE SHEET NO. 1 OF 2 SHEETS STA. 17+53.36 TO STA. 22+39.64

O.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
213	0102B-1	COOK	54	3
D-91-052-02			CONTRACT NO. 62390	
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				