



**TOTAL BILL OF MATERIAL**

ITEM	UNIT	TOTAL
Segmental Concrete Block Wall	Sq. Ft.	400
Structure Excavation	Cu. Yd.	65

Excavation required for installation of Segmental Concrete Block Wall shall be done in accordance with the applicable portions of Section 502 of the Standard Specifications and will be paid for as Structure Excavation.

The color of the wall shall be approved by the Engineer.

**NORTHEAST RETAINING WALL DETAILS  
WINN ROAD  
OVER NIPPERSINK CREEK  
F.A.U. ROUTE 0157  
SECTION NO. 07-00012-00-BR  
MCHENRY COUNTY  
STATION 30+56.78  
STRUCTURE NO. 056-6123**

DATE: 6/23/11

SHEET NO. S-4	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
				0157	07-00012-00-BR
CONTRACT NO. 63544					
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT BRM-8003 (921)					

**SEC GROUP, INC.**  
An HR Green Company  
420 N. Front Street, McHenry, IL 60050  
1.815.385.1778 f.815.385.1781  
www.secgroupinc.com  
McHenry, IL • Yorkville, IL • New Lenox, IL • Chicago, IL

DESIGNED	JMW
CHECKED	RGD
DRAWN	RCB
CHECKED	RGD

FILE NAME: 052012\_wa02.dgn  
PLOT DRIVER: pdfplot  
PEN TABLE: standard-trans.tbl