

PI#	ITEM DESCRIPTION	SPECIAL PROVISION	SPECIALTY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
						STP FUNDS				
						0004	0021	0042	0021	0021
					ROADWAY	TRAFFIC SIGNALS*	TRAINEES	HIGHWAY LIGHTING	EMERGENCY VEHICLE PREEMPTION	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT			FOOT	5535	5535				
48100700	AGGREGATE SHOULDERS, TYPE A 8"			SQ YD	2166	2166				
48203029	HOT-MIX ASPHALT SHOULDERS, 8"			SQ YD	2909	2909				
50105220	PIPE CULVERT REMOVAL			FOOT	620	620				
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"			FOOT	138	138				
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"			FOOT	48	48				
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"			EACH	13	13				
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"			EACH	4	4				
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"			EACH	3	3				
54247100	GRATING FOR CONCRETE FLARED END SECTION 15"	*		EACH	13	13				
54247110	GRATING FOR CONCRETE FLARED END SECTION 18"	*		EACH	4	4				
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"			EACH	3	3				
550A2330	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 15"	*		FOOT	194	194				
550A2340	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 18"	*		FOOT	107	107				
550A2360	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 24"	*		FOOT	66	66				
550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	*		FOOT	65	65				
550A2560	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 24"	*		FOOT	162	162				
56400100	FIRE HYDRANTS TO BE MOVED	*	X	EACH	1	1				
56400300	FIRE HYDRANTS TO BE ADJUSTED	*	X	EACH	1	1				
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS			EACH	13	13				
60107600	PIPE UNDERDRAINS 4"			FOOT	900	900				
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	*		FOOT	270	270				
60108300	PIPE UNDERDRAINS 8" (SPECIAL)	*		FOOT	300	300				
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID			EACH	3	3				
60200205	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID			EACH	1	1				
60203805	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID			EACH	3	3				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12			FOOT	80	80				
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS		X	FOOT	208	208				
63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS		X	FOOT	565	565				
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2		X	EACH	1	1				
63200310	GUARDRAIL REMOVAL			FOOT	767	767				
67000500	ENGINEER'S FIELD OFFICE, TYPE B			CAL MO	5	5				
67100100	MOBILIZATION			L SUM	1	1				
66900200	NON-SPECIAL WASTE DISPOSAL		X	CU YD	227	227				

\* 50% STATE, 25% CITY, 25% DORR TOWNSHIP

FILE NAME = P:\2010\100174\cod\phase 2\dwg\100174-sh-cv-cover.dgn	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES IL ROUTE 176 AND BRIARWOOD RD.</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = #SCALE#	PLOT DATE = 8/9/2011	DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	McHENRY	56	3A
		CHECKED -	REVISED -								CONTRACT NO.	63551	
		DATE -	REVISED -								ILLINOIS FED. AID PROJECT		