

SUMMARY OF QUANTITIES

GREAT WESTERN TRAIL

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	75% FED 25% LOCAL	75% FED 25% GCPF	75% FED 25% LOCAL	75% FED 25% LOCAL	75% FED 25% GCPF	75% FED 25% GCPF	75% FED 25% LOCAL	75% FED 25% LOCAL	
				BIKE PATH	BIKE PATH	BRIDGE, NEW CONSTRUCTION	BRIDGE, NEW CONSTRUCTION	BRIDGE, NEW CONSTRUCTION	BRIDGE, NEW CONSTRUCTION	RETAINING WALL	LANDSCAPING	LIGHTING
				0028	0028	SN 022-3120	SN 022-3121	SN 022-3121	SN 022-3122	SN 022-3123	0031	0021
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	426	284	142	0008	0008	0008	0008	0040	0031	0021
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	203	135	68							
20100500	TREE REMOVAL, ACRES	ACRE	3.0	2.0	1.0							
20101100	TREE TRUNK PROTECTION	EACH	29	19	10							
20200100	EARTH EXCAVATION	CU YD	2,980	1,490	1,490							
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	3,660	1,830	1,830							
20400100	BORROW EXCAVATION	CU YD	6,900	3450	3450							
20400800	FURNISHED EXCAVATION	CU YD	10,505	5,253	5,252							
20800150	TRENCH BACKFILL	CU YD	65	43	22							
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	11,350		5,675						5,675	
25000200	SEEDING, CLASS 2	ACRE	3.0		1.0						2.0	
25000312	SEEDING, CLASS 4A	ACRE	2.5		0.83						1.67	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	270		90						180	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	270		90						180	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	270		90						180	
25100630	EROSION CONTROL BLANKET	SQ YD	13,750		4,583						9,167	
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	12,000		4,000						8,000	
25200100	SODDING	SQ YD	435		145						290	
25200200	SUPPLEMENTAL WATERING	UNIT	4.5		1.5						3	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	800.0		266.7						533.3	
28000400	PERIMETER EROSION BARRIER	FOOT	7,611	5,100	2,511							
28000510	INLET FILTERS	EACH	17	11	6							
28100101	STONE RIPRAP, CLASS A1	SQ YD	163	109	54							
28200200	FILTER FABRIC	SQ YD	163	109	54							
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	1,906	1,277	629							
40200900	AGGREGATE SURFACE COURSE, TYPE B	CU YD	93	93								
40600200	BITUMINOUS MATERIALS, PRIME COAT	TON	3.8	1.9	1.9							
40600300	AGGREGATE (PRIME COAT)	TON	3.8	1.9	1.9							
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	301	202	99							
42001300	PROTECTIVE COAT	SQ YD	250	167	83							
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	22		22							
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1591.0	1,061	530							
42400800	DETECTABLE WARNINGS	SQ FT	20.0	13.3	6.7							

* SPECIALTY ITEMS

FILE NAME = M:\756-204_Lombard - DWI Bridges Phase II\CADD Sheets\01756204-sh-500.dgn

Bollinger, Lach & Associates, Inc.
ITASCA, ILLINOIS

USER NAME = gonzalo	DESIGNED - BD	REVISED - 9-12-11
PLOT SCALE = 20.0000' / IN.	DRAWN - DC	REVISED -
PLOT DATE = 9/13/2011	CHECKED - BD	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
GREAT WESTERN TRAIL**

**GREAT WESTERN TRAIL BIKE PATH
SUMMARY OF QUANTITIES**

SCALE: NONE SHEET NO. SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	06-00151-00-BR		201	3
CONTRACT NO. 63568			ILLINOIS FED. AID PROJECT	