SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	GREAT WESTERN TRAIL								
				75% FED 25% LOCAL	75% FED 25% GCPF	75% FED 25% LOCAL	75% FED 25% LOCAL	75% FED 25% GCPF	75% FED 25% GCPF	75% FED 25% GCPF	75% FED 25% LOCAL	75% FED 25% LOCAL
				BIKE PATH	BIKE PATH	BRIDGE, NEW CONSTRUCTION SN 022-3120	BRIDGE, NEW CONSTRUCTION SN 022-3121	BRIDGE, NEW CONSTRUCTION SN 022-3121	BRIDGE, NEW CONSTRUCTION SN 022-3122	RETAINING WALL SN 022-3123	LANDSCAPING	LIGHTING
				0028	0028	0008	0008	0008	0008	0040	0031	0021
44000100	PAVEMENT REMOVAL	SQ YD	377	252.6	124.4							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	90	60	30							
44000600	SIDEWALK REMOVAL	SQ FT	780	520	260							
48101500	AGGREGATE SHOULDERS, TYPE B, 6"	SQ YD	660	400	260							
50157300	PROTECTIVE SHIELD	SQ YD	172						172			
50200100	STRUCTURE EXCAVATION	CU YD	3,470			510		754	1945	261		
50300225	CONCRETE STRUCTURES	CU YD	132.0			21.0	50.1		60.9			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	304.7			59.3	88.3		157.1			
50300300	PROTECTIVE COAT	SQ YD	743			154	226		363			
50400745	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS, 72"	FOOT	415.5						415.5			
50401005	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 48"	FOOT	782.0			389.0	393.0					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	78,910			16,040	23,560		39,310			
50800515	BAR SPLICERS	EACH	76				34		42			
* 50901730	BRIDGE FENCE RAILING	FOOT	283.9						283.9			
* 50901750	PARAPET RAILING	FOOT	667.1			197	280.8		189.3			
51201610	FURNISHING STEEL PILES HP12X63	FOOT	1,400				462		938			
51202305	DRIVING PILES	FOOT	1,400				462		938			
51203610	TEST PILE STEEL HP12X63	EACH	4.0				2		2			
51204650	PILES SHOES	EACH	24				8		16			
51500100	NAME PLATES	EACH	6			2	2		2			
52000110	PREFORMED JOINT STRIP SEAL	FOOT	40.0						40.0			
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	3						3			
52100400	STEEL BEARING ASSEMBLY	EACH	3						3			
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	7	4	3							
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	349	233	116							
55100500	STORM SEWER REMOVAL 12"	FOOT	33	24.6	8.4							
58700300	CONCRETE SEALER	SQ FT	580						580			
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	30				30					
△1 60200305	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 3 FRAME, AND GRATE	EACH	1	1								
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	4	3	1							
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	5	3	2							
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	2	1	1							
60500050	REMOVING CATCH BASINS	EACH	1	1								

* SPECIALTY ITEMS

FILE NAME = W:\756-004_Lombard - GWT Bridges Phase II\CADD Sheets\01756004-sht-SQ0.dgn

Bollinger, Lach & Associates, Inc.
ITASCA, ILLINOIS

USER NAME = gonzalo	DESIGNED - BD	REVISED - △1 9-12-11
	DRAWN - DC	REVISED -
PLOT SCALE = 20.0000 ' / IN.	CHECKED - BD	REVISED -
PLOT DATE = 9/13/2011	DATE -	REVISED -

STATE OF ILLINOIS
GREAT WESTERN TRAIL

GREAT WESTERN TRAIL BIKE PATH
SUMMARY OF QUANTITIES

SCALE: NONE | SHEET NO. | SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	06-00151-00-BR	DuPAGE	201	4
		CONTRACT NO. 63568		
	ILLINOIS	FED. AID PROJECT		