SUMMARY OF QUANTITIES

	CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY 90% FED 10% COUNTY	CONSTRUCTION TYPE CODE 0003 QUANTITY	CONSTRUCTION TYPE CODE 0021 QUANTITY
†	X5539700	STORM SEWERS TO BE CLEANED	FOOT	120	120	-
†*	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	-
†*	X7810300	RECESSED REFLECTIVE PAVEMENT MARKER	EACH	227	227	-
†*	X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	1117	-	1117
†*	X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	373	-	373
†*	XX003338	TEST HOLE	EACH	4	4	-
†*	XX006926	ILLUMINATED STREET NAME SIGN	EACH	4	-	4
†	Z0001056	AGGREGATE SUBGRADE 16"	SQ YD	1256	1256	-
†	Z0004510	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3"	SQ YD	56.8	56.8	-
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	-
†	Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	5	5	-
†	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	20	20	-
†	Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	1	1	-
†*	Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1	-	1
†*	Z0033056	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1	-	1
†*	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	52	52	-
†	Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	146	146	-
†	Z0064560	SEGMENTAL BLOCK RETAINING WALL	SQ FT	175	175	-
†△	Z0076600	TRAINEES	HOUR	500	500	-
	XX008551	TEMPORARY STONE	TON	20	20	-

† SPECIAL PROVISION
* SPECIALTY ITEM
△ 0042

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY 90% FED 10% COUNTY	CONSTRUCTION TYPE CODE 0003 QUANTITY	CONSTRUCTION TYPE CODE 0021 QUANTITY

200 22ND Street, Suite 216, Lombard, IL 60148
630.705.0110 voice, 630.839.2566 fax
www.mps-il.com
MILLENNIA PROFESSIONAL SERVICES

DESIGNED	CJD	REVISED	-
DRAWN	CJD	REVISED	-
CHECKED	TVN	REVISED	-
DATE	8/16/2011	REVISED	-

DUPAGE COUNTY DEPARTMENT OF TRANSPORTATION

ROSELLE RD. & WALNUT ST.
INTERSECTION IMPROVEMENTS

SCALE: N/A | SHEET NO. 3 OF 3 SHEETS | STA. | TO STA.

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
364	07-00184-12-CH	DUPAGE	49	6

CONTRACT NO. 63611

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

FILE NAME = P:\2010\ME10015_Roselle_DPCDOT\CADD\Shts\04-SOQ-sht-Roselle.dgn
PLOT SCALE = 1.0000 ' / IN.
USER NAME = Millennia Professional Services

P:\2010\ME10015_Roselle_DPCDOT\CADD\Shts\04-SOQ-sht-Roselle.dgn