

INDEX OF SHEETS

1	COVER SHEET
2	INDEX OF SHEETS & GENERAL NOTES
3	SUMMARY OF QUANTITIES
4-5	TYPICAL SECTIONS
6-8	SCHEDULE OF QUANTITIES
9-10	PLAN AND PROFILE
11	STAGE CONSTRUCTION AND BARRIER LAYOUT
12-13	SOIL EROSION AND SEDIMENT CONTROL PLAN
14	GENERAL PLAN AND ELEVATION
15	CONSTRUCTION STAGING AND TEMPORARY SHEET PILING LAYOUT
16	TEMPORARY CONCRETE BARRIER FOR STAGE CONSTRUCTION
17	RIPRAP AND PILE LAYOUT
18	TOP OF SLAB ELEVATIONS
19	TOP OF WEST APPROACH SLAB ELEVATIONS
20	TOP OF EAST APPROACH SLAB ELEVATIONS
21	SUPERSTRUCTURE
22	SUPERSTRUCTURE DETAILS
23	FRAMING PLAN AND DIAPHRAGM DETAILS
24-25	WEST & EAST BRIDGE APPROACH SLAB DETAILS
26	48" PCC I-BEAM
27	48" PCC I-BEAM DETAILS
28	WEST ABUTMENT DETAILS
29	EAST ABUTMENT DETAILS
30	BAR SPLICER ASSEMBLY AND MECHANICAL SPLICER DETAILS
31	METAL SHELL PILE DETAILS
32	BORING LOGS
33-40	CROSS SECTIONS - STAGE 1 CONSTRUCTION
41-48	CROSS SECTIONS - STAGE 2 CONSTRUCTION
49-56	CROSS SECTIONS - FINAL STAGE CONSTRUCTION
57	DISTRICT ONE DETAIL - RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)
58	DISTRICT ONE DETAIL - TYPICAL PAVEMENT MARKINGS

GENERAL NOTES

EXISTING STRUCTURES (INCLUDING FOUNDATIONS, WALLS, CISTERNS, WELLS, OR OTHER UNDERGROUND STRUCTURES) WITHIN THE RIGHT OF WAY SHALL BE REMOVED IN ACCORDANCE WITH ARTICLE 501.04 AND 501.05 OF THE STANDARD SPECIFICATIONS, WITHOUT ADDITIONAL COMPENSATION, UNLESS OTHERWISE NOTED IN THE PLANS OR SPECIAL PROVISIONS.

EXISTING STREET SIGNS AND TRAFFIC SIGNS THAT ARE WITHIN THE CONSTRUCTION LIMITS SHALL BE REMOVED AND RESET BY THE CONTRACTOR IN ACCORDANCE WITH ARTICLE 107.25.

WHERE THE PROPOSED CONSTRUCTION MEETS AN EXISTING BITUMINOUS OR CONCRETE SURFACE, OR WHERE SAWING IS STATED ON THE PLANS, THE EXISTING SURFACE SHALL BE SAWED IN A NEAT, STRAIGHT LINE. COST OF SAWING IS TO BE INCLUDED IN THE UNIT BID PRICES OF THE CONTRACT.

ALL TREES LESS THAN 6" DIAMETER WITHIN THE CONSTRUCTION LINES AND SHOWN ON THE PLANS TO BE REMOVED WILL NOT BE PAID FOR UNDER THE BID ITEM OF "TREE REMOVAL". THE COST OF REMOVING THESE TREES SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE BID PER CUBIC YARD FOR EARTH EXCAVATION.

NO OVERHAUL HAS BEEN COMPUTED AND NONE SHALL BE PAID FOR FROM ANY SOURCE.

ANY TEMPORARY SEEDING THAT IS DIRECTED BY THE ENGINEER SHALL BE PAID AS TEMPORARY EROSION CONTROL SEEDING.

BITUMINOUS MATERIALS (PRIME COAT) SHALL BE RC-70 OR SS-1 ON BITUMINOUS AND MC-30 OR P.E.P. ON AGGREGATE AND SHALL BE APPLIED AT THE RATE OF 0.10-0.40 GALLONS PER SQUARE YARD, OR AS DIRECTED BY THE ENGINEER.

ALL PAVEMENT SHALL BE CLEANED AND "FRESH OIL" SIGNS SHALL BE PLACED AT ALL INTERSECTIONS OF THE STREETS PRIOR TO APPLYING BITUMINOUS MATERIALS (PRIME COAT).

AGGREGATE (PRIME COAT) SHALL BE APPLIED AT THE RATE OF 6 POUNDS PER SQUARE YARD OR AS DIRECTED BY THE ENGINEER.

THE FINAL TOP FOUR INCHES OF SOIL IN ANY RIGHT-OF-WAY AREA DISTURBED BY THE CONTRACTOR MUST BE A COHESIVE SOIL CAPABLE OF SUPPORTING VEGETATION.

ALL DISTURBED GROUND WITHIN THE COUNTY RIGHT-OF-WAY SHALL BE RE-SEEDED (CLASS 2A & 4), FERTILIZED, AND EXCELSIOR BLANKET INSTALLED TO THE SATISFACTION OF THE ENGINEER.

VERTICAL HEADWALLS, DECORATIVE SIGNING, PLANTINGS, SHRUBBERY, AND TREES ARE PROHIBITED INSIDE THE COUNTY RIGHT-OF-WAY.

THE CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF ALL FIELD TILES, UNDERGROUND AND SURFACE UTILITIES AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS, EVEN THOUGH THEY MAY NOT BE SHOWN IN THE PLANS. ANY FIELD TILE THAT IS DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED IN ACCORDANCE WITH SECTION 611 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION. THIS WORK SHALL BE CONSIDERED AS INCLUDED IN THE UNIT BID PRICES OF THE CONTRACT, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED. ANY UTILITY PROPERTY DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED OR REPLACED TO THE SATISFACTION OF THE OWNER AT THE CONTRACTOR'S EXPENSE.

ALL CONSTRUCTION TO BE ACCORDING TO IDOT DESIGN AND STANDARD SPECIFICATIONS, MUST ADHERE TO THE WILL COUNTY DEPARTMENT OF HIGHWAYS PERMIT REGULATIONS AND ACCESS CONTROL REGULATIONS, AND SHALL FOLLOW THE LATEST WILL COUNTY STORM WATER MANAGEMENT ORDINANCE AND WILL COUNTY WATER RESOURCE ORDINANCE AT ALL TIMES.

A PROOF ROLL OF THE SUBGRADE IS REQUIRED PRIOR TO PLACING THE AGGREGATE SUB-BASE AND MUST BE OBSERVED BY A CERTIFIED TESTING COMPANY. NOTIFY THE ENGINEER PRIOR TO DOING THE PROOF ROLL.

RECORD DRAWINGS SHALL BE PREPARED IN ACCORDANCE WITH WCDH REQUIREMENTS AND SHALL BE SUBMITTED IN ELECTRONIC FORMAT.

THE WILL COUNTY DEPARTMENT OF HIGHWAYS MUST BE NOTIFIED A MINIMUM OF TWO (2) WORKING DAYS IN ADVANCE OF ANY NON-EMERGENCY CONSTRUCTION WITHIN THE RIGHT-OF-WAY.

GENERAL NOTES (CONT.)

THE LOCATION AND ELEVATION OF THE UNDERGROUND UTILITIES AS SHOWN ON THE PLANS ARE NOT TO BE TAKEN AS EXACT. THE CONTRACTOR SHALL USE SPECIAL CARE WHEN CONDUCTING CONSTRUCTION OPERATIONS NEAR THEM TO PREVENT DAMAGE.

THE CONTRACTOR SHALL NOTIFY THE RESPECTIVE UTILITIES TO MAKE THE NECESSARY ADJUSTMENTS PRIOR TO THIS CONSTRUCTION.

THE CONTRACTOR SHALL CONTACT THE BEECHER PUBLIC WORKS DEPARTMENT IN ORDER TO HAVE THE EXISTING WATERMAIN SHUT-OFF PRIOR TO EXCAVATION OF THE STREAMBED AND SLOPES OVER THE EXISTING 10" WATERMAIN. THE CONTRACTOR SHALL PROCEED WITH CAUTION WHILE EXCAVATING IN THIS LOCATION AND NOTIFY THE PUBLIC WORKS DEPARTMENT IMMEDIATELY IF THE WATERMAIN IS EXPOSED DURING CONSTRUCTION.

THE UTILITIES LOCATED WITHIN THE PROJECT LIMITS OR IMMEDIATELY ADJACENT TO THE PROJECT CONSTRUCTION LIMITS INCLUDE:

COMED 1910 S. BRIGGS STREET JOLIET, IL 60433 T: 630-437-3313 ATTN: CRAIG WEBER	AT&T DISTRIBUTION 1000 COMMERCE DRIVE OAK BROOK, IL 60523 T: 630-573-6447 E: mc1365@att.com
--	---

BEECHER PUBLIC WORKS DEPARTMENT
724 PENFIELD STREET
PO BOX 1154
BEECHER, IL 60401
T: 708-946-2261
F: 708-946-3764
ATTN: BUD COWGER
D: 708-946-3636

A REGIONAL 404 PERMIT HAS BEEN ISSUED FOR THIS PROJECT AND THE CONDITIONS OF THAT PERMIT MUST BE ADHERED TO.

WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKERS, MONUMENTS, AND RIGHT OF WAY PINS UNTIL THE OWNER, AN AUTHORIZED SURVEYOR, OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION.

ALL COUNTY ROW MONUMENTATION (BOUNDARY CORNERS) SHALL BE ACCORDING TO ARTICLE 1.7.13 OF THE PERMIT REGULATIONS UTILIZING THE "WCDH MONUMENTATION STANDARD".

ALL CONSTRUCTION MATERIALS WITHIN THE COUNTY ROW MUST BE IDOT CERTIFIED. DOCUMENTATION OF MATERIAL CERTIFICATION SHALL BE SUBMITTED PRIOR TO ENGINEER APPROVAL. ALL CONSTRUCTION MATERIAL NEEDING INSPECTION SHALL BE DONE ACCORDING TO THE LATEST IDOT PROJECT AND PROCEDURES GUIDE.

THE CONTRACTOR SHALL PROVIDE THE ENGINEER A LIST OF MATERIALS USED AND IDENTIFY THEIR ASSOCIATED IDOT CERTIFICATION, SHALL PROVIDE THE ENGINEER WITH A COPY OF ALL MATERIAL TESTING COMPANY RESULTS, SHALL SIGN AND PROVIDE THE ENGINEER ON A WEEKLY BASIS WEEKLY FIELD REPORTS UTILIZING THE APPROPRIATE IDOT FORM, SHALL SUBMIT TO THE ENGINEER A CERTIFICATION LETTER THAT CERTIFIES COMPLIANCE WITH THE PLANS AND SPECIFICATIONS.

FILE = S:\Struct-1033004-Indiana Avenue.Design\1033004\Cover.dgn

CONTRACT NO. 63617

REVISION	DATE	BY	REMARKS	DRAWN	CHECKED	APPROVED	ILLINOIS DEPARTMENT OF TRANSPORTATION BRIDGE REPLACEMENT INDIANA AVENUE (CH 24) OVER TRIM CREEK	WILLET HOFMANN & ASSOCIATES INC. ENGINEERING ARCHITECTURE LAND SURVEYING 809 EAST 2ND STREET, DIXON, IL 61021-0367 T: 815-784-3381 DESIGN FIRM #184-000918	WILL COUNTY	INDEX OF SHEETS & GENERAL NOTES STRUCTURE NO. 099-3378	SECTION 01-00042-07-BR STA. 47+00	COUNTY WILL STA. 53+50	TOTAL SHEETS 58	SHEET NO. 02
				L.G.N.	G.F.S.	B.K.C.					WHA #:	DATE: 6/9/2011		