

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE
CODE NUMBER	PAY ITEMS	UNITS	TOTAL QUANTITY	001*
* 81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	850	850
* 81101000	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., GALVANIZED STEEL	FOOT	1730	1730
* 81101100	CONDUIT ATTACHED TO STRUCTURE, 5" DIA., GALVANIZED STEEL	FOOT	1385	1385
* 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	1680	1680
* 81400100	HANDHOLE	EACH	9	9
* 81400200	HEAVY-DUTY HANDHOLE	EACH	7	7
* 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	1085	1085
* 81702150	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	4660	4660
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2205	2205
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2	2
* 89502380	REMOVE EXISTING HANDHOLE	EACH	3	3
* X6120170	INSTALL WATER SERVICE COMPLETE	EACH	1	1
X0325862	CONCRETE BRIDGE RAILING	FOOT	718	718
* X0326654	ORNAMENTAL LIGHT UNIT, COMPLETE	EACH	14	14
* X0323927	MAINTENANCE OF LIGHTING SYSTEMS	EACH	2	2
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	637	637
X4230800	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH, SPECIAL	SQ YD	75	75
X4240440	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH, SPECIAL	SQ FT	1300	1300
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	1447	1447
* X5090810	PEDESTRIAN RAIL (SPECIAL)	FOOT	4	4
* X5610712	WATER MAIN REMOVAL, 12"	FOOT	135	135
* XX008501	BARE COPPER WIRE, NO. 2/0	FOOT	660	660
* X6022820	MANHOLES, SANITARY, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2
* X6026056	SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	5	5
X6030205	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	5	5
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	6255	6255
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	1520	1520
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0018002	DRAINAGE SCUPPER, DS11	EACH	3	3
Z0021904	SILICONE JOINT SEALER, 1"	FOOT	301	301
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	1500	1500
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	150	150
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	302	302
* Z0056800	SANITARY SEWER 6"	FOOT	75	75
* Z0056900	SANITARY SEWER 8"	FOOT	105	105
* Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	2	2
Δ Z0076600	TRAINEES	HOURLY	1500	

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE
CODE NUMBER	PAY ITEMS	UNITS	TOTAL QUANTITY	001*
XX008570	FURNISHING AND ERECTING PRECAST CONCRETE PANELS, STRUCTURE 1	L SUM	1	1
XX008571	FURNISHING AND ERECTING PRECAST CONCRETE PANELS, STRUCTURE 2	L SUM	1	1
XX008572	WATER MAIN ATTACHED TO STRUCTURE 12"	FOOT	340	340
* XX008573	12" VALVES IN VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2
* XX008574	LINE STOP VALVES 12" IN VALVE VAULTS, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1

\*SPECIALTY ITEM  
ΔCONSTRUCTION CODE 0042

HRGREEN  
PROJECT CONTACT: Michael G. Harding  
CLIENT: City of Aurora  
DATE PLOTTED: 8/26/11 10:58:41 AM  
FILE NAME: 86090472-Soc.dgn  
PLOT DRIVER: pdfplot  
PEN TABLE: Struct 20x34.tbl



USER NAME = whoad  
FILE NAME = 86090472-Soc.dgn  
PLOT SCALE =  
PLOT DATE = 7/26/2011

DESIGNED - JPG  
DRAWN - WJH  
CHECKED - MGH  
DATE - 7/26/11

REVISED -  
REVISED -  
REVISED -  
REVISED -

CITY OF AURORA

SUMMARY OF QUANTITIES  
DOWNER PLACE

SCALE: SHEET NO. 2 OF 2 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	07-00264-00-BR	KANE	164	5
CONTRACT NO. 63620			FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT	