

33. RIGHT-OF-WAY MARKERS WILL BE ERECTED WITH THE BACK FACE OF THE MARKER ON THE RIGHT-OF-WAY LINE UNLESS THE NEW RIGHT-OF-WAY LINE HAS BEEN SURVEYED AND PINNED, IN WHICH INSTANCE THE RIGHT-OF-WAY MARKERS WILL BE ERECTED 300 MM (12 INCHES) INSIDE THE NEW RIGHT-OF-WAY LINE.

34. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY DURING CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED FOR NON-EMERGENCY WORK. THE JULIE NUMBER IS 800-892-0123. THE FOLLOWING LISTED UTILITIES LOCATED WITHIN THE PROJECT LIMITS OR IMMEDIATELY ADJACENT TO THE PROJECT CONSTRUCTION LIMITS ARE MEMBERS OF JULIE:

NAME AND ADDRESS OF UTILITY	TYPE
AT&T COMMUNICATIONS, INC. MR. CARL DONAHUE 866 ROCK CREEK ROAD PLANO, IL 60545 (630)-552-4677	TELEPHONE
COMMONWEALTH EDISON COMPANY MR. MICHAEL LENOX 123 ENERGY AVE. ROCKFORD, IL 61109 (815)-490-2869	ELECTRIC
NICOR GAS CO. MS. CONSTANCE LANE 1844 FERRY ROAD NAPERVILLE, IL 60563-9600 (630)-983-8676	GAS
FRONTIER/CITIZENS MR. DAVID DAY 684 N. BROAD/P.O. BOX 12 LANARK, IL 61046	TELEPHONE

35. THE APPLICABLE PORTIONS OF ARTICLE 105.07 OF THE STANDARD SPECIFICATION SHALL APPLY EXCEPT FOR THE FOLLOWING: THE CONTRACTOR SHALL BE RESPONSIBLE TO LOCATE THE VERTICAL DEPTHS OF THE UNDERGROUND UTILITIES WHICH MAY INTERFERE WITH CONSTRUCTION OPERATIONS. THIS WORK WILL NOT BE MEASURED OR PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED AS INCLUDED IN THE UNIT BID PRICE FOR THE ITEM OF CONSTRUCTION INVOLVED. PER SB 699 (90 DAY UTILITY RELOCATION LAW), ONCE RIGHT-OF-WAY IS CLEAR TO AWARD THE PROJECT, A NOTICE WILL BE SENT TO THE UTILITY COMPANIES INSTRUCTING THEM TO HAVE THEIR FACILITIES RELOCATED WITHIN 90 DAYS. ESTIMATED DATE RELOCATION COMPLETE = AWARD DATE + 100 DAYS.

36. CADD DATA WILL BE AVAILABLE TO CONTRACTORS AND CONSULTANTS WORKING ON THIS PROJECT. THIS INFORMATION WILL BE PROVIDED UPON REQUEST AS MICROSTATION CADD FILES AND GEOPAK COORDINATE GEOMETRY FILES ONLY. IF DATA IS REQUIRED IN OTHER FORMATS IT WILL BE YOUR RESPONSIBILITY TO MAKE THESE CONVERSIONS. IF ANY DISCREPANCY OR INCONSISTENCY ARISES BETWEEN THE ELECTRONIC DATA AND THE INFORMATION ON THE HARD COPY, THE INFORMATION ON THE HARD COPY SHOULD BE USED. CONTACT THE DISTRICT'S PROJECT ENGINEER TO REQUEST THESE FILES.

37. TEMPORARY IMPACT ATTENUATORS THAT HAVE BEEN FURNISHED AND PLACED COULD BE RELOCATED ON THE SAME PROJECT. THE ATTENUATORS RELOCATED, FROM ONE STAGE TO ANOTHER, FROM THE PROJECT TO AN OFFSITE LOCATION, OR FROM THE OFFSITE LOCATION BACK TO THE PROJECT, WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER EACH FOR IMPACT ATTENUATORS RELOCATE OF THE PARTICULAR TYPE SPECIFIED.


38. TEMPORARY CONCRETE BARRIER THAT HAS BEEN FURNISHED AND PLACED COULD BE RELOCATED ON THE SAME PROJECT. THE TEMPORARY CONCRETE BARRIER RELOCATED, FROM ONE STAGE TO ANOTHER, FROM THE PROJECT TO AN OFFSITE LOCATION, OR FROM THE OFFSITE LOCATION BACK TO THE PROJECT, WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER FOOT FOR RELOCATE TEMPORARY CONCRETE BARRIER.

39. THE CONTRACTOR SHALL BEGIN FENCE ERECTION AS SOON AS CLEARING OPERATIONS PERMIT. BEFORE REMOVING EXISTING FENCE FROM AN AREA THAT CONTAINS LIVESTOCK, THE CONTRACTOR SHALL ERECT, ALONG THE PROPOSED RIGHT OF WAY LINES, A TEMPORARY FENCE OR WIRE MEETING THE APPROVAL OF THE ENGINEER. THE CONTRACTOR SHALL CONCENTRATE HIS PERMANENT FENCING OPERATIONS AT THESE LOCATIONS AND AT OTHER SPECIFIED LOCATIONS AS DIRECTED BY THE ENGINEER. THE COST OF ARRANGING WORK AS HEREIN SPECIFIED AND ERECTING ANY TEMPORARY FENCING WILL NOT BE PAID FOR AS A SEPARATE ITEM BUT SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE PER METER (FOOT) FOR WOVEN WIRE FENCE AND/OR CHAIN LINK FENCE.

40. THE CONTRACTOR SHALL CONTACT IDOT DISTRICT 2 MAINTENANCE FIELD ENGINEER MS. TRISHA THOMPSON (815 284 5408) PRIOR TO REMOVING THE GUARDRAIL ON ANY SECTION OF THE PROJECT.

41. REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (500 CUBIC YARDS) HAS BEEN PROVIDED IN THE CONTRACT. THE ACTUAL NEED FOR THIS WORK SHALL BE DETERMINED IN THE FIELD BY THE ENGINEER.

FILE NAME = s:\j\6300--6399\6346\027\microra\sh\sh-gennot.e2.dgn



1170 SOUTH HOUBOLT ROAD JOLIET, ILLINOIS 60431 (815) 744-4200	USER NAME = brianf	DESIGNED -	REVISED -
	PLOT SCALE = 28,0000 ' / IN.	DRAWN -	REVISED -
	PLOT DATE = 7/19/2011	CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

GENERAL NOTES

SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
585	128 BR	HENRY	106	4
CONTRACT NO. 64C20				
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT				