

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROCK ISLAND COUNTY	ROCK ISLAND COUNTY	MERCER COUNTY	ROCK ISLAND COUNTY	ROCK ISLAND COUNTY
				L2AED	L2AED	L2AED	07C0D	07P0D
				80% FED 20% STATE 0040	80% FED 20% STATE 0005	80% FED 20% STATE 0005	50% STATE 50% VILLAGE 0005	100% VILLAGE 0005
40600525	LEVELING BINDER (HAND METHOD), N50	TON	35		34	1		
40600895	CONSTRUCTING TEST STRIP	EACH	1		1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2,606		2,455	151		
40600990	TEMPORARY RAMP	SQ YD	353		322	31		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	10,478		9,772	612	43	51
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	1,188		1,116	72		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	3,056		1,943		513	600
44000400	GUTTER REMOVAL	FOOT	1,989	1,989				
44201383	CLASS C PATCHES, TYPE IV, 12 INCH	SQ YD	1,201	1,201				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1,867		1,867			
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	14,686		14,686			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	39,220		36,715	2,505		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	3,493		3,214	279		
48203020	HOT-MIX ASPHALT SHOULDER, 5-3/4"	SQ YD	6,400		6,400			
50100300	REMOVAL OF EXISTING STRUCTURES NO.1	EACH	1	1				
50100400	REMOVAL OF EXISTING STRUCTURES NO.2	EACH	1	1				
50100500	REMOVAL OF EXISTING STRUCTURES NO.3	EACH	1	1				
50100600	REMOVAL OF EXISTING STRUCTURES NO.4	EACH	1	1				
50100700	REMOVAL OF EXISTING STRUCTURES NO.5	EACH	1	1				
50100800	REMOVAL OF EXISTING STRUCTURES NO.6	EACH	1	1				
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1				
51500100	NAME PLATES	EACH	5	5				

* SPECIALTY ITEMS

* 221,213 & 220
** ROCK ISLAND & MERCER COUNTY

FILE NAME =	USER NAME = cushmanbw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cr\pwwork\pwwork\dot\cushmanbw\d0184077\02	2307-sht-schedule.dgn	DRAWN -	REVISED -			*	(19,20)RS-2	**	231	3	
	PLOT SCALE = 50.0000' / 1in.	CHECKED -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.	CONTRACT NO. 64D72	
	PLOT DATE = Mon Jun 27 13:33:22 2011	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					