

# SCHEDULE OF QUANTITIES

78001110

**PAINT PAVEMENT MARKING - LINE 4"**

**LOCATION**

**Mercer County**

LOCATION	FOOT	COMMENTS
STA 983+72 TO 991+61 Yellow	(2 Apl.) 394.50	Skip Dash Center
STA 991+61 TO 1000+93 Yellow	(2 Apl.) 2,330.00	Solid RT, Skip Dash LT
STA 00+00 TO 7+85 Yellow	(2 Apl.) 3,140.00	Double Solid
190th Ave West Yellow	(2 Apl.) 40.00	2 Skip Dashes
<b>TOTAL YELLOW:</b>	<b>5,904.50</b>	

STA 983+72 TO 1000+93 White	(2 Apl.) 6,884.00	LT & RT Edge Lines
STA 00+00 TO 3+57 White	(2 Apl.) 1,428.00	LT & RT Edge Lines
STA 3+57 TO 4+77 White	(2 Apl.) 240.00	RT Edge Line - 190th Ave West
STA 4+77 TO 7+85 White	(2 Apl.) 1,232.00	LT & RT Edge Lines
190th Ave West White	(2 Apl.) 400.00	LT & RT Edge Lines
<b>TOTAL WHITE:</b>	<b>10,184.00</b>	

MERCER CO YELLOW AND WHITE GRAND TOTAL: 16,088.50

**Rock Island County**

STA 7+85 TO 30+38 Yellow	(2 Apl.) 9,012.00	Double Solid
STA 30+38 TO 41+28 Yellow	(2 Apl.) 2,725.00	Skip Dash RT, Solid LT
STA 41+28 TO 52+27 Yellow	(2 Apl.) 549.50	Skip Dash Center
STA 52+27 TO 64+21 Yellow	(2 Apl.) 2,985.00	Solid RT, Skip Dash LT
STA 64+21 TO 111+12 Yellow	(2 Apl.) 18,764.00	Double Solid
STA 111+12 TO 121+68 Yellow	(2 Apl.) 2,640.00	Skip Dash RT, Solid LT
STA 121+68 TO 123+31 Yellow	(2 Apl.) 81.50	Skip Dash Center
STA 123+31 TO 130+66 Yellow	(2 Apl.) 1,837.50	Solid RT, Skip Dash LT
STA 130+66 TO 198+40 Yellow	(2 Apl.) 27,096.00	Double Solid
STA 198+40 TO 207+87 Yellow	(2 Apl.) 2,367.50	Skip Dash RT, Solid LT
STA 207+87 TO 212+41 Yellow	(2 Apl.) 227.00	Skip Dash Center
STA 212+41 TO 223+81 Yellow	(2 Apl.) 2,850.00	Solid RT, Skip Dash LT
STA 223+81 TO 241+11 Yellow	(2 Apl.) 6,920.00	Double Solid
STA 241+11 TO 250+77 Yellow	(2 Apl.) 2,415.00	Skip Dash RT, Solid LT
STA 250+77 TO 253+21 Yellow	(2 Apl.) 122.00	Skip Dash Center
STA 253+21 TO 261+76 Yellow	(2 Apl.) 2,137.50	Solid RT, Skip Dash LT
STA 261+76 TO 321+03 Yellow	(2 Apl.) 23,708.00	Double Solid
STA 321+03 TO 329+51 Yellow	(2 Apl.) 2,120.00	Solid RT, Skip Dash LT
STA 329+51 TO 331+80 Yellow	(2 Apl.) 916.00	Double Solid
STA 331+80 TO 341+92 Yellow	(2 Apl.) 2,530.00	Skip Dash RT, Solid LT
STA 341+92 TO 347+00 Yellow	(2 Apl.) 254.00	Skip Dash Center
STA 347+00 TO 355+82 Yellow	(2 Apl.) 2,205.00	Solid RT, Skip Dash LT
STA 355+82 TO 358+77 Yellow	(2 Apl.) 1,180.00	Double Solid
STA 358+77 TO 369+50 Yellow	(2 Apl.) 2,682.50	Skip Dash RT, Solid LT
STA 369+50 TO 370+79 Yellow	(2 Apl.) 64.50	Skip Dash Center
STA 370+79 TO 375+00 Yellow	(2 Apl.) 1,052.50	Solid RT, Skip Dash LT
105th St West Yellow	(2 Apl.) 40.00	2 Skip Dashes
176th Ave West Yellow	(2 Apl.) 40.00	2 Skip Dashes
<b>TOTAL YELLOW:</b>	<b>119,522.00</b>	

STA 7+85 TO 53+03 White	(2 Apl.) 18,072.00	LT & RT Edge Lines
STA 53+03 TO 54+33 White	(2 Apl.) 260.00	RT Edge Line - 105th St W
STA 54+47 TO 55+00 White	(2 Apl.) 106.00	LT Edge Line - 195th St
STA 55+00 TO 105+51 White	(2 Apl.) 20,204.00	LT & RT Edge Lines
STA 105+51 TO 106+10 White	(2 Apl.) 118.00	LT Edge Line - 205th St
STA 106+10 TO 106+64 White	(2 Apl.) 216.00	LT & RT Edge Lines
STA 106+64 TO 107+37 White	(2 Apl.) 146.00	RT Edge Line - 91st St W
STA 107+37 TO 131+72 White	(2 Apl.) 9,740.00	LT & RT Edge Lines
STA 131+72 TO 132+24 White	(2 Apl.) 104.00	LT Edge Line - 210th St
STA 132+24 TO 133+27 White	(2 Apl.) 412.00	LT & RT Edge Lines
STA 133+27 TO 134+09 White	(2 Apl.) 164.00	RT Edge Line - 84th St W
STA 134+09 TO 148+67 White	(2 Apl.) 5,832.00	LT & RT Edge Lines
STA 148+67 TO 149+54 White	(2 Apl.) 174.00	LT Edge Line - 180th Ave
STA 149+54 TO 157+03 White	(2 Apl.) 2,996.00	LT & RT Edge Lines
STA 157+03 TO 157+76 White	(2 Apl.) 146.00	RT Edge Line - Sunset Blvd
STA 157+76 TO 160+75 White	(2 Apl.) 1,196.00	LT & RT Edge Lines
Skip Through West Blvd		
STA 161+24 TO 168+35 White	(2 Apl.) 2,844.00	LT & RT Edge Lines
Skip Through Madison St		
STA 168+78 TO 176+79 White	(2 Apl.) 3,204.00	LT & RT Edge Lines
STA 176+79 TO 177+37 White	(2 Apl.) 116.00	RT Edge Line - Posey St
STA 177+37 TO 180+60 White	(2 Apl.) 1,292.00	LT & RT Edge Lines
Skip Through Williams St		
STA 181+12 TO 183+16 White	(2 Apl.) 216.00	Parking Lanes LT & RT
STA 181+13 TO 183+50 White	(2 Apl.) 948.00	LT & RT Edge Lines
STA 183+50 TO 184+62 White	(2 Apl.) 224.00	LT Edge Line - Main St
STA 184+62 TO 185+25 White	(2 Apl.) 252.00	LT & RT Edge Lines
STA 185+25 TO 185+60 White	(2 Apl.) 70.00	LT Edge Line - Front St
Skip Through Part of Front St		
STA 185+83 TO 186+16 White	(2 Apl.) 66.00	RT Edge Line - Front St
STA 186+16 TO 207+13 White	(2 Apl.) 8,388.00	LT & RT Edge Lines
STA 207+13 TO 207+75 White	(2 Apl.) 124.00	RT Edge Line - Lloyd St
STA 207+75 TO 210+82 White	(2 Apl.) 1,228.00	LT & RT Edge Lines
STA 210+82 TO 211+23 White	(2 Apl.) 82.00	RT Edge Line - Hartman St
STA 211+23 TO 233+53 White	(2 Apl.) 8,920.00	LT & RT Edge Lines
STA 233+53 TO 234+31 White	(2 Apl.) 156.00	RT Edge Line - 176th Ave W
STA 234+31 TO 234+52 White	(2 Apl.) 84.00	LT & RT Edge Lines
STA 234+52 TO 235+98 White	(2 Apl.) 292.00	LT Edge Line - 176th Ave W
STA 235+98 TO 340+25 White	(2 Apl.) 41,708.00	LT & RT Edge Lines
STA 340+25 TO 340+82 White	(2 Apl.) 228.00	LT Edge Line - Side Road/PE
STA 340+82 TO 375+00 White	(2 Apl.) 13,672.00	LT & RT Edge Lines
105th St West White	(2 Apl.) 330.00	LT & RT Edge Lines
176th Ave West White	(2 Apl.) 374.00	LT & RT Edge Lines
<b>TOTAL WHITE:</b>	<b>144,704.00</b>	

ROCK ISLAND CO YELLOW AND WHITE GRAND TOTAL: 264,226.00

**BOTH COUNTIES YELLOW AND WHITE GRAND TOTAL: 280,314.50**

\* 221,213 & 220  
\*\* ROCK ISLAND & MERCER COUNTY

FILE NAME =	USER NAME = grantpm	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca\pwork\pwork\grantpm\d8184077\02122027-sht-schedule.dgn	DRAWN -	REVISED -	*			(19,20)RS-2	**	231	18	
PLOT SCALE = 50,0000' / 1in.	CHECKED -	REVISED -	CONTRACT NO. 64D72							
PLOT DATE = Thu Jun 23 08:45:47 2011	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
				SCALE:	SHEET NO. OF SHEETS	STA. TO STA.				