

ENTRANCE SCHEDULE

LOCATION				ENT. TYPE	NOTE	SIDE ROAD WIDTH FT	BUTT JOINT AREA SQ FT	TOTAL AGGREGATE AREA SQ FT	TOTAL BITUMINOUS AREA SQ FT	TOTAL AGGREGATE AREA SQ YD	TOTAL BITUMINOUS AREA SQ YD	40600200	40600982	44000158	40600990	35101400	40800050
												BIT PRIME COAT TON	H.M.A. SURF REM - BUTT JOINT SQ YD	HMA SURF REM 2.25" SQ YD	TEMP RAMP SQ YD	AGG BASE CSE TYPE B TON	2.25" INC H.M.A. SURF TON
IL 94 - Mercer County																	
998+90	PE & MB	RT	BIT						545		60.6	0.02					9.3
999+36	PE	RT	AGG	New Driveway			590	540	65.6	60.0	0.02					29.9	9.2
4+37	SR	LT	BIT	190th Ave W	24.0	756		3095		343.9	0.10	84.00		11.11			53.0
SUBTOTAL- Mercer County												0.13	84.00		11.11	29.86	71.52
IL 94 - Rock Island County																	
17+79	FE	RT	AGG	Existing Widened FE			773									39.1	
18+39	FE	RT	AGG	Existing Widened FE			804									40.7	
21+06	PE	RT	BIT	Existing Widened PE			1390	1390		154.4	0.04					70.4	23.8
24+03	FE	LT	AGG	Existing Widened FE			2220									112.4	
24+85	FE	RT	AGG	Existing Widened FE			1289									65.2	
40+86	PE	RT	BIT					420		46.7	0.01						7.2
53+79	SR	LT	BIT	105th St W	29.0	1201		3135		348.3	0.10	133.44		13.43			53.6
54+63	SR & MB	RT	BIT	195th St	15.0	570		1206		134.0	0.04	63.33		6.94			20.6
55+92	PE	LT	BIT					553		61.4	0.02						9.5
90+37	PE	LT	BIT					407		45.2	0.01						7.0
90+37	MB	RT	BIT	New Mailbox Turn Out (6' Wide)							0.06					24.5	
95+12	PE & MB	RT	BIT					645		71.7	0.02						11.0
105+79	SR	RT	BIT	205th St - Road is agg beyond apron				673		74.8	0.02						11.5
107+04	SR	LT	BIT	91st St W	23.0	895		1497		166.3	0.05	99.44		10.65			25.6
131+97	SR	RT	BIT	210th St	14.0	659		659		73.2	0.02	73.22		6.48			11.3
133+66	SR	LT	BIT	84th St W	21.0	1403		1890		210.0	0.06	155.89		9.72			32.3
149+24	SR	RT	BIT	180th Ave	17.0	1525		1525		169.4	0.05	169.44		7.87			26.1
157+41	SR	LT	BIT	Sunset Blvd	23.0	1080		1080		120.0	0.03	120.00		10.65			18.5
160+33	PE	LT	BIT					500		55.6	0.02						8.6
160+95	SR	RT	BIT	West St	22.0	831		831		92.3	0.03	92.33		10.19			14.2
161+09	SR	LT	BIT	West St	25.0	1064		1064		118.2	0.03	118.22		11.57			18.2
163+70	PE	LT	BIT					646		71.8	0.02						11.1
164+42	PE	RT	BIT					522		58.0	0.02						8.9
164+70	PE	LT	BIT					395		43.9	0.01						6.8
165+97	PE	LT	BIT					444		49.3	0.01						7.6
166+69	PE	RT	BIT					390		43.3	0.01						6.7
168+51	SR	RT	BIT	Madison St	21.0	792		792		88.0	0.03	88.00		9.72			13.6
168+57	SR	LT	BIT	Madison St	21.0	969		969		107.7	0.03	107.67		9.72			16.6
170+48	PE	RT	BIT					365		40.6	0.01						6.2
170+92	PE	RT	BIT					460		51.1	0.01						7.9
171+78	PE	LT	BIT					1500		166.7	0.05						25.7
172+53	PE	RT	BIT					454		50.4	0.01						7.8
177+07	SR	LT	BIT	Posey St	22.0	960		960		106.7	0.03	106.67		10.19			16.4
177+07	PE	RT	BIT					474		52.7	0.02						8.1
178+99	Alley	RT	BIT		13.0	458		458		50.9	0.01	50.89		6.02			7.8
180+88	SR	LT	BIT	Williams St	48.0			1241		137.9	0.04		137.89	22.22			21.2
180+88	SR	RT	BIT	Williams St	34.0			1304		144.9	0.04		144.89	15.74			22.3
183+79	SR	RT	BIT	Main St	32.0			5339		593.2	0.17		593.22	14.81			91.4

* 221,213 & 220
** ROCK ISLAND & MERCER COUNTY

FILE NAME =	USER NAME = grantpm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ENTRANCE SCHEDULE	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
est\pwork\pwork\grantpm\d0184077\021207-sht-schedule.dgn		DRAWN -	REVISED -			*	(19,20)RS-2	**	231	21	
PLOT SCALE = 50.0000' / in.		CHECKED -	REVISED -			CONTRACT NO. 64D72					
PLOT DATE = Thu Jun 23 08:45:49 2011		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					