

ENTRANCE SCHEDULE

LOCATION	ENT. TYPE		NOTE	SIDE	BUTT	TOTAL	TOTAL	TOTAL	TOTAL	40600200	40600982	44000158	40600990	35101400	40800050	
				ROAD	JOINT	AGGREGATE	BITUMINOUS	AGGREGATE	BITUMINOUS	BIT	H.M.A. SURF	HMA	TEMP	AGG	2.25" INC	
				WIDTH	AREA	AREA	AREA	AREA	PRIME	REM - BUTT	SURF REM	RAMP	BASE CSE	H.M.A. SURF		
				FT	SQ FT	SQ FT	SQ FT	SQ YD	COAT	JOINT	2.25"	SQ YD	SQ YD	TON	TON	
IL 94 - Rock Island County																
185+50	SR	RT	BIT	Front St	31.0	1314		1314		146.0	0.04	146.00		14.35		22.5
185+92	SR	LT	BIT	Front St	30.0	1060		1060		117.8	0.03	117.78		13.89		18.1
190+00	CE	LT	BIT	U-shaped bitum between Casey's and Garage, plus garage				2876		319.6	0.09					49.2
191+39	Alley & 2 PE's	LT	BIT					1662		184.7	0.05					28.4
192+56	PE	LT	BIT					747		83.0	0.02					12.8
194+03	PE	LT	BIT					432		48.0	0.01					7.4
194+91	PE	LT	BIT					421		46.8	0.01					7.2
195+59	PE	LT	BIT					282		31.3	0.01					4.8
196+47	PE	LT	BIT					339		37.7	0.01					5.8
198+47	PE	LT	BIT					316		35.1	0.01					5.4
198+70	PE	LT	AGG					390		43.3	0.01					6.7
204+70	CE	LT	BIT					544		60.4	0.02					9.3
207+46	SR	LT	BIT	Lloyd St	22.0	928		928		103.1	0.03	103.11		10.19		15.9
211+03	SR	RT	BIT	Hartman St	24.0	777		777		86.3	0.02	86.33		11.11		13.3
228+00	PE & MB	RT	BIT					677		75.2	0.02					11.6
233+91	SR	LT	BIT	176th St W	27.0	1286		1707		189.7	0.05	142.89		12.50		29.2
235+21	SR	RT	BIT	176th St W	30.0	2223		3161		351.2	0.10	247.00		13.89		54.1
243+00	CE	LT	BIT	FS				1123		124.8	0.04					19.2
243+00	MB	RT	BIT					487		54.1	0.02					8.3
245+51	CE	LT	BIT	FS				825		91.7	0.03					14.1
247+50	PE & MB	RT	BIT					777		86.3	0.02					13.3
250+24	PE & MB	RT	BIT					556		61.8	0.02					9.5
259+08	PE	LT	BIT					396		44.0	0.01					6.8
259+33	MB	RT	BIT					411		45.7	0.01					7.0
278+87	PE & MB	RT	BIT					584		64.9	0.02					10.0
280+10	PE	RT	BIT					401		44.6	0.01					6.9
311+97	FE	RT	AGG	Existing Widened FE			1273		141.4					64.4		
313+19	PE	LT	BIT	Existing Widened PE			1301	1301	144.6	144.6	0.04			65.9	22.3	
315+35	FE	RT	AGG	Existing Widened FE			1439		159.9					72.8		
327+79	PE & MB	RT	BIT					641		71.2	0.02					11.0
328+00	PE	LT	BIT					430		47.8	0.01					7.4
328+88	PE	LT	BIT					427		47.4	0.01					7.3
330+17	PE	LT	AGG					856		95.1	0.03					14.6
330+84	PE	RT	BIT					384		42.7	0.01					6.6
332+05	PE & MB	RT	BIT					597		66.3	0.02					10.2
333+52	PE	LT	BIT					384		42.7	0.01					6.6
334+04	PE	RT	BIT					235		26.1	0.01					4.0
340+46	PE	RT	BIT					687		76.3	0.02					11.8
345+03	MB	LT	BIT					472		52.4	0.01					8.1
345+11	PE	LT	BIT					494		54.9	0.02					8.5
365+44	FE	RT	BIT	Existing Widened FE			1713		190.3					86.7		
370+54	PE	RT	BIT					942		104.7	0.03					16.1
371+00	FE	RT	AGG	Existing Widened FE			1423		158.1					72.0		
SUBTOTAL- Rock Island County										2.13	2,221.67	876.00	251.85	714.16	1,116.17	
GRAND TOTALS										2.27	2,305.67	876.00	262.96	744.02	1,187.70	

* 221,213 & 220
** ROCK ISLAND & MERCER COUNTY

FILE NAME =	USER NAME = grantpm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				ENTRANCE SCHEDULE				F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
ci:\pwork\pwork\grantpm\20184077\02122017-sht-schedule.dgn		DRAWN -	REVISED -									*	(19,20)RS-2	**	231	22			
PLOT SCALE = 50.0000' / 1in.		CHECKED -	REVISED -									SCALE: SHEET NO. OF SHEETS STA. TO STA.				ILLINOIS FED. AID PROJECT			
PLOT DATE = Thu Jun 23 08:45:49 2011		DATE -	REVISED -									CONTRACT NO. 64D72							