

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	STP		HSIP									
				URBAN	80% FED/ 20% STATE	90% FED/ 10% STATE	90% FED/ 6.67% STATE/ 3.33% CITY	90% FED/ 5% STATE/ 5% CITY	90% FED/ 5% STATE/ 5% CITY	90% FED/ 10% STATE	90% FED/ 5% STATE/ 5% CITY	90% FED/ 10% STATE	90% FED/ 10% STATE	100% CITY	100% CITY
				ROADWAY 0005	ROADWAY 0005	TRAFFIC SIGNALS SYCAMORE STREET 0021	TRAFFIC SIGNALS PINE STREET 0021	TRAFFIC SIGNALS LOCUST STREET 0021	IL 38 0021	TRAFFIC SIGNALS TAYLOR STREET 0021	TRAFFIC SIGNALS 0021	LIGHTING 0021	LIGHTING 0021	EMERGENCY VEHICLE PREEMPTION 0021	UTILITIES 0043
88102825	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	30	---	---	6	8	8	---	8	---	---	---	---	---
88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	62	---	---	11	10	12	17	12	---	---	---	---	---
88500100	INDUCTIVE LOOP DETECTOR	EACH	28	---	---	3	6	8	---	12	---	---	---	---	---
88600100	DETECTOR LOOP, TYPE I	FOOT	2460	---	---	---	391	496	---	1573	---	---	---	---	---
88700200	LIGHT DETECTOR	EACH	16	---	---	---	---	---	---	---	---	---	---	19	---
88700300	LIGHT DETECTOR AMPLIFIER	EACH	5	---	---	---	---	---	---	---	---	---	---	5	---
88800100	PEDESTRIAN PUSH-BUTTON	EACH	30	---	---	6	8	8	---	8	---	---	---	---	---
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	3	---	---	---	---	---	2	---	1	---	---	---	---
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	23571	---	---	3689	3533	3213	6591	2093	---	---	4452	---	---
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	5	---	---	1	1	1	1	1	---	---	---	---	---
89502380	REMOVE EXISTING HANDHOLE	EACH	8	---	---	---	1	---	3	4	---	---	---	---	---
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	32	---	---	4	8	6	8	6	---	---	---	---	---
X6026056	SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	10	10	---	---	---	---	---	---	---	---	---	---	---
Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1	---	---	---	---	---	---	---	1	---	---	---	---
X4404700	SIDEWALK REMOVAL (SPECIAL)	SQ FT	1559	1559	---	---	---	---	---	---	---	---	---	---	---
X6026054	SANITARY MANHOLES TO BE REMOVED	EACH	1	1	---	---	---	---	---	---	---	---	---	---	---
X8250505	LIGHTING CONTROLLER, SPECIAL	EACH	3	---	---	---	---	---	---	---	---	---	3	---	---
87301900	ELECTRIC CABLE IN CONDUIT/GROUNDING, NO. 6 1C <i>EQUIPMENT CONDUCTOR</i>	FOOT	4927	---	---	459	844	812	986	1064	---	---	762	---	---
X8808118	OPTICALLY PROGRAMMED SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1	---	---	---	---	---	1	---	---	---	---	---	---
X8808120	OPTICALLY PROGRAMMED SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4	---	---	---	---	---	4	---	---	---	---	---	---
X8808121	OPTICALLY PROGRAMMED SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	1	---	---	---	---	---	1	---	---	---	---	---	---
X8860100	LOOP DETECTOR TESTING	EACH	2	---	---	1	---	1	---	---	---	---	---	---	---
Z0033900	MASONRY SIDEWALK	SQ. FT.	2074	2074	---	---	---	---	---	---	---	---	---	---	---
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	---	---	---	---	---	---	---	---	---	---	---
X0327273	RELOCATE EXISTING RAILROAD WAYSIDE HORN	EACH	4	---	---	---	---	---	---	4	---	---	---	---	---
X0327274	RELOCATE EXISTING RAILROAD WAYSIDE HORN CABINET	EACH	4	---	---	---	---	---	---	4	---	---	---	---	---
X0327275	RELOCATE EXISTING DUAL RAILROAD CONFIRMATION SIGNAL	EACH	1	---	---	---	---	---	---	1	---	---	---	---	---
87301270	ELECTRIC CABLE IN CONDUIT, NO. 16 2C <i>SIGNAL</i>	FOOT	1223	---	---	---	---	---	---	1223	---	---	---	---	---
87301282	ELECTRIC CABLE IN CONDUIT, NO. 16 10C <i>SIGNAL</i>	FOOT	1179	---	---	---	---	---	---	1179	---	---	---	---	---
87704312	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 22 FT. AND 40 FT.	EACH	1	---	---	1	---	---	---	---	---	---	---	---	---
87704311	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 20 FT. AND 48 FT.	EACH	1	---	---	---	1	---	---	---	---	---	---	---	---
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	7125	---	---	---	---	---	---	---	7125	---	---	---	---
87301732	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 20 3 C	FOOT	3266	---	---	---	---	---	---	---	---	---	---	3266	---
X8770250	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 32 FT. AND 48 FT. (SPECIAL)	EACH	1	---	---	---	---	1	---	---	---	---	---	---	---

* - SPECIALTY ITEM

FILE NAME = 0366983-SHT-500.DGN

USER NAME = ---
PLOT SCALE = 1"=20'
PLOT DATE = 01/11

DESIGNED - DJD
DRAWN - NV
CHECKED - DJD
DATE - 01/11

REVISED - ---
REVISED - ---
REVISED - ---
REVISED - ---

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: 1"=20' SHEET NO. ___ OF ___ SHEETS STA. TO STA.

Rev.
F.A.P. RTE. 68 SECTION (28)N, TS & I COUNTY DEKALB TOTAL SHEETS 120 SHEET NO. 7 CONTRACT NO. 66983
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT