

RESURFACING SCHEDULE

STATION	HMA BASE COURSE WIDENING 9" (TON)	AGGREGATE PRIME COAT (TON)	BIT. MAT'L PRIME COAT (TON)	LEVELING BINDER (TON)	HMA SURFACE COURSE MIX "C", N70 (TON)	HMA SHOULDERS 2" (TON)	HMA SHOULDERS 8" (SQ YD)	AGGREGATE SHOULDERS TYPE B 6" (SQ YD)	BRIDGE APPROACH PVMT. CONNECT (FLEXIBLE) (SQ YD)	STRIP REFLECTIVE CRACK CONTROL TREATMENT (FT)
621+25.00 LT TO 623+00.00 LT	48.61									
621+25.00 RT/LT TO 622+41.50 RT/LT		0.47	0.10	18.27	26.10			77.67		233
621+25.00 RT TO 622+41.50 RT						4.35				
621+25.00 RT/LT TO 621+55.00 RT/LT							38.83			
622+41.50 RT/LT TO 622+47.50 RT/LT								25.22		
623+32.09 LT TO 625+00.00 LT	46.64									
623+84.50 RT/LT TO 623+90.50 RT/LT								25.22		
623+90.50 RT/LT TO 625+00.00 RT/LT		0.44	0.09	14.88	24.53			73.00		219
623+90.50 LT TO 625+00.00 LT						4.09				
623+90.50 RT TO 625+00.00 RT							36.50			
624+70.00 RT/LT TO 625+00.00 RT/LT										
TOTAL	95.25	0.90	0.19	33.15	50.62	8.44	75.33	150.67	50.44	452.00

TEMPORARY EROSION CONTROL SCHEDULE

LOCATION	RT/LT	TEMP. EROS. CONTROL SEEDING (POUND)	MULCH METHOD 1 (ACRE)	STATION	LT	RT
621+25.00 TO 625+00.00	LT	24.85	0.28	621+50.00	17	17
621+25.00 TO 625+00.00	RT	28.65	0.32	622+50.00	17	17
				623+75.00	17	17
				624+75.00	17	17
TOTAL		53.50	0.59	SUB TOTAL	68	68
				TOTAL	136	

REMOVAL SCHEDULE

STATION	HMA SURF. REMOVAL VARIABLE DEPTH (SQ YD)	HMA SURF. BUTT-JOINT REMOVAL (SQ YD)	PAVEMENT REMOVAL (SQ YD)	SPBGR REMOVAL (FT)	RAISED REFL. PAVEMENT MARKER REMOVAL (EA)	PIPE CULVERT REMOVAL 18" CMP (FT)	24" CMP (FT)
619+77.00 TO 627+22.00 CL					10		
621+25.00 TO 621+55.00 RT/LT		83.33					
621+25.00 TO 622+41.50 RT/LT	240.28						
621+97.50 TO 623+00.00 RT/LT				205.00			
622+41.50 TO 623+00.00 RT/LT			162.50				
623+40.00 TO 623+90.50 RT/LT			140.28				
623+40.00 TO 625+00.00 RT/LT	220.83						
622+68.80 TO 622+97.38 LT						29	
622+77.20 TO 623+02.60 RT							25
623+11.60 TO 623+61.70 LT						50	
623+32.50 TO 624+35.00 RT/LT				205.00			
624+70.00 TO 625+00.00 RT/LT		83.33					
SUB TOTAL						79	25
TOTAL	461.11	166.66	302.78	410.00	10	104	

TEMP. CONCRETE BARRIER SCHEDULE

LOCATION	STAGE I	STAGE II
621+09.80 RT TO 622+22.00 LT	112.50	
622+22.00 LT TO 624+09.50 LT	187.50	
624+09.50 LT TO 625+21.50 RT	112.50	
621+47.50 LT TO 622+22.00 RT		75.00
622+22.00 RT TO 624+09.50 RT		187.50
624+09.50 RT TO 625+09.50 LT		100.00
SUB TOTAL	412.50	362.50
TOTAL	775.00	

SEEDING SCHEDULE

LOCATION	SEEDING CLASS 2 (ACRE)	NITROGEN FERT. NUTR (POUND)	PHOSPHORUS FERT. NUTR (POUND)	POTASSIUM FERT. NUTR (POUND)	MULCH METHOD 1 (ACRE)
621+25.00 TO 625+00.00 RT	0.16	14.32	14.32	14.32	0.159
621+25.00 TO 625+00.00 LT	0.14	12.42	12.42	12.42	0.138
TOTAL	0.30	26.75	26.75	26.75	0.30

GUARDRAIL SCHEDULE

STATION	RT/LT	SPBGR (FT)	TBT - T1 (SPECIAL) (EA)	TERMINAL MARKER (DIRECT APPL) (EA)	TBT-T6 (EA)	GUARDRAIL MARKERS TYPE A (EA)	PRISMATIC BARRIER REFLECTOR (EA)
621+71.25 TO 622+77.50 LT	LT	12.5	1	1	1	2	
621+71.25 TO 622+77.50 RT	RT	12.5	1	1	1	2	
622+77.50 TO 623+54.50 RT/LT	RT/LT						4
623+54.50 TO 624+60.75 LT	LT	12.5	1	1	1	2	
623+54.50 TO 624+60.75 RT	RT	12.5	1	1	1	2	
TOTAL		50	4	4	4	8	4

ROW MARKERS SCHEDULE

STATION	OFFSET	ROW MARKERS (EA)
621+50.00	38.86' RT	1
621+50.00	41.14' LT	1
622+50.00	63.80' RT	1
622+50.00	66.20' LT	1
624+50.00	63.58' RT	1
624+10.00	66.29' LT	1
625+25.00	38.67' RT	1
625+25.00	41.33' LT	1
TOTAL		8

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJTD FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
STA 621+25.00 TO STA 625+00.00	426.5	319.9	220.6	99.2

NOTE: WIDENING IS INCLUDED IN THE TOTAL

TEMPORARY PAVEMENT MARKING SCHEDULE

STATION	TEMPORARY PAVEMENT MARKING LINE 4" (FT)	TEMPORARY PAVEMENT MARKING LINE 6" (FT)	SHORT TERM PAVEMENT MARKING (FT)	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)	PAVEMENT MARKING REMOVAL (SQ FT)
619+77.00 TO 627+22.00 RT/LT	EDGE LINES				496.7
619+77.00 TO 627+22.00 CL	CENTER LINE				62.1
622+00.00 TO 627+00.00 CL	CENTER LINE				166.7
619+77.00 TO 627+22.00 RT/LT	EDGE LINES - STAGE 1	1490.00	447.0	645.7	
621+09.80 TO 625+21.90	CONC. BARR - STAGE 1		412.50		
619+86.00 TO 626+90.50 RT/LT	EDGE LINES - STAGE 2	1409.00	211.4	540.1	
621+47.50 TO 625+09.50	CONC. BARR - STAGE 2		362.50		
TOTAL		2899.0	775.0	658.4	1185.8

PAVEMENT MARKING SCHEDULE

STATION	THERMOPLASTIC PVMT MKG			POLYUREA			RAISED REFL. PMK MKRS TWO-WAY (EA)
	4" WHITE LINE (FT)	YELLOW SKIP DASH LINE (FT)	4" YELLOW LINE (FT)	4" WHITE LINE (FT)	YELLOW SKIP DASH LINE (FT)	4" YELLOW LINE (FT)	
619+77.00 LT/RT TO 622+47.50 LT/RT	EDGE LINE	541.00					
619+77.00 CL TO 622+47.50 CL	CENTER LINE		67.62				4
622+00.00 CL TO 622+47.50 CL	CENTER LINE		47.50				
622+47.50 LT/RT TO 623+84.50 LT/RT	EDGE LINE			274.00			
622+47.50 CL TO 623+84.50 CL	CENTER LINE				34.25		2
622+47.50 CL TO 623+84.50 CL	CENTER LINE					137.00	
623+84.50 LT/RT TO 627+22.00 LT/RT	EDGE LINE	675.00					
623+84.50 CL TO 627+22.00 CL	CENTER LINE		84.38				4
623+84.50 CL TO 627+22.00 CL	CENTER LINE		337.50				
SUB TOTAL		1216.00	152.00	385.00	274.00	34.25	137.00
TOTAL		1753.00			445.25		10