

TYSON ENGINEERING, INC.
 CONSULTING CIVIL ENGINEERS
 LAND SURVEYORS
 DESIGN FIRM LICENSE #184-001136
 367 SOUTH SCHUYLER AVENUE
 KANKAKEE, ILLINOIS 60901
 PHONE (815) 952-7406

This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of Tyson Engineering Inc. and is not to be used in whole or in part, for any other project without written authorization of Tyson Engineering Inc.
 Do not scale drawings. Use dimensions only.
 Contractor shall be responsible for verifying all dimensions.
 Information hereon and herein is confidential.

REVISIONS			
NO.	DATE	BY	DESCRIPTION
1	7/28/11	NRD	REV. PER IDOT

SCHEDULE OF QUANTITIES

PROJECT: **GREENWAYS TRAIL**
 MANTENO, ILLINOIS

SECTION 08-00058-00-BT	
DATE: 7/15/11	JOB NO. E08110
SCALE: N/A	FILE NO.
DRAWN BY: MRG	SHEET
CHECKED BY: SRM	5

PAVEMENT SCHEDULE						
LOCATION	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION (SQ YD)	AGGREGATE BASE COURSE TYPE B 8" (SQ YD)	AGGREGATE SHOULDERS TYPE B 4" (SQ YD)	HOT-MIX ASPHALT SURFACE COURSE MIX "C", N30 (TON)	LEVELING BINDER (MACHINE METHOD), N30 (TON)	COMBINATION CONCRETE CURB & GUTTER TYPE B-6.12 (FOOT)
STA 1+00 TO 15+04.57	1561	1561	624	141	141	
STA 15+84.57 TO 18+52.79	298	298	119	27	27	
STA 18+52.79						10
STA 100+00 TO 103+98.74	444	444	178	40	40	
TOTAL	2303	2303	921	208	208	10

MISCELLANEOUS SCHEDULE					
LOCATION	BOLLARDS (EACH)	STORM SEWER CLASS A, TYPE 1		PRECAST REINFORCED CONCRETE FLARED END SECTIONS	
		12" (FOOT)	24" (FOOT)	12" (EACH)	24" (EACH)
STA 1+05	1				
STA 13+85			40		2
STA 16+40		64		2	
STA 18+47	1				
TOTAL	2	64	40	2	2

EROSION CONTROL SCHEDULE			
LOCATION	PERIMETER EROSION BARRIER (FOOT)	INLET AND PIPE PROTECTION (EACH)	STABILIZED CONSTRUCTION ENTRANCE (SQ YD)
STA 1+00			125
STA 1+00 TO 18+52.79	1825		
STA 13+85		1	
STA 14+13		1	
STA 16+40		1	
TOTAL	1825	3	125

PAVEMENT MARKING SCHEDULE			
LOCATION	THERMOPLASTIC PAVEMENT MARKING		
	LINE 4" (FOOT)	LINE 12" (FOOT)	
STA 1+00 TO 18+52	438		SKIP DASH YELLOW
STA 1+05		5	STOP BAR WHITE
STA 18+47		5	STOP BAR WHITE
STA 100+00 TO 103+99	100		SKIP DASH YELLOW
STA 100+12		5	STOP BAR WHITE
TOTAL	538	15	

TURF ESTABLISHMENT SCHEDULE			
LOCATION	TOP SOIL 4" (SQ YD)	SEEDING CLASS 1B (ARCE)	MULCH METHOD 2 (ACRE)
STA 1+00 TO 15+04.57	1391	0.3	0.3
STA 15+84.57 TO 18+52.79	844	0.2	0.2
STA 100+00 TO 103+98.74	311	0.1	0.1
TOTAL	2546	0.6	0.6

SIGNS SCHEDULE			
LOCATION	SIGN PANEL TYPE 1 (SQ FT)	METAL POST TYPE A (FOOT)	
STA 1+05 - 8 LT	2.25	12	STOP SIGN (R1-1) (18"x18")
STA 1+05 - 8 RT	4	12.5	NO MOTOR VEHICLES (R5-3) (24"x24")
STA 18+47 - 8 LT	4	12.5	NO MOTOR VEHICLES (R5-3) (24"x24")
STA 18+47 - 8 RT	2.25	12	STOP SIGN (R1-1) (18"x18")
STA 100+12 - 8 LT	2.25	12	STOP SIGN (R1-1) (18"x18")
TOTAL	14.75	61	

EARTH EXCAVATION SCHEDULE		
LOCATION	EARTH EXCAVATION (CU YD)	FILL (CU YD)
STA 1+00 TO 15+14.57	448	660
STA 15+74.57 TO 18+52.79	92	860
STA 100+00 TO 103+98.74	89	53
TOTAL	629	1573

RAILING SCHEDULE	
LOCATION	BICYCLE RAILING (FOOT)
STA 14+94 TO 15+04 - RT	10
STA 14+94 TO 15+04 - LT	10
STA 15+85 TO 15+95 - RT	10
STA 15+85 TO 15+95 - LT	10
TOTAL	40

REMOVALS SCHEDULE	
LOCATIONS	COMBINATION CURB & GUTTER REMOVAL (FOOT)
STA 1+00	10
STA 18+53	10
TOTAL	20

SIDEWALK SCHEDULE		
LOCATION	PORTLAND CEMENT CONCRETE SIDEWALK 5" (SQ FT)	DETECTABLE WARNINGS (SQ FT)
STA 1+00 TO 1+05	50	18
STA 18+48 TO 18+52.79	50	18
TOTAL	100	36