

# SUMMARY OF QUANTITIES

SPECIAL PROVISION	SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
						80% FEDERAL 20% STATE		100% LOCAL
						ROADWAY 0004 URBAN	BRIDGE 0011 URBAN	TRAINEES 0042 URBAN
		20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	140	140		
		20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	18	18		
		20101100	TREE TRUNK PROTECTION	EACH	9	9		
S		20200100	EARTH EXCAVATION	CU YD	570	570		
		20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,725	1725		
		20300100	CHANNEL EXCAVATION	CU YD	1,060	1060		
		20400800	FURNISHED EXCAVATION	CU YD	800	800		
		20800150	TRENCH BACKFILL	CU YD	255	255		
		21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	3,700	3700		
		21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3,499	3499		
S		21400100	GRADING AND SHAPING DITCHES	FOOT	113	113		
	*	25000110	SEEDING, CLASS 1A	ACRE	0.75	0.75		
	*	25000312	SEEDING, CLASS 4A	ACRE	0.25	0.25		
	*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90	90		
	*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	90		
	*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90	90		
	*	25100630	EROSION CONTROL BLANKET	SQ YD	3,599	3599		
	*	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	413	413		
S		28000305	TEMPORARY DITCH CHECKS	FOOT	230	230		
		28000400	PERIMETER EROSION BARRIER	FOOT	1,556	1556		
		28000500	INLET AND PIPE PROTECTION	EACH	16	16		
		28100107	STONE RIPRAP, CLASS A4	SQ YD	1,018		1018	
		28200200	FILTER FABRIC	SQ YD	1,018		1018	
		31101100	SUBBASE GRANULAR MATERIAL, TYPE B	CU YD	66	66		
		35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	112	112		
		40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5	5		
		40600300	AGGREGATE (PRIME COAT)	TON	6	6		
		40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	130	130		
		40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	72	72		
		40600990	TEMPORARY RAMP	SQ YD	107	107		
		40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	797	797		
		40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	272	272		

FILE NAME = \\A:\Projects\2010\1000054\Berkong\Berkong\Drawings\Sheet\5001.dgn



USER NAME = #USER#	DESIGNED - DPB	REVISED -
	DRAWN - NDP	REVISED -
PLOT SCALE =	CHECKED - SBP	REVISED -
PLOT DATE = 7/6/2011	DATE - 7/8/11	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET NO. 4 OF 88 SHEETS STA. TO STA.

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5355	04-00167-00-BR	DEKALB	88	4
CONTRACT NO. 87491				
FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT				