

SCHEDULE OF QUANTITIES

63100085 TRAFFIC BARRIER TERMINAL, TYPE 6				
EACH	LOCATION		O/S	REMARKS
1	16+61.30	17+04.20	LT	NW CORNER DEPARTING
1	16+59.60	17+04.20	RT	SW CORNER APPROACH
1	18+62.90	19+08.00	LT	NE CORNER APPROACH
1	18+62.90	19+08.00	RT	SE CORNER DEPARTING
4	TOTAL			

70106800 CHANGEABLE MESSAGE SIGN		
CAL MO	LOCATION	REMARKS
3	EAST OF PROJECT	STAGE 1 - AS DIRECTED BY R. E.
3	WEST OF PROJECT	
3	EAST OF PROJECT	STAGE 2 - AS DIRECTED BY R. E.
3	WEST OF PROJECT	
12	TOTAL	

63100167 TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT				
EACH	LOCATION		O/S	REMARKS
1	16+11.30	16+61.30	LT	NW CORNER DEPARTING
1	16+09.60	16+59.60	RT	SW CORNER APPROACH
1	19+08.00	19+61.30	LT	NE CORNER APPROACH
1	19+08.00	19+62.90	RT	SE CORNER DEPARTING
4	TOTAL			

70300100 SHORT TERM PAVEMENT MARKING				
FOOT	LOCATION		O/S	REMARKS
212	12+19.00	22+80.00	CL	STAGE 3- DOUBLE 4" SKIP-DASH
14	12+19.00	13+62.70	LT	STAGE 3 - SINGLE 4" WHITE LANE
8	12+64.00	13+43.00	RT	STAGE 3 - SINGLE 4" WHITE LANE
234	SUB-TOTAL			
2	APPLICATIONS			
469	TOTAL			

63200310 GUARDRAIL REMOVAL				
FOOT	LOCATION		O/S	REMARKS
139	15+71.80	17+10.60	LT	NW CORNER DEPARTING
139	15+71.90	17+10.60	RT	SW CORNER APPROACH
138	18+56.50	19+94.80	LT	NE CORNER APPROACH
138	18+56.70	19+94.90	RT	SE CORNER DEPARTING
554	TOTAL			

X2130010 EXPLORATION TRENCH, SPECIAL			
FOOT	LOCATION		REMARKS
100	13+19.00	21+80.00	AS DIRECTED BY R.E.
100	TOTAL		

66500105 WOVEN WIRE FENCE, 4'				
FOOT	LOCATION		O/S	REMARKS
16	18+35.90	18+35.90	LT	
101	18+35.90	19+37.03	LT	
118	TOTAL			

Z0007124 STEEL RAILING (SPECIAL)				
(FOOT)	LOCATION		O/S	REMARKS
65.9	16+51.28	17+17.20	RT	WEST APPROACH
47.1	18+49.90	18+96.98	RT	EAST APPROACH
113.0	TOTAL ROADWAY			
132.7	17+17.20	18+49.90	RT	BRIDGE
132.7	TOTAL BRIDGE			

70103815 TRAFFIC CONTROL SURVEILLANCE				
CAL DAYS	LOCATION		O/S	REMARKS
14	13+19.00	21+80.00	LT/RT	STAGE 1 A AND STAGE 3
14	TOTAL			

Z0013302 SEGMENTAL CONCRETE BLOCK WALL				
SQ FT	LOCATION		O/S	REMARKS
52	16+87.00		LT	TREE WALL
52	17+20.00		LT	TREE WALL
104	TOTAL			

FILE NAME = W:\P\Projects\2010\80954_Bethon\B\veedh\Civil\Dgn\SHA\SCHEDULE3.dgn

WILLS BURKE KELSEY ASSOCIATES LTD.
 110 West Main Street, Suite 201
 St. Charles, Illinois 60114
 (630) 443-7755

USER NAME = #USER#	DESIGNED - DPB	REVISED -
PLOT SCALE =	DRAWN - NDP	REVISED -
PLOT DATE = 7/8/2011	CHECKED - SBP	REVISED -
	DATE - 7/8/11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES	
SCALE:	SHEET NO. 11 OF 88 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5355	04-00167-00-BR	DEKALB	88	11
CONTRACT NO. 87491				
FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT				