

# SEEDING AND EROSION CONTROL SCHEDULE

LOCATION	OFF.	20101100	21101625	25000110	25000312	25000400	25000500	25000600	25100630	28000250	28000305	28000400	28000500	28100107	28200200
		TREE TRUNK PROTECTION	TOPSOIL FURNISH AND PLACE, 4"	SEEDING, CLASS 1A	SEEDING, CLASS 4A	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	STONE RIPRAP, CLASS A4	FILTER FABRIC
		(EACH)	(SQ YD)	(SQ YD)	(SQ YD)	(LBS)	(LBS)	(LBS)	(SQ YD)	(LBS)	(FOOT)	(FOOT)	(EACH)	(SQ YD)	(SQ YD)
<b>MAINLINE</b>															
13+19.00 - 13+50.00			84.2	84.2		1.6	1.6	1.6	84.2	10.0	10	62	1		
13+50.00 - 14+00.00			62.5	62.5		1.2	1.2	1.2	62.5	7.4		58	1		
14+00.00 - 14+50.00			164.6	164.5		3.1	3.1	3.1	164.6	19.4		100			
14+50.00 - 15+00.00			242.1	242.0		4.6	4.6	4.6	242.1	28.6		100	1		
15+00.00 - 15+26.00			116.6	116.5		2.2	2.2	2.2	116.6	13.8	10	45	3		
15+26.00 - 15+50.00			106.8	106.7		2.0	2.0	2.0	106.8	12.6	10	46			
15+50.00 - 16+00.00			254.3	250.4		4.8	4.8	4.8	254.3	30.0	10	103			
16+00.00 - 16+50.00		1.0	200.2	111.5	3.8	88.6	3.8	3.8	200.2	23.6	10	101			
16+50.00 - 17+00.00			263.0	103.8	159.2	4.9	4.9	4.9	263.0	31.0		100			
17+00.00 - 17+16.20			93.5	49.0	44.5	1.8	1.8	1.8	93.5	11.1		22		12.6	12.6
<b>BRIDGE</b>												50		992.4	992.4
18+49.87 - 19+00.00		1.0	170.8	49.0	121.7	3.2	3.2	3.2	170.8	20.2		88		13.0	13.0
19+00.00 - 19+50.00		1.0	251.7	108.2	143.3	4.7	4.7	4.7	251.7	29.7	10	121	2		
19+50.00 - 20+00.00		1.0	203.8	124.9	78.8	3.8	3.8	3.8	203.8	24.0	10	100	2		
20+00.00 - 20+50.00		1.0	320.8	320.7		6.0	6.0	6.0	320.8	37.8		100	2		
20+50.00 - 21+00.00		2.0	367.9	367.8		6.9	6.9	6.9	367.9	43.4	40	100			
21+00.00 - 21+50.00			368.4	368.4		6.9	6.9	6.9	368.4	43.4	20	100			
21+50.00 - 22+00.00		1.0	227.8	227.8		4.3	4.3	4.3	227.8	26.9	20	60			
22+00.00 - 22+50.00		1.0													
22+50.00 - 23+00.00															
<b>MAINTENANCE / REPL.</b>															
13+19.00 - 23+00.00	LT/RT								100.0		80	100	4		
<b>TOTAL</b>		<b>9</b>	<b>3,499.0</b>	<b>2,857.9</b>	<b>639.9</b>	<b>65.8</b>	<b>65.8</b>	<b>65.8</b>	<b>3,599.0</b>	<b>413.0</b>	<b>230</b>	<b>1,556</b>	<b>16</b>	<b>1,018.0</b>	<b>1,018.0</b>
				<b>0.75 AC</b>	<b>0.25 AC</b>	<b>90.0</b>	<b>90.0</b>	<b>90.0</b>							

FILE NAME: \\N:\Projects\2010\08054\_Boston\gpr\SHA\SCHEDULE.dgn