

SUMMARY OF QUANTITIES				CONSTRUCTION CODES		
CODE NO.	ITEM	SP. PROV.	UNIT	TOTAL QUANTITIES	0021	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)		UNIT	32	32	
20200100	EARTH EXCAVATION		CU YD	970	970	
25100105	MULCH, METHOD 1		ACRE	0.7	0.7	
28000250	TEMPORARY EROSION CONTROL SEEDING		POUND	100	100	
31100300	SUBBASE GRANULAR MATERIAL, TYPE A 4"		SQ YD	646	646	
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"		SQ YD	796	796	
40600200	BITUMINOUS MATERIALS (PRIME COAT)		TON	5.8	5.8	
40600300	AGGREGATE (PRIME COAT)		TON	23.4	23.4	
40600895	CONSTRUCTING TEST STRIP		EACH	1	1	
40600990	TEMPORARY RAMP		SQ YD	137	137	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50		TON	283	283	
40603535	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50		TON	982	982	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH		SQ YD	63	63	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH		SQ YD	472	472	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH		SQ FT	12968	12968	
42400800	DETECTABLE WARNINGS		SQ FT	148	148	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"		SQ YD	11041	11041	
44000200	DRIVEWAY PAVEMENT REMOVAL		SQ YD	655	655	
44000300	CURB REMOVAL		FOOT	19	19	
44000500	COMBINATION CURB AND GUTTER REMOVAL		FOOT	1114	1114	
44000600	SIDEWALK REMOVAL		SQ FT	6355	6355	
44201737	CLASS D PATCHES, TYPE I, 8 INCH		SQ YD	30	30	
44201741	CLASS D PATCHES, TYPE II, 8 INCH		SQ YD	50	50	
Δ 56109210	WATER VALVES TO BE ADJUSTED	•	EACH	3	3	
Δ 56400510	FIRE HYDRANTS TO BE REMOVED AND REPLACED	•	EACH	3	3	
60255500	MANHOLES TO BE ADJUSTED		EACH	2	2	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12		FOOT	1102	1102	
67100100	MOBILIZATION		L SUM	1	1	
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502		L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606		L SUM	1	1	

Δ SPECIALTY ITEMS

FILE NAME =	USER NAME = seb	DESIGNED -	REVISED -	CITY OF QUINCY 730 MAINE STREET QUINCY, IL 62301	SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
P:\08files\080297\05 Plans\Construction	Plans\QUANT_080297.dgn	DRAWN -	REVISED -			7807	08-00307-00-TL	ADAMS	50	3	
	PLOT SCALE = 28.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 93554					
	PLOT DATE = 6/28/2011	DATE -	REVISED -			SCALE: None	SHEET NO. 1 OF 4 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	