

SUMMARY OF QUANTITIES				CONSTRUCTION CODES		
CODE NO.	ITEM	SP. PROV.	UNIT	TOTAL QUANTITIES	0021	
81700315	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 3-1/C NO. 10		FOOT	697	697	
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK		FOOT	420	420	
82104250	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, PHOTO-CELL CONTROL, 250 WATT		EACH	4	4	
82500335	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240VOLT, 100AMP		EACH	1	1	
84200500	REMOVAL OF LIGHTING UNIT, SALVAGE		EACH	1	1	
84200804	REMOVAL OF POLE FOUNDATION		EACH	1	1	
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	•	EACH	1	1	
85900100	TRANSCEIVER		EACH	1	1	
87301165	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 12 9C		FOOT	555	555	
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C		FOOT	2256	2256	
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C		FOOT	1857	1857	
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C		FOOT	1300	1300	
87301705	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 18 3 PAIR		FOOT	399	399	
87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 3 C		FOOT	79	79	
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C		FOOT	612	612	
87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT.		EACH	4	4	
87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.		EACH	3	3	
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	•	EACH	1	1	
87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	•	EACH	1	1	
87702900	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 34 FT.	•	EACH	1	1	
87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT.	•	EACH	1	1	
87800100	CONCRETE FOUNDATION, TYPE A		FOOT	23	23	
87800150	CONCRETE FOUNDATION, TYPE C		FOOT	3	3	
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER		FOOT	48	48	
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED		EACH	4	4	
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED		EACH	4	4	
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED		EACH	4	4	
88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED		EACH	4	4	
88102825	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	•	EACH	8	8	
88200100	TRAFFIC SIGNAL BACKPLATE		EACH	20	20	

△ SPECIALTY ITEMS

FILE NAME =  
P:\08\iles\080297\05 Plans\Construction

USER NAME = eeb  
Plans\QUANT\_080297.dgn  
PLOT SCALE = 20.0000' / IN.  
PLOT DATE = 6/28/2011

DESIGNED -  
DRAWN -  
CHECKED -  
DATE -

REVISED -  
REVISED -  
REVISED -  
REVISED -

CITY OF QUINCY  
730 MAINE STREET  
QUINCY, IL 62301

SUMMARY OF QUANTITIES

SCALE: None

SHEET NO. 3 OF 4 SHEETS STA. TO STA.

F.A.U.  
RTE.  
7807

SECTION  
08-00307-00-TL

COUNTY  
ADAMS

TOTAL SHEETS  
50

SHEET NO.  
5

CONTRACT NO. 9354

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT