

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	556	9
STA.	TO STA.			
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
62300 * (1818, ETC. 2324.6-1P)R-8				

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	90% FEDERAL / 10% STATE				
				ROADWAY J000-2A	SIGNING Y002-1C	SURVEILLANCE Y032-1F	SN 016-2625 X928-2A	SN 016-0142 SN 016-1148 SFTY-2A
* 81400200	HEAVY-DUTY HANDHOLE	EACH	13			13		
* 81400205	HEAVY-DUTY HANDHOLE (SPECIAL)	EACH	2			2		
* 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	305			305		
* 84200800	POLE FOUNDATION, REMOVED	EACH	130	130				
□ K1003660	MOWING CYCLE	EACH	6	6				
X0320870	BRACED EXCAVATION	CU YD	6,621	6,621				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	729	729				△
X0323221	PLUG AND ABANDON EXISTING PIPE	CU YD	251	251				
□ X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	209	209				
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	33,389	33,389				△
X0324112	BARRIER BASE	FOOT	27,132	27,132				△
X0324431	TEMPORARY SOIL RETENTION SYSTEM (TO REMAIN IN PLACE)	SQ FT	763	763				
X0324697	SOIL STABILIZERS	POUND	65,508	65,508				
X0324698	APPLYING DUST SUPPRESSION AGENT	UNIT	95	95				
X4210400	LUG SYSTEM REMOVAL	EACH	2	2				△
X4834090	PORTLAND CEMENT CONCRETE SHOULDERS 14"	SQ YD	52,692	52,692				
X6063401	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12	FOOT	248	248				
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	956	956				△
X6370910	CONCRETE BARRIER, SINGLE FACE 32" HEIGHT	FOOT	1,742	1,742				
X6370925	CONCRETE BARRIER SINGLE FACE 42" (SPECIAL)	FOOT	2,241	2,241				△
X6370930	CONCRETE BARRIER, DOUBLE FACE, 32"	FOOT	2,715	2,715				
X6700410	ENGINEER'S FIELD OFFICE TYPE A (SPECIAL)	CAL MO	15	15				
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1				
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	303	303				
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	59	59				
X7040600	FURNISH TEMPORARY CONCRETE BARRIER	FOOT	17,648	17,648				△
* X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	100		100			
XX001854	STABILIZED SUB-BASE, 6"	SQ YD	212,833	212,833				△
XX004201	PAVEMENT REINFORCEMENT 14"	SQ YD	148,588	148,588				△
* XX004812	VIDEO TAPING OF SEWERS	FOOT	1,191	1,191				
Z0002600	BAR SPLICERS	EACH	257			257		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
□ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	51	51				△
△ Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	6	6				
△ Z0030070	IMPACT ATTENUATORS (SEVERE USE, NARROW), TEST LEVEL 3	EACH	3	3				
△ Z0030090	IMPACT ATTENUATORS (SEVERE USE, WIDE), TEST LEVEL 3	EACH	1	1				
△ Z0030150	IMPACT ATTENUATORS, (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1				
△ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	7	7				△
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	298	298				△

* SPECIALITY ITEM □ NON-PARTICIPATING

△ INDICATES PAY CODE TYPE SFTY-3N



ONE NORTH FRANKLIN
CHICAGO, IL 60606
PHONE: (312) 251-3000
FAX: (312) 251-3015
WEB: WWW.EKCORP.COM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
31ST STREET TO 71ST STREET
NB EXPRESS LANE RECONSTRUCTION
SUMMARY OF QUANTITIES

SCALE: NONE
DATE: 7/7/05

DRAWN BY: TAI
CHECKED BY: PJM