

F.A.I. RTE. 94/90	SECTION *	COUNTY COOK	TOTAL SHEETS 556	SHEET NO. 22B
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
62300		• (1818, ETC, 2324.6-1P/R-8		

EARTHWORK SCHEDULE

STATION TO STATION		EARTH EXCAVATION (CU YD)	EXCAVATE EXISTING GRANULAR MATERIAL (CU YD)	PLACE EXISTING GRANULAR MATERIAL (CU YD)	EXISTING GRANULAR MATERIAL BALANCE SURPLUS (+) OR SHORTAGE (-) (CU YD)
2592+00.00	2593+00.00	69.8	609	309.4	300
2593+00.00	2594+00.00	74.6	596	309.6	286
2594+00.00	2595+00.00	72.8	600	309.4	291
2595+00.00	2596+00.00	65.2	624	309.5	314
2596+00.00	2597+00.00	68.9	629	308.7	320
2597+00.00	2598+00.00	71.7	632	311.9	320
2598+00.00	2599+00.00	64.2	632	313.9	318
2599+00.00	2600+00.00	64.8	622	311.1	311
2600+00.00	2601+00.00	75.4	616	309.8	307
2601+00.00	2602+00.00	81.0	623	309.9	313
2602+00.00	2603+00.00	79.7	636	311.7	324
2603+00.00	2604+00.00	77.2	652	312.9	339
2604+00.00	2605+00.00	75.1	670	314.0	356
2605+00.00	2606+00.00	238.2	514	315.7	199
2606+00.00	2607+00.00	342.3	353	315.0	38
2607+00.00	2608+00.00	272.2	353	310.3	43
2608+00.00	2609+00.00	136.0	453	321.2	132
2609+00.00	2610+00.00	51.6	586	280.8	305
2610+00.00	2611+00.00	116.4	603	265.7	337
2611+00.00	2612+00.00	149.1	563	297.4	266
2612+00.00	2613+00.00	153.9	544	291.2	253
2613+00.00	2614+00.00	147.8	570	289.9	280
2614+00.00	2615+00.00	141.1	615	284.4	331
2615+00.00	2616+00.00	138.9	640	281.9	358
2616+00.00	2617+00.00	140.6	623	282.9	340
2617+00.00	2618+00.00	144.6	582	291.9	290
2618+00.00	2619+00.00	274.3	447	303.6	144
2619+00.00	2620+00.00	396.2	334	304.6	30
2620+00.00	2621+00.00	333.2	342	291.2	51
2621+00.00	2622+00.00	326.9	352	283.5	69
2622+00.00	2623+00.00	225.9	513	297.4	216
2623+00.00	2624+00.00	70.1	681	311.1	370
2624+00.00	2625+00.00	71.6	669	312.5	356
2625+00.00	2626+00.00	72.6	659	307.2	352
2626+00.00	2627+00.00	66.4	678	301.3	377
2627+00.00	2628+00.00	62.9	668	296.6	372
2628+00.00	2629+00.00	56.1	650	292.1	358
2629+00.00	2630+00.00	43.6	667	287.8	380
2630+00.00	2631+00.00	44.2	700	284.8	415
2631+00.00	2632+00.00	247.6	534	283.7	250
2632+00.00	2633+00.00	439.5	352	283.6	68
2633+00.00	2634+00.00	438.0	351	282.9	69
2634+00.00	2635+00.00	458.8	352	281.9	70
2635+00.00	2636+00.00	431.2	333	296.9	36
2636+00.00	2637+00.00	378.6	333	261.0	72
2637+00.00	2637+49.00	169.2			
TOTALS		172,538	44,744	44,744	0

REVISIONS	
NAME	DATE
ADDENDUM 1	8/12/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
31ST STREET TO 71ST STREET
NB EXPRESS LANE RECONSTRUCTION
 EARTHWORK
 SCHEDULE

SCALE: _____ DRAWN BY: _____
 DATE: 7/7/05 CHECKED BY: _____

**Edwards
AND Kelcey**
 ONE NORTH FRANKLIN
 CHICAGO, IL 60606
 PHONE: (312) 251-3000
 FAX: (312) 251-3015
 WEB: WWW.EKCORP.COM

P:\03000\9490\5555\Corr 148\5\CADD\A\FSC\400328-517 08/19/2005 03:52:00 PM