

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	*	COOK	556	26
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
62300	* (1818, ETC, 2324.6-1P/R-8			

SHEET NUMBER	LINE DESCRIPTION	STATION	TO STATION	PAVEMENT MARKING TYPE III 4" (FOOT)
STAGE IA MOT-4	SOLID (Y)	2352+00	2367+00	1500
	6'S - 2'D (W)	2359+50	2362+53	76
	SOLID (W)	2354+35	2367+00	1265
	SOLID (Y)	2367+00	2382+00	1500
	SOLID (W)	2367+00	2372+14	514
MOT-5	SOLID (Y)	2367+52	2374+60	708
	SOLID (W)	2367+52	2382+00	1448
	SOLID (Y)	4381+76	4397+07	1531
	SOLID (W)	4381+76	4389+83	807
	SOLID (Y)	4384+24	4389+83	559
STAGE IB MOT-6	SOLID (W)	4384+24	4397+07	1283
	SOLID (Y)	4397+07	4400+96	389
	SOLID (W)	4397+07	4400+96	389
	SOLID (Y)	2356+78	2367+00	1022
	SOLID (W)	2354+35	2367+00	1265
MOT-7	SOLID (Y)	2354+35	2356+78	243
	6'S - 2'D (W)	2360+22	2363+22	75
	SOLID (Y)	2367+00	2382+00	1500
	SOLID (W)	2374+71	2382+00	729
	SOLID (W)	2367+00	2374+37	737
STAGE IC MOT-8	SOLID (Y)	4381+76	4391+37	961
	SOLID (W)	4381+76	4389+83	807
	SOLID (W)	4384+63	4391+37	674
	SOLID (Y)	4384+63	4389+83	520
	SOLID (Y)	2367+00	2382+00	1500
MOT-9	SOLID (W)	2367+00	2374+76	776
	SOLID (W)	2374+60	2382+00	740
	SOLID (Y)	4381+76	4387+27	551
	SOLID (W)	4381+76	4387+27	551
	SOLID (Y)	4400+96	4412+42	1146
STAGE I MOT-10	SOLID (W)	4400+96	4412+42	1146
	SOLID (Y)	4412+42	4426+98	1456
	SOLID (W)	4412+42	4414+24	182
	SOLID (W)	4414+24	4426+98	1274
	SOLID (W)	4416+78	4426+98	255
MOT-11	6'S - 2'D (W)	4426+98	4430+00	76
	SOLID (Y)	4426+98	4441+96	1498
	SOLID (W)	4426+98	4432+84	586
	SOLID (W)	4432+84	4440+60	776
	SOLID (Y)	4440+60	4441+96	136
MOT-12	6'S - 2'D (W)	4434+89	4438+07	80
	SOLID (Y)	4441+96	4457+00	1504
	SOLID (W)	4441+96	4457+00	1504
	6'S - 2'D (W)	4455+57	4457+00	36
	SOLID (Y)	4457+00	4471+99	1499
MOT-13	6'S - 2'D (W)	4457+00	4458+85	46
	SOLID (W)	4457+00	4461+99	499
	SOLID (W)	4461+99	4471+99	1000
	SOLID (Y)	4471+99	4486+99	1500
	SOLID (W)	4471+99	4486+99	1501
MOT-14	SOLID (W)	4486+99	4487+50	51
	6'S - 2'D (W)	4488+99	4492+60	90
	SOLID (W)	4487+50	4502+00	1450
	SOLID (Y)	4502+00	4517+01	1501
	SOLID (W)	4502+00	4514+05	1205
MOT-15	6'S - 2'D (W)	4506+05	4510+02	99
	SOLID (W)	4514+05	4517+01	296
	SOLID (Y)	4517+01	4529+76	1275
	SOLID (Y)	4517+01	4529+76	1275
	SOLID (W)	4517+01	4529+76	1275

SHEET NUMBER	LINE DESCRIPTION	STATION	TO STATION	PAVEMENT MARKING TYPE III 4" (FOOT)
STAGE II MOT-25	SOLID (Y)	2364+20	2367+00	280
	SOLID (W)	2364+20	2367+00	280
	6'S - 2'D (W)	2364+20	2367+00	70
	SOLID (Y)	2367+00	2382+00	1500
	SOLID (W)	2367+00	2374+60	760
MOT-26	SOLID (Y)	2372+75	2382+00	925
	SOLID (Y)	2372+75	2374+60	185
	SOLID (Y)	2382+00	2392+67	1067
	SOLID (W)	2382+00	2392+67	1067
	SOLID (Y)	4384+63	4391+37	674
MOT-19	SOLID (W)	4384+63	4391+37	674
	SOLID (Y)	4428+00	4442+00	1400
	6'S - 2'D (W)	4428+00	4432+00	100
	SOLID (W)	4436+98	4442+00	502
	SOLID (Y)	2442+00	2457+00	1500
MOT-20	SOLID (W)	2442+00	2457+00	1500
	SOLID (Y)	2457+00	2472+00	1500
	SOLID (W)	2457+00	2472+00	1500
	SOLID (Y)	2472+00	2487+00	1500
	SOLID (W)	2472+00	2487+00	1500
MOT-21	SOLID (Y)	2487+00	2502+00	1500
	SOLID (W)	2487+00	2502+00	1500
	SOLID (Y)	2502+00	2517+00	1500
	SOLID (W)	2502+00	2517+00	1500
	SOLID (Y)	2517+00	2530+00	1300
STAGE I MOT-14	SOLID (W)	2517+00	2520+00	300
	6'S - 2'D (W)	4523+76	4528+00	106
	SOLID (W)	4540+70.00	4542+31.00	161
	6'S - 2'D (W)	4543+00.00	4547+06.00	102
	SOLID (W)	4550+00.00	4554+05.00	405
MOT-15	SOLID (Y)	4529+80.00	4554+05.00	2,425
	SOLID (W)	4554+05.00	4564+00.00	995
	SOLID (W)	4565+51.00	4569+83.00	432
	SOLID (W)	4573+88.00	4578+05.00	417
	SOLID (Y)	4554+05.00	4578+05.00	2,400
MOT-16	6'S - 2'D (W)	4565+15.00	4571+25.00	153
	SOLID (W)	4578+05.00	4582+66.00	461
	SOLID (W)	4586+40.00	4601+00.00	1,460
	SOLID (Y)	4578+05.00	4602+05.00	2,400
	6'S - 2'D (W)	4582+66.00	4584+51.00	46
MOT-17	SOLID (W)	4610+50.00	4616+86.00	636
	SOLID (W)	4621+67.00	4624+32.00	265
	SOLID (Y)	4602+05.00	4626+05.00	2,400
	6'S - 2'D (W)	4604+50.00	4610+50.00	150
	6'S - 2'D (W)	4620+17.00	4624+59.00	111
MOT-18	SOLID (W)	4626+90.00	4629+80.00	290
	SOLID (Y)	4626+05.00	4629+80.00	375
	SOLID (W)	4619+92.00	4626+06.30	616
	SOLID (Y)	4619+92.00	4626+06.30	616
	6'S - 2'D (W)	4616+00.00	4617+93.60	49
MOT-18A	SOLID (W)	4626+06.30	4642+29.00	1,630
	SOLID (Y)	4626+06.30	4642+29.00	1,630
	6'S - 2'D (W)	4541+99.00	4626+05.00	8,406
	SOLID (W)	4541+99.00	4626+05.00	8,406
	SOLID (Y)	4541+99.00	4626+05.00	8,406
MOT-23	SOLID (W)	4626+05.00	4642+29.00	1,624
	SOLID (Y)	4626+05.00	4642+29.00	1,624
	TOTAL			114,100

SHEET NUMBER	LINE DESCRIPTION	STATION	TO STATION	PAVEMENT MARKING TYPE III 12" (FOOT)
STAGE IA MOT-4	⊙ GORE (DIAGONAL)	2354+35	2359+50	313
MOT-5	⊙ GORE (DIAGONAL)	2364+04	2367+52	202
STAGE IB MOT-6	⊙ GORE (DIAGONAL)	4389+83	4390+95	13
MOT-7	⊙ GORE (DIAGONAL)	2356+78	2360+22	137
STAGE IC MOT-8	⊙ GORE (DIAGONAL)	2370+28	2374+71	125
STAGE I MOT-10	⊙ GORE (DIAGONAL)	4389+83	4390+99	9
MOT-11	⊙ GORE (DIAGONAL)	2368+71	2374+76	707
MOT-12	⊙ GORE (DIAGONAL)	4414+24	4416+78	59
MOT-13	⊙ GORE (DIAGONAL)	4432+84	4434+89	94
MOT-14	⊙ GORE (DIAGONAL)	4438+07	4440+60	205
MOT-15	⊙ GORE (DIAGONAL)	4458+85	4461+99	100
MOT-16	⊙ GORE (DIAGONAL)	4487+50	4488+99	22
MOT-17	⊙ GORE (DIAGONAL)	4510+02	4514+05	102
MOT-18	⊙ GORE (DIAGONAL)	4542+31.00	4543+00.00	20
MOT-18A	SHLDR DIAG.	4541+99.00	4637+65.00	541
MOT-18B	⊙ GORE (DIAGONAL)	4617+93.6	4619+92.8	3
STAGE II MOT-19	⊙ GORE (DIAGONAL)	4432+00	4436+98	153
MOT-20	⊙ SHLDR. (DIAGONAL)	4436+98	4442+00	27
MOT-21	⊙ SHLDR. (DIAGONAL)	2442+00	2472+00	122
MOT-22	⊙ SHLDR. (DIAGONAL)	2472+00	2502+00	151
MOT-23	⊙ GORE (DIAGONAL)	4520+00	4523+76	122
MOT-24	⊙ SHLDR. (DIAGONAL)	2502+00	2530+00	96
MOT-25	⊙ GORE (DIAGONAL)	2367+00	2372+75	457
△ TOTAL				3,813

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.I. 94/90 (DAN RYAN EXPRESSWAY) 31ST STREET TO 71ST STREET NB EXPRESS LANE RECONSTRUCTION MAINTENANCE OF TRAFFIC SCHEDULE
NAME	DATE	
ADDENDUM 1	8/12/05	SCALE: NONE DATE: 7/7/05 DRAWN BY: ATD CHECKED BY: TAI



14030000035000 1480510000V3301400026-SFT 03/26/05 PW 08/17/2005