

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	556	8
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
62300		• (1818, ETC. 2324.6-1PR-8		

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	90% FEDERAL / 10% STATE				
				ROADWAY	SIGNING	SURVEILLANCE	SN 016-2625	SN 016-0142 SN 016-1148
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	31,465	31,465				
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	180	180				
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	114,100	114,100				
70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	15,638	15,638				
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	16,720	16,720				
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	3813	3813				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	63,771	63,771				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	24,096	24,096				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	24,950	24,950				
72000100	SIGN PANEL - TYPE 1	SQ FT	12		12			
72000200	SIGN PANEL - TYPE 2	SQ FT	96		96			
72000300	SIGN PANEL - TYPE 3	SQ FT	4,186		4,186			
72100100	SIGN PANEL OVERLAY	SQ FT	2		2			
72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	72		72			
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	591		591			
72400720	RELOCATE SIGN PANEL - TYPE 2	SQ FT	12		12			
72400730	RELOCATE SIGN PANEL - TYPE 3	SQ FT	488		488			
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	1,890		1,890			
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	88		88			
73000100	WOOD SIGN SUPPORT	FOOT	17		17			
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" x 4'-6")	FOOT	72		72.0			
73300300	OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (5'-0" x 7'-0")	FOOT	142		142			
73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT	332		332			
73305000	OVERHEAD SIGN STRUCTURE WALKWAY	FT	362		362			
73400100	CONCRETE FOUNDATIONS	CU YD	7		7			
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	179		179			
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	6		6			
73602000	REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	EACH	7		7			
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	11		11			
78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	327		327			
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	100,671		100,671			
78005120	EPOXY PAVEMENT MARKING - LINE 5"	FOOT	26,758		26,758			
78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	21,714		21,714			
78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	5,824		5,824			
78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	1663		1663			
78200530	BARRIER WALL MARKERS, TYPE C	EACH	414		414			
78201000	TERMINAL MARKER, DIRECT APPLIED	EACH	1		1			
78300100	PAVEMENT MARKING REMOVAL	SQ FT	26,297		26,297			
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	299			299		

* SPECIALITY ITEM @ 3FTY-3C



ONE NORTH FRANKLIN
CHICAGO, IL 60606
PHONE: (312) 251-3000
FAX: (312) 251-3015
WEB: WWW.EKCORP.COM

Rev. 9-19-05
Rev. 8-29-05

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
31ST STREET TO 71ST STREET
NB EXPRESS LANE RECONSTRUCTION

SUMMARY OF QUANTITIES
SCALE: NONE
DATE: 7/7/05
DRAWN BY: TAI
CHECKED BY: PJM

S00-4

06/28/2005 12:42:17 PM