

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	556	11
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
62300		* (1818, ETC, 2324.6-1)PR-8		

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	90% FEDERAL / 10% STATE					
				ROADWAY	SIGNING	SURVEILLANCE	SN 016-2625	SN 016-0142 SN 016-1148	
				J000-2A	Y002-1C	Y032-1F	X928-2A	SFTY-2A	
Z0018800	DRAINAGE SYSTEM	L SUM	1	1					
* 50700209	UNTREATED TIMBER LAGGING	SQ FT	14,707	14,707					
* X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	30,688	30,688					
* X5120905	FURNISHING SOLDIER PILES W 12X72	FOOT	1680	1680					
* X5120906	FURNISHING SOLDIER PILES W 12X106	FOOT	6620	6620					
* X5120907	FURNISHING SOLDIER PILES W 12X120	FOOT	8720	8720					
Z0018800	DRILL AND GROUT BOWEL BARS	EACH							
50200100	STRUCTURE EXCAVATION	CU YD	789	789					
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1					
60248640	JUNCTIONCHAMBER NO. 11	EACH	1	1					
60248650	JUNCTIONCHAMBER NO. 12	EACH	1	1					
60248660	JUNCTIONCHAMBER NO. 13	EACH	1	1					
* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	6			6			
XX005489	STEEL CASINGS 48"	FOOT	600	600					
Z0026420	STEEL CASINGS 60"	FOOT	71	71					
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	133,635	133,635					
X2020300	EXCAVATE AND PLACE EXISTING GRANULAR MATERIAL	CU YD	45,107	45,107					
50102400	CONCRETE REMOVAL	CU YD	8	8					
Z0072600	TRAINEES	HOUR	2000	2000					
Z0002300	BALLAST	CU YD	5894	5894					

* SPECIALITY ITEM

⊙ Y080

Rev. 9-19-05

Rev. 8-29-05



ONE NORTH FRANKLIN
CHICAGO, IL 60606
PHONE: (312) 251-3000
FAX: (312) 251-3015
WEB: WWW.EKCORP.COM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
31ST STREET TO 71ST STREET
NB EXPRESS LANE RECONSTRUCTION

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: 7/7/05

DRAWN BY: TAI
CHECKED BY: PJM

S00-7

06/28/2005 12:44:36 PM