

SCHEDULE OF STORM SEWERS

F.A.I. SECTION COUNTY TOTAL SHEETS SHEET NO.
 94/90 * COOK 556 141
 STA. TO STA. TO STA.
 62300 * (1818, ETC, 2324.6-IPR-8)

FROM STRUCTURE	TO STRUCTURE	SLOPE %	SS CL A T1 12	SS CL A T1 15	SS CL A T1 18	SS CL A T1 21	SS CLA T2 12	SS CLA T2 15	SS CLA T2 18	SS CLA T2 21	SS CLA T2 24	SS CLA T2 27	SS CLA T2 30	SS CLA T2 33	SS CLA T2 36	SS CL A T2 42	SS CLA T2 48	SS CLA T3 12	SS CLA T3 21	SS CLA T3 24	SS CLA T3 30	SS CLA T3 36	SS CLA T3 42	SS CLB T1 12	SS CLB T1 15	TRENCH BACKFILL
8-14	8-12	3.00		2																						0.5
8-13	8-14	0.50	11																							1.7
8-15	8-14	0.50	11																							1.7
8-16	8-17	0.50	11																							1.9
8-17	8-14	3.50						53																		18.1
8-18	8-17	0.50	11																							1.9
9-01	EXIST.	1.00					60																			47.5
9-02	9-03	0.45	23																							3.8
9-03	9-04	0.46	89																							21.0
9-05	9-04	4.50	51																							7.8
9-06	9-04	0.52	52																							11.2
EXIST.	9-08	0.50	21																							3.8
9-09	9-10	2.00					51																			16.6
9-08	9-10	1.00	1																							0.5
9-10	9-12	0.28									31															25.0
10-11	9-10	0.40							116																	82.5
10-01	10-11	0.40						43																		29.0
10-02	10-01	1.00	1																							0.5
10-03	10-01	0.40						102																		66.0
10-04	10-03	4.30	51																							7.8
10-05	10-08	0.50	42																							8.2
10-08	10-03	1.00	24																							5.5
EXIST.	10-05	0.50	36																							8.2
10-07	JC T2 10-01	1.00					18																			13.1
10-09	JC T2 10-01	0.25																			49					93.4
10-10	10-09	0.35						102																		158.9
11-02	11-05	0.66	159																							24.2
11-03	11-11	0.52	39																							5.6
11-05	JC T2 11-01	0.66	75																							17.7
11-11	11-06	0.24								121																171.3
11-06	11-07	0.24								58																86.4
11-07	JC T2 11-01	0.13													46											87.4
11-09	11-10	1.00	57																							17.1
11-10	11-07	0.13														112										200.6
EXIST.	11-10	0.50						49																		8.2
12-02	12-01	0.54	57																							11.7
12-03	12-01	1.10	10																							1.5
12-01	12-04	0.15												41												45.6
12-04	12-05	0.15												121												128.6
12-06	12-05	0.55	56																							11.5
12-07	12-05	3.30	3																							0.5
12-05	12-08	0.15												51												51.7
12-08	12-09	0.15												122												111.6
12-10	12-09	1.40	7																							1.0
12-11	12-09	0.54	57																							9.9
12-09	12-12	0.15												35												30.3
12-12	13-01	0.15												33												7.3
EXIST.	12-12						15																			3.9
13-04	13-01	1.00								2																0.8
13-02	13-01	0.54		57																						36.4
12-14	13-02	0.50					11																			7.7
13-03	13-02	0.50					11																			7.7
12-13	13-04	0.50					11																			7.7
13-05	13-04	0.50					11																			7.7
13-01	13-06	0.30													39											35.7
13-07	13-06	0.18											37													27.8
13-06	JC T2 13-01	0.30													56											53.0
13-08	13-07	0.55	56																							9.7
13-09	13-07	2.00	2																							0.5
13-11	13-07	0.14											79													59.3
13-10	13-09	1.32	22																							3.3
13-12	13-11	0.50	56																							9.1
13-13	13-11	2.20	5																							0.8
13-14	13-11	0.68							80																	64.1
13-15	13-14	1.68		6																						1.8
13-16	13-14	0.68							117																	98.3
13-17	13-16	0.55	56																							6.7
13-18	13-16	2.00	5																							1.4
13-19	13-16	0.69								89																78.2
13-20	13-19	1.29	28																							8.1
14-01	JC T2 14-01	1.00	6																							0.9
14-02	JC T2 14-01	0.17													63											109.2

NOTE: * INDICATED STRUCTURE BEEN CONSTRUCTED IN CONTRACT 62302

REVISIONS	
NAME	DATE
ADDENDUM 2	9/16/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
 31ST STREET TO 71ST STREET
 NB EXPRESS LANE RECONSTRUCTION
 DRAINAGE SCHEDULE
 PROPOSED STORM SEWERS
 SCALE: 1" = N.T.S. DRAWN BY: MJO
 DATE: 7/7/05 CHECKED BY: LPN



09/14/2005 02:49:48 PM

DS-26