

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN		90% FEDERAL / 10% STATE						
			TOTAL QUANTITY	ROADWAY J000-2A	RETAINING WALLS Y007	S.N. 016-2625 X928-2A	SIGNING Y002-1C	SAFETY SFTY-3N	LIGHTING Y030-1E	SURVEILLANCE Y032-1F	BRIDGE REPAIRS SFTY-2A
20200100	EARTH EXCAVATION	CU YD	155,251	155,251							
20700220	POROUS GRANULAR EMBANKMENT	CU YD	965		965						
20800150	TRENCH BACKFILL	CY YD	31,274	31,274							
20900410	SAND BACKFILL	CU YD	680	680							
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	228,820	228,820							
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,865	1,865							
21101630	TOPSOIL FURNISH AND PLACE, 8"	SQ YD	3,762	3,762							
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	3,762	3,762							
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	1,518	1,518							
25000210	SEEDING, CLASS 2A	ACRE	1	1							
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	105	105							
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	105	105							
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	105	105							
25100115	MULCH, METHOD 2	ACRE	1	1							
25100630	EROSION CONTROL BLANKET	SQ YD	5,629	5,629							
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	117	117							
28000400	PERIMETER EROSION BARRIER	FOOT	975	975							
28000510	INLET FILTERS	EACH	221	221							
31101860	SUB-BASE GRANULAR MATERIAL, TYPE B 24"	SQ YD	62,191	62,191							
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	452			452					
42001300	PROTECTIVE COAT	SQ YD	231,107	231,107							
42100380	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 14"	SQ YD	146,669	146,669							
42101448	LUG SYSTEM COMPLETE 48'	EACH	3	3							
44000013	BITUMINOUS SURFACE REMOVAL, 5"	SQ YD	143			143					
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	82			82					
44000100	PAVEMENT REMOVAL	SQ YD	161,041	161,041							
44000500	COMBINATION CURB AND GUTTER REMOVA	FOOT	6,313	6,313							
44000700	APPROACH SLAB REMOVAL	SQ YD	219			219					
44001980	CONCRETE BARRIER REMOVAL	FOOT	24,320	24,320							
44004250	PAVED SHOULDER REMOVAL	SQ YD	62,227	62,227							
44201423	CLASS C PATCHES, TYPE I, 16 INCH	SQ YD	25	25							
44201427	CLASS C PATCHES, TYPE II, 16 INCH	SQ YD	60	60							
44201431	CLASS C PATCHES, TYPE III, 16 INCH	SQ YD	50	50							
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	36	36							

62302 \*1818, ETC, 2324.6-1PR-9

S.N. 016-0142  
S.N. 016-1148

\* - SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)  
31ST STREET TO 71ST STREET  
SB EXPRESS LANE RECONSTRUCTION  
SUMMARY OF QUANTITIES  
SCHEDULE

SCALE: NTS  
DATE: 07/07/05

DRAWN BY: RA  
CHECKED BY: JDC

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
Chicago, Illinois  
312.228.0100  
www.bbainc.com

Rev. 8-31-05

500-01  
5:56:44 PM  
6/29/2005