

SCHEDULE OF STORM SEWERS

F.A.I. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	COOK	598	148
STA. TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	
62302		• (818, ETC, 2324.6-IPR-9	

FROM STRUCTURE	TO STRUCTURE	SLOPE %	SS CL A T1 12	SS CL A T1 15	SS CL A T1 18	SS CL A T1 21	SS CL A T1 27	SS CL A T2 12	SS CL A T2 15	SS CL A T2 18	SS CL A T2 21	SS CL A T2 24	SS CL A T2 27	SS CL A T2 30	SS CL A T2 33	SS CL A T2 36	SS CL A T2 42	SS CL A T2 48	SS CL A T3 21	SS CL A T3 24	SS CL A T3 27	SS CL A T3 30	SS CL A T3 36	TRENCH BACKFILL
13-16	13-11	0.63								119														42.6
14-01	14-08*	0.16												40										55.3
14-03	14-01	1.12	2																					0.5
14-04	14-08*	0.52	16																					2.8
14-05	14-06	1.00		7																				2.2
14-06	14-01	0.22																						174.7
14-07	14-06	0.50	45																					9.7
14-08	14-06	0.70	43																					8.3
15-01	15-08	0.50	11																					1.7
15-02	15-03	0.50	10																					1.5
15-03	15-13	0.58							78															66.1
15-05	15-06	0.50	11																					1.9
15-06	15-03	1.00						6																4.2
15-07	15-06	0.50	11																					1.9
15-08	15-06	0.60	33																					7.1
15-09	15-08	0.50	11																					1.9
15-10	15-11	0.50	11																					1.9
15-11	15-13	0.50		8																				1.3
EXIST.	15-13	1.00	41																					35.7
15-12	15-11	0.50						11																3.1
15-13	15-06*	0.30																						38.1
15-14	15-03	0.50	45																					35.7
15-15	15-16	0.50	11																					2.6
15-16	15-06*	1.11																						1.9
15-17	15-06*	0.50						9	2															0.5
15-19	15-21	0.50						45																12.5
15-20	15-27	0.43		38																				9.0
15-21	15-13	0.30															86							58.7
15-22	15-23	1.68	6																					1.3
15-23	15-21	0.22																						102.2
15-24	15-29	0.80							4															1.0
15-25	15-29	0.50	45																					6.8
15-26	15-24	0.30		30																				6.4
15-27	15-28	0.50																						8.5
15-28	15-21	0.80		4																				2.7
15-29	15-23	0.30															55							48.7
16-01	16-05	0.24															203							146.8
EXIST.	16-01	0.64																						3.9
16-03	16-04	0.58	46																					8.9
16-04	16-01	0.50	17																					4.0
16-05	17-04	0.27																						26.4
16-06	16-05	1.00															53							1.1
16-07	16-05	0.50	62																					13.3
17-01	17-02	0.50	11																					1.9
17-03	17-02	0.40	11																					1.9
17-02	17-04	0.30																						0.5
17-04	17-18	0.15				2																		31.0
17-06	17-07	0.50	11																					1.9
17-08	17-07	0.50	11																					1.9
17-07	17-18	1.00																						0.6
17-18	17-04*	0.15																						4.8
17-09	17-04*	0.58	53																					9.2
17-10	17-03	0.39		43																				8.2
17-11	17-13	0.50																						3.1
17-12	17-13	0.50	59																					10.2
17-13	17-15	0.31																						148.6
17-14	17-15	2.50	4																					0.7
17-15	17-18*	0.20																						61.9
17-17	17-18*	1.68	6																					1.6
17-19	17-11	0.50	50																					2.9
18-01	18-07	0.43																						0.5
18-02	18-07	0.50	58																					10.0
18-03	18-05	0.81																						154.9
18-04	18-05	2.50	4																					0.8
18-05	19-03	0.64																						183.3
18-06	18-05	0.53	57																					9.9
18-07	18-03	0.81																						20.7
19-01	19-04	0.65																						3.1
19-02	19-03	0.68	6																					1.2
19-03	19-04	0.20																						64.5
19-06	19-05	0.50																						2.1
19-05	19-04	0.61																						10.9
19-07	19-06	0.50	11																					2.1
19-09	19-10	0.91	11																					2.1
19-10	19-12	3.34																						0.6

NOTE: \* INDICATED STRUCTURE HAS BEEN CONSTRUCTED IN CONTRACT 62300



REVISIONS	
NAME	DATE
ADDENDUM 1	8/12/05

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)  
31ST STREET TO 71ST STREET  
SB EXPRESS LANE RECONSTRUCTION  
DRAINAGE SCHEDULE  
PROPOSED STORM SEWER PIPES  
SCALE: DRAWN BY:  
DATE: 7/1/05 CHECKED BY:

DS-28

08/11/2005 03:05:27 PM