

SCHEDULE OF STORM SEWERS

F.A.I. RTE. 94/90	SECTION	COUNTY COOK	TOTAL SHEETS 598	SHEET NO. 150A
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
62302		1818, ETC, 2324.6-1PR-9		

FROM STRUCTURE	TO STRUCTURE	SLOPE %	SS CL A T1 12	SS CL A T1 15	SS CL A T1 18	SS CL A T1 21	SS CL A T1 27	SS CLA T2 12	SS CLA T2 15	SS CLA T2 18	SS CLA T2 21	SS CLA T2 24	SS CLA T2 27	SS CLA T2 30	SS CLA T2 33	SS CLA T2 36	SS CL A T2 42	SS CLA T2 48	SS CLA T3 21	SS CLA T3 24	SS CLA T3 27	SS CLA T3 30	SS CLA T3 36	TRENCH BACKFILL
PLUG	15-26	0.44	2																					0.5
PLUG	16-01	0.44	19																					6.8
PLUG	16-06	0.44	2																					0.6
PLUG	17-02	0.44	4																					1.0
PLUG	17-10	0.44	3																					0.6
PLUG	17-11	0.44	3																					0.6
PLUG	17-14	0.44	3																					0.5
PLUG	18-01	0.44	3																					0.5
PLUG	19-09	0.44	3																					0.5
PLUG	19-15	0.44	3																					1.0
PLUG	19-18	0.44	3																					0.5
PLUG	19-19	0.44	3																					0.5
PLUG	20-03	0.44	3																					0.5
PLUG	20-05	0.44	3																					0.5
PLUG	20-09	0.44	3																					0.5
PLUG	21-02	0.44	3																					0.5
PLUG	22-01	0.44	3																					0.5
PLUG	22-11	0.58	6																					1.5
PLUG	22-07	0.44	6																					1.6
PLUG	23-01	0.44	3																					0.5
PLUG	23-06	0.44	3																					2.3
PLUG	23-11	0.50		3																				0.8
PLUG	24-04	0.44	3																					0.6
PLUG	24-05	0.44	3																					0.7
PLUG	24-15	0.44	3																					0.5
PLUG	24-20	2.63	8																					2.3
25-14	25-18	0.31												79										135.8
PLUG	25-18	1.65	9																					3.8
PLUG	25-10	0.44	3																					0.5
PLUG	26-12	0.44	3																					0.5
PLUG	27-06	0.44		5																				0.9
PLUG	27-11	1.73	3																					0.5
PLUG	28-05	0.44	3																					1.0
PLUG	28-12	0.44	3																					0.7
5-15	5-06	3.00		3																				1.4
8-17	8-15	4.00	2																					0.5
13-04	13-03	0.54		38																				9.9
19-08	19-06	0.60	2																					0.5
24-12	24-10	2.50	2																					1.0

NOTE: \* INDICATED STRUCTURE HAS BEEN CONSTRUCTED IN CONTRACT 62300

**Edwards AND Kelcey**  
 ONE NORTH FRANKLIN  
 CHICAGO, IL 60606  
 PHONE: (312) 251-3000  
 FAX: (312) 251-3015  
 WEB: WWW.EKCORP.COM

REVISIONS	
NAME	DATE
ADDENDUM 1	8/12/05

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. 94/90 (DAN RYAN EXPRESSWAY)  
 31ST STREET TO 71ST STREET  
 SB EXPRESS LANE RECONSTRUCTION

DRAINAGE SCHEDULE  
 PROPOSED STORM SEWER PIPES

SCALE: \_\_\_\_\_ DRAWN BY: \_\_\_\_\_  
 DATE: 7/7/05 CHECKED BY: \_\_\_\_\_

DS-30A

08/17/2005 03:06:27 PM