

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	*	COOK	598	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

62302 * (1818, ETC, 2324.6-1)PR-9

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN		90% FEDERAL / 10% STATE							
			TOTAL QUANTITY	ROADWAY J000-2A	RETAINING WALLS Y007	S.N. 016-2625 X928-2A	SIGNING Y002-1C	SAFETY SFTY-3N	LIGHTING Y030-1E	SURVEILLANCE Y032-1F	BRIDGE REPAIRS SFTY-2A	
550B0050	STORM SEWERS, CLASS B, TYPE 1 12"	FOOT	486	486								
550B0070	STORM SEWERS, CLASS B, TYPE 1 15"	FOOT	38	38	△							
552A1300	STORM SEWERS JACKED IN PLACE, CLASS A 36"	FOOT	85	85								
552A1500	STORM SEWERS JACKED IN PLACE, CLASS A 42"	FOOT	259	259								
552A1600	STORM SEWERS JACKED IN PLACE, CLASS A 48"	FOOT	120	120	△							
X0320870	BRACED EXCAVATION	CU YD	4,980	4,980	△							
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	957	957								
X0323221	PLUG AND ABANDON EXISTING PIPE	CU YD	341	341	△							
□ X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	222	222								
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	34,916	34,916	△							
X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	37,117	37,117	△							
X0324112	BARRIER BASE	FOOT	28,985	28,985	△							
X0324431	TEMPORARY SOIL RETENTION SYSTEM (TO REMAIN IN PLACE)	SQ FT	16,000		16,000							
X0324697	SOIL STABILIZERS	POUND	163,129	163,129								
X0324698	APPLY DUST SUPPRESSION AGENTS	UNIT	95	95								
X4210400	LUG SYSTEM REMOVAL	EACH	2	2								
X4834090	PORTLAND CEMENT CONCRETE SHOULDERS - 14"	SQ YD	58,371	58,371	△							
* X5120905	FURNISHING SOLDIER PILES W 12X72	FOOT	1420	1420	△							
* X5120907	FURNISHING SOLDIER PILES W 12X120	FOOT	9060	9060	△							
* X5120952	FURNISHING SOLDIER PILES W 24X106	FOOT	5120	5120	△							
X6020166	DRAINAGE STRUCTURES, TYPE 1 SPECIAL WITH TWO TYPE 20 FRAMES AND GRATES	EACH	52	52	△							
X6020167	DRAINAGE STRUCTURES, TYPE 2 SPECIAL WITH TWO TYPE 22 FRAMES AND GRATES	EACH	4	4								
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	674	674								
X6370910	CONCRETE BARRIER, SINGLE FACE, 32" HEIGHT	FOOT	2,672	2,672								
X6370925	CONCRETE BARRIER, SINGLE FACE, 42" (SPECIAL)	FOOT	21,311	21,311	△							
X6370930	CONCRETE BARRIER, DOUBLE FACE, 32" HEIGHT	FOOT	2,677	2,677								
X6370935	CONCRETE BARRIER, SINGLE FACE, 32" (MODIFIED)	FOOT	815	815								
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1								
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	270	270								
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	55	55								
X7040600	FURNISH TEMPORARY CONCRETE BARRIER	FOOT	15,863	15,863	△							
* X7330110	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	46				46					
* X8160380	UNIT DUCT, W 3-1/2 NO.2 AND 1/2 NO.4 GRND, 600V (EPR-TYPE RHW), 1 1/4" DIA., POLYETHYLENE	FOOT	825						825			
XX001854	STABILIZED SUB-BASE 6"	SQ YD	215,848	215,848	△							

□ - NON-PARTICIPATING
* - SPECIALTY ITEM

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com

△ Rev. 9-19-05
△ Rev. 8-21-05

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
31ST STREET TO 71ST STREET
SB EXPRESS LANE RECONSTRUCTION
SUMMARY OF QUANTITIES
SCHEDULE

SCALE: NTS
DATE: 07/07/05

DRAWN BY: RA
CHECKED BY: JDC

S00-06

6/29/2005 5:36:08 PM