

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN		90% FEDERAL / 10% STATE								
			TOTAL QUANTITY	ROADWAY J000-2A	RETAINING WALLS Y007	S.N. 016-2625 X928-2A	SIGNING Y002-1C	SAFETY SFTY-3N	LIGHTING Y030-1E	SURVEILLANCE Y032-1F	BRIDGE REPAIRS SFTY-2A		
XX004201	PAVEMENT REINFORCEMENT 14"	SQ YD	146,672	146,672									
XX004812	VIDEO TAPING OF SEWERS	FOOT	753	753									
XX005489	STEEL CASING 48"	FOOT	85	85									
Z0026420	STEEL CASING 60"	FOOT	259	259									
Z0068426	STEEL CASING 66"	FOOT	120	120									
Z0002600	BAR SPLICERS	EACH	277	20		257							
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1									
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	42	42									
Z0018800	DRAINAGE SYSTEM	L SUM	1	1									
Z0018900	DRILL AND GROUT DOWEL BARS	EACH	6,494	6,494									
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	6						6				
Z0002300	BALLAST	CU YD	5018	5018									
Z0030070	IMPACT ATTENUATORS (SEVERE USE, NARROW) TEST LEVEL 3	EACH	2						2				
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1						1				
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	5						5				
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	494	494									
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	0.8								0.2	
Z0076600	TRAINEES	HOUR	2000	2000									
X8100042	CONDUIT ENCASED, CONCRETE, 3" DIA., PVC	FOOT	777									777	
X0325080	VIDEO TAPING OF MWRD CULVERT	FOOT	245				245						
X4810100	TEMPORARY SHOULDERS	SQ YD	7713	7713									
X0325081	CONCRETE SLAB HYDRO-DEMOLITION	SQ YD	237				237						
X03270927	CONCRETE BARRIER SINGLE FACE 72" (SPECIAL)	FOOT	166	166									
X0325082	CTA BARRIER REMOVAL	FOOT	22,239	22,239									
X0325083	CTA FENCE	FOOT	21,718	21,031			87						
X0325084	CTA GATES	EACH	24	24									
X0325085	TEMPORARY PAVEMENT (INTERSTATE)	SQ YD	10,717	10,717									
X7011008	TRAFFIC CONTROL AND PROTECTION FOR ALTERNATE ROUTE SIGNING	L.M.M.D	10	10									
X0325086	TEMPORARY CTA BALLAST RETENTION	L SUM	1				1						
X7330105	OVERHEAD SIGN STRUCTURE WALKWAY TYPE A	FOOT	56					56					
X0950610	REMOVE AND RELOCATE EXISTING LIGHTING UNIT	EACH	5							5			
X0210015	TEMPORARY LUMINAIRE, 400 WATT HPSV	EACH	5							5			
X2020300	EXCAVATE AND PLACE EXISTING GRANULAR MATERIAL	CU YD	56,192	56,192									
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	166,371	166,371									
B1000800	CONDUIT IN TRENCH, 3" DIA. GALVANIZED STEEL	FOOT	75									75	
B3600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	65									65	
S0102400	CONCRETE REMOVAL	CU YD	3.2	3.2									

* - Y000
 * - SPECIALTY ITEM
 □ - NON-PARTICIPATING

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
 31ST STREET TO 71ST STREET
 SB EXPRESS LANE RECONSTRUCTION
 SUMMARY OF QUANTITIES
 SCHEDULE

SCALE: NTS
 DATE: 07/07/05
 DRAWN BY: RA
 CHECKED BY: JDC

BOWMAN, BARRETT & ASSOCIATES INC.
 CONSULTING ENGINEERS
 Chicago, Illinois
 312.228.0100
 www.bbainc.com

Rev. 8-31-05

6/29/2005 5:38:42 PM