

PAVEMENT, SHOULDERS, AND MEDIANS

STATION	TO STATION	CONT REINF PCC PVT 14 (SQ YD)	PAVT REINF (SQ YD)	PCC SHOULDERS 14 (SQ YD)	TEMP PAVEMENT (INTERSTATE) (SQ YD)	TEMP SHOULDERS (SQ YD)	STAB SUB- BASE 6 (SQ YD)	SUB GRAN MAT B 24 (SQ YD)	SUB GRAN MAT B 12 (SQ YD)	GEOTECH FAB F/GR STAB (SQ YD)	CONC MEDIAN SURF 6 SP (SQ YD)	PROTECTIVE COAT (SQ YD)	BIT SHLD SUPER 6 (SQ YD)
1367+00	1382+00	10242	10242	1235	51		11751	11751		11751	218	11528	
1382+00	1397+00	8536	8536	2559			11436	11436		11436	13800	11095	36
1397+00	1412+00	6000	6000	3485			10077	10077		10077		9489	
1412+00	1427+00	6000	6000	4234	219		10816	10816		10816		10453	
1427+00	1442+00	6000	6000	3360	569		8520	8520		8520		8259	
1442+00	1457+00	8356	8356	4568	1448		7074	7074	5035	11989		11474	
1457+00	1472+00	8547	8547	2964	712				14085	14085		13827	
1472+00	1487+00	8000	8000	3219	788				11874	11874		11752	
1487+00	1502+00	8000	8000	3181	828				12261	12261		12009	
1502+00	1517+00	10419	10419	3260	2096				16182	16182	2471	15775	
1517+00	1530+00	5771	5771	2850	1892				10922	10922	4071	10513	
1530+00	1542+00	5074	5074	2953	254	1593	8239		10262	9943		8027	
1542+00	1554+00	8171	8171	2410		1274	10779		12068	11563		10581	
1554+00	1566+00	6400	6400	2463		1042	9038		10103	9738		8863	
1566+00	1578+00	6400	6400	2439	381	627	8985		10030	9631		8839	
1578+00	1590+00	5937	5937	2262	211	777	8362		9372	9035		8199	
1590+00	1602+00	6400	6400	2439		1112	9039		10159	9759		8839	
1602+00	1614+00	6400	6400	2289	406	620	8795		9838	9515		8689	
1614+00	1626+00	6400	6400	2146	743	308	8557		9625	9238		8546	
1626+00	1638+00	6400	6400	2583	120	360	9204		9698	9629		8983	
1638+00	1644+22	3215	3215	1470			4856	4856	4856	4856		4685	
TOTAL		146669	146669	58370	10717	7712	215767	59674	166371	222820	20560	210425	36

PAVEMENT AND SHOULDER REMOVAL

STATION	TO STATION	PAVEMENT REM (SQ YD)	PAVED SHLD REMOVAL (SQ YD)	APPROACH SLAB REM (SQ YD)
1367+00	1382+00	9680	1500	
1382+00	1397+00	13889	1500	
1397+00	1412+00	8605	1672	
1412+00	1427+00	8642	1886	
1427+00	1442+00	6330	3311	
1442+00	1457+00	10038	4037	
1457+00	1472+00	8475	3333	
1472+00	1487+00	8485	3061	
1487+00	1502+00	8429	3333	
1502+00	1517+00	10115	4163	
1517+00	1530+00	6449	4233	
1530+00	1542+00	6267	3392	
1542+00	1554+00	7884	3532	
1554+00	1566+00	6400	3190	
1566+00	1578+00	6400	3189	
1578+00	1590+00	6036	3076	219
1590+00	1602+00	6400	3160	
1602+00	1614+00	6400	3105	
1614+00	1626+00	6400	3090	
1626+00	1638+00	6400	2925	
1638+00	1644+22	3317	1537	
TOTAL		161041	62228	219

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
Chicago, Illinois  
312.228.0100  
www.bbandainc.com

REVISIONS	
NAME	DATE
ADDENDUM 1	08/12/05
ADDENDUM 2	09/16/05

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)  
31ST STREET TO 71ST STREET  
SB EXPRESS LANE RECONSTRUCTION  
ROADWAY SCHEDULES  
SCALE: 1"=N.T.S.  
DATE: 07/07/05  
DRAWN BY: RR  
CHECKED BY: JDC

RSCH-01

9/15/2005 2:16:01 PM