F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	*	COOK	598	147
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

62302 * (1818, ETC, 2324.6-1)R-9

SCHEDULE OF STORM SEWERS

FROM STRUCTURE	TO STRUCTURE	SLOPE %	SS CL A T1 12	SS CL A T1 15	SS CL A T1 18	SS CL A T1 21	SS CL A T1 27	SS CLA T2 12	SS CLA T2 15	SS CLA T2 18	SS CLA T2 21	SS CLA T2 24	SS CLA T2 27	SS CLA T2 30	SS CLA T2 33	SS CLA T2 36	SS CL A T2 42	SS CLA T2 48	SS CLA T3 21	SS CLA T3 24	SS CLA T3 27	SS CLA T3 30	SS CLA T3 36	TRENCH BACKFILL
8-16	8-15	0.50	11																					1.7
8-14	8-19*	0.50		41																				9.7
8-18	8-19	1.26		2																				0.5
EXIST.	8-18	0.50		8																				1.5
8-07	8-19	0.35									56													40.5
8-19	8-13	0.35									80													67.2
8-20	8-07	0.50	43																					8.3
9-01	9-02	1.12	9																					1.6
9-02	9-04	0.45							145															127.9
9-03	9-04	0.50						43																12.9
9-04	9-06	0.36								186														235.5
9-05	9-06	2.50	4																					0.7
9-06	9-11*	0.15														40								64.3
9-08	9-11*	0.65	26																					4.5
9-09	9-06	0.25											208											295.2
9-10	9-09	1.68	6																					1.0
9-11	9-09	0.61						44																13.2
9-12	EXIST.	1.00	7																					0.5
9-13	EXIST.	1.00	8																					0.5
9-14	EXIST.	1.00	6																					0.5
9-15	EXIST.	1.00	9																					0.5
10-01	9-09	0.32									180													248.4
10-02	10-01	1.44	3																					0.5
10-03	10-01	0.50						45																13.5
10-04	10-05	3.30	3																					0.5
10-05	10-01	0.32									114													209.1
10-06	10-05	0.50						44																13.2
10-07	10-06*	0.15														41								76.0
10-08	10-07	2.00	2																					0.5
10-10	10-06*	2.00	2																					0.5
10-11	10-07	0.18												97										169.1
10-12	10-11	0.18												84										138.9
10-13	10-12	2.00	2																					0.5
10-14	10-12	0.65	45																					8.7
10-15	EXIST.	0.50	217																					21.8
10-16	10-15	0.43	7																					0.9
10-17	10-16	0.56	106																					15.1
11-01	11-02	0.50	46																					8.9
11-02	10-12	0.32									187													251.0
11-03	11-02	0.34		30																				5.7
11-04	11-06	0.50		64																				12.8
11-05	11-01*	0.50	73																					12.6
11-06	11-01*	0.23															38							72.2
11-08	11-06	0.20															139							241.3
11-09	11-08	0.50	44																					8.5
EXIST.	11-06	0.50	5																					6.2
12-01	11-08	1.12	3																					0.7
12-02	11-08	0.20															21							33.1
12-03	12-04	0.50	44																					8.5
12-04	12-02	0.20															182							257.5
12-05	12-04	3.30	3																					0.6
12-06	12-07	0.50	46																					8.9
EXIST.	12-07	1.00	4																					3.8
12-07	12-04	0.20															175							191.3
12-08	12-09	3.30	3																					0.6
12-09	12-07	0.25														60								46.0
12-10	12-09	0.25														89								58.8
12-11	12-10	0.50	44																					8.5
EXIST.	12-10	1.00	5																					1.0
12-12	13-05	0.50	11																					1.7
12-13	13-01	0.50	11																					1.7
13-01	13-03	1.00		2																				0.5
13-02	13-01	0.32		15																				2.1
13-03	12-10	0.25														57								29.6
13-05	13-03	0.54		44																				10.4
13-06	13-05	0.50	11																					1.7
13-07	13-08	0.50	44																					8.5
13-08	13-03	0.25														83								17.5
13-09	13-10	3.30	3																					0.5
13-10	13-08	0.35												41										8.0
13-11	13-10	0.50										107												26.5
13-12	13-11	0.50	44																					13.5
13-13	13-16	3.60	2																					0.5
13-14	13-16	0.63								86														33.0
13-15	13-14	0.62	49																					11.6

NOTE: * INDICATED STRUCTURE HAS BEEN CONSTRUCTED IN CONTRACT 62300

Edwards AND Kelcey
ONE NORTH FRANKLIN
CHICAGO, IL 60606
PHONE: (312) 251-3000
FAX: (312) 251-3015
WEB: WWW.EKCORP.COM

REVISIONS	
NAME	DATE
1 ADDENDUM 1	8/12/05
2 ADDENDUM 2	9/16/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
31ST STREET TO 71ST STREET
SB EXPRESS LANE RECONSTRUCTION

DRAINAGE SCHEDULE
PROPOSED STORM SEWER PIPES

SCALE:
DATE: 7/7/05
DRAWN BY:
CHECKED BY:

DS-27

p:\30019235\Con 148\5\CADD\DS\DS15\30232e.sht
09/14/2005 11:04:42 AM