

SCHEDULE OF STORM SEWERS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	598	149
STA.		TO STA.		
62302		11818, ETC, 2324.6-1PR-9		

FROM STRUCTURE	TO STRUCTURE	SLOPE %	SS CL A T1 12	SS CL A T1 15	SS CL A T1 18	SS CL A T1 21	SS CL A T1 27	SS CLA T2 12	SS CLA T2 15	SS CLA T2 18	SS CLA T2 21	SS CLA T2 24	SS CLA T2 27	SS CLA T2 30	SS CLA T2 33	SS CLA T2 36	SS CL A T2 42	SS CLA T2 48	SS CLA T3 21	SS CLA T3 24	SS CLA T3 27	SS CLA T3 30	SS CLA T3 36	TRENCH BACKFILL
19-11	19-10	0.50	11																					2.1
19-12	19-03	0.34								61														18.7
19-13	19-14	0.54	56																					10.9
19-14	19-12	0.57						91																23.6
19-15	19-14	2.00	5																					1.1
19-16	19-23	0.50								38														12.6
19-17	19-16	0.50	54																					9.3
19-18	19-16	0.64	4																					0.7
19-19	19-21	1.68	6																					1.2
19-20	19-22	1.12	9																					1.7
19-23	19-21	0.50								141														111.8
19-21	19-22	0.12																						66.7
20-01	19-21	0.20																						73.6
20-02	20-01	0.20																						91.3
20-03	20-02	1.70	6																					1.0
20-04	20-02	0.58	51																					8.8
20-05	20-07	3.30	3																					0.5
20-06	20-07	0.52	55																					9.5
20-07	20-11	0.40												31										39.1
20-11	20-02	0.40												135										150.1
20-08	20-07	0.40												197										281.1
20-09	20-08	2.00	2																					0.5
20-10	20-08	0.50	55																					9.5
21-01	20-08	0.55									210													298.0
21-02	21-01	1.12	3																					0.6
21-03	21-01	0.58	52																					9.0
EXIST.	21-01	0.50	14																					2.7
22-01	22-03	3.30	3																					0.6
22-02	22-03	0.55	56																					9.7
22-03	22-11	0.50																						162.9
22-04	22-05	0.55	55																					9.5
22-05	22-07	0.35												142										209.2
22-06	22-05	3.30	3																					0.6
22-07	22-08	0.35												46										61.5
22-08	23-02	0.17																						219.4
22-09	22-08	1.68	3																					0.6
22-10	22-08	0.55	55																					10.7
22-11	22-05	0.36																						86.9
EXIST.	22-07	1.00						3																2.9
EXIST.	22-11	1.00						3																3.4
23-01	23-02	1.00		3																				0.6
23-02	23-03	0.17																						129.9
23-03	23-07	0.17																						57.4
23-04	23-02	0.56	56																					10.9
23-05	23-08	0.61	23																					3.5
23-06	23-07	3.34	3																					0.6
23-07	23-08	0.20																						69.4
23-09	23-07	0.38												173										124.6
23-10	23-09	0.53	55																					9.5
23-11	23-09	0.78	17																					5.1
24-01	24-03	0.55	57																					9.9
24-02	24-03	1.00	3																					0.7
24-03	24-08	0.35																						24.1
24-04	24-02	0.92	11																					2.1
24-05	24-06	1.57	7																					1.2
24-06	24-08	1.00		3																				0.9
24-07	24-06	0.50	11																					2.1
24-08	24-13	0.33																						22.8
24-09	24-10	0.50	11																					2.1
24-10	24-11	1.00		11																				2.1
24-11	24-14	1.00		47																				12.2
24-15	24-13	2.00	5																					1.0
24-13	24-14	0.20																						39.0
24-16	24-14	0.64	28																					5.4
24-17	24-19	1.33	3																					0.6
24-18	24-19	0.57	56																					8.5
24-19	24-13	0.21																						174.9
24-20	24-19	0.20																						70.1
EXIST.	24-20	0.50	5																					0.8
25-01	24-20	0.20																						179.3
25-02	25-04	3.00	3																					0.6
25-03	25-04	0.50	60																					10.4
25-04	25-01	0.20																						25.7
25-05	25-14	1.00																						0.5
25-06	25-14	0.35																						32.6



NOTE: * INDICATED STRUCTURE HAS BEEN CONSTRUCTED IN CONTRACT 62300

REVISIONS	
NAME	DATE
ADDENDUM 1	8/12/05
ADDENDUM 2	9/16/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
 31ST STREET TO 71ST STREET
 SB EXPRESS LANE RECONSTRUCTION

DRAINAGE SCHEDULE
 PROPOSED STORM SEWER PIPES

SCALE: DATE: 7/7/05 DRAWN BY: CHECKED BY:

DS-29

09/14/2005 11:05:24 AM