

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	556	19
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
62300		• (1818, ETC, 2324.6-1P)R-8		

CONCRETE BARRIER WALL, COMBINATION CONCRETE CURB AND GUTTER, & CTA FENCE

STATION	TO STATION	CONC BAR 1F 32HT (FOOT)	CONC BAR 1F 42HT SPL (FOOT)	CTA FENCE (FOOT)	CONC BAR 1F 72HT SPL (FOOT)	CONC BAR 2F 32HT (FOOT)	CONC BAR TRANS (FOOT)	BARRIER BASE (FOOT)	BARRIER WALL MARKERS (EACH)	COMB CC&G TM4.24 (FOOT)	CTA GATE (EACH)	PROTECTIVE COAT (SQ YD)
2367+00	2382+00		783	826			15	798	10		1	656
2382+00	2397+00		1297	1338	66		39	1402	18	447	1	1,251
2397+00	2412+00	413	1600	1418		80	60	2153	28	509	2	1,834
2412+00	2427+00		1720	1376			110	1830	23		2	1,570
2427+00	2442+00	500	1500	1467				2000	25		1	1,563
2442+00	2457+00	829	1371	1423			40	2240	28		2	1,707
2457+00	2472+00		1411	1441			60	1471	19		1	1,209
2472+00	2487+00		478	572	30		91	599	9		1	509
2487+00	2502+00		1426	1438	39		68	1533	19		1	1,282
2502+00	2517+00		1398	1413		177	15	1590	22		1	1,307
2517+00	2530+00		1134	1149		1171	45	2350	44		1	1,932
2530+00	2542+00		113	162		1150	40	1352	45			981
2542+00	2554+00		1125	1100	75	137	28	1364	19		2	731
2554+00	2566+00		1076	1111			117	1192	15		2	537
2566+00	2578+00		993	1051			113	1106	15			495
2578+00	2590+00		1000	1104			45	1045	15		1	500
2590+00	2602+00		1200	1188			24	1224	15		1	600
2602+00	2614+00		680	683			31	711	15		1	340
2614+00	2626+00		44	80	61		15	169	15		1	97
2626+00	2637+49		890	907	61		52	1003	15		1	495
TOTAL		1,742	21,241	21,248	332	2,715	973	27,132	414	956	23	19,599

CONCRETE BARRIER & COMBINATION CONCRETE CURB AND GUTTER REMOVAL

STATION	TO STATION	CONC BARRIER REMOV (FOOT)	CTA BARRIER REMOV (FOOT)	COMB CURB GUTTER REM (FOOT)
2367+00	2382+00		907	720
2382+00	2397+00		1393	593
2397+00	2412+00	30	1418	880
2412+00	2427+00	1019	1418	478
2427+00	2442+00	1500	1500	68
2442+00	2457+00	1,526	1422	604
2457+00	2472+00	1441	1441	
2472+00	2487+00	1376	501	
2487+00	2502+00	1467	1478	
2502+00	2517+00	1474	1413	1185
2517+00	2530+00	1200	1150	1250
2530+00	2542+00	1200	162	1045
2542+00	2554+00	1250	1200	2008
2554+00	2566+00	1126	1117	
2566+00	2578+00	1051	1060	
2578+00	2590+00	1102	1114	
2590+00	2602+00	1200	1200	
2602+00	2614+00	1112	694	
2614+00	2626+00	1132	93	
2626+00	2637+49	1112	1100	
TOTAL		21,318	21,780	8,832

**Edwards
AND
Kelcey**
ONE NORTH FRANKLIN
CHICAGO, IL 60606
PHONE: (312) 251-3000
FAX: (312) 251-3015
WEB: WWW.EKCORP.COM

REVISIONS	
NAME	DATE
ADDENDUM 1	8/12/05
ADDENDUM 2	9/16/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
31ST STREET TO 71ST STREET
NB EXPRESS LANE RECONSTRUCTION

ROADWAY
SCHEDULE

SCALE: NONE
DATE: 7/7/05

DRAWN BY: TAI
CHECKED BY: PJM

09/15/2005 09:48:03 AM