

SCHEDULE OF STORM SEWERS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	COOK	556	143	
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
62300	• (1818, ETC, 2324.6-IPR-8			

FROM STRUCTURE	TO STRUCTURE	SLOPE %	SS CL A T1 J2	SS CL A T1 15	SS CL A T1 18	SS CL A T1 21	SS CL A T2 12	SS CL A T2 15	SS CL A T2 18	SS CL A T2 21	SS CL A T2 24	SS CL A T2 27	SS CL A T2 30	SS CL A T2 33	SS CL A T2 36	SS CL A T2 42	SS CL A T2 48	SS CL A T3 12	SS CL A T3 21	SS CL A T3 24	SS CL A T3 30	SS CL A T3 36	SS CL A T3 42	SS CL B T1 12	SS CL B T1 15	TRENCH BACKFILL	
20-02	JC T2 20-01*	0.50	5																							0.8	
20-03	20-01	2.00	5																								0.8
20-12	20-01	0.30													76												114.6
20-05	20-04	0.61	54																								8.8
20-06	20-04	1.30	2																								0.5
20-04	20-12	0.20													107												186.5
EXIST.	20-12	1.00	5																								0.9
20-08	20-07	1.00						54																			15.0
20-09	20-07	2.50					15																				13.7
20-13	20-09	2.50					80																				32.2
20-07	20-04	0.15													184												326.8
20-11	20-10	0.16																									16.1
20-10	20-07	0.35											65	97													130.6
EXIST.	20-11	1.00	2																								0.5
21-01	20-11	0.25											41														56.6
21-02	21-01	0.50	55																								7.3
21-03	21-01	1.30	2																								0.5
21-04	21-01	0.50											188														266.8
21-05	21-04	0.51	59																								9.0
21-06	21-04	0.60	20																								3.0
EXIST.	21-04	0.50	2																								0.5
21-07	22-03	1.00	71																								18.2
22-02	22-03	0.78		3																							0.8
22-04	22-03	0.55	55																								9.7
22-05	22-06	1.10	45																								13.4
22-03	22-07	0.45												202													302.2
22-06	22-07	1.33	3																								1.0
22-08	22-07	0.57	55																								9.7
22-07	22-09	0.30													157												245.4
22-10	22-09	2.50	4																								0.7
22-11	22-09	0.51	40																								11.5
22-09	JC T2 22-01	0.30													51												72.8
22-12	JC T2 22-01	1.08	26																								4.5
22-14	JC T2 22-01	0.50	45																								8.7
23-01	23-02	3.50	6																								1.3
23-02	23-03	1.29						7																			1.8
23-04	23-03	0.60	55																								9.5
23-03	23-05	0.12																									233.4
23-06	23-05	2.51	4												203												1.0
23-09	23-05	0.23													185												178.0
23-05	JC T2 23-01*	0.10																									66.7
23-08	JC T2 23-01*	1.44	7												49												1.2
23-10	23-09	0.54	57																								9.9
23-11	23-09	0.92																									4.8
24-02	24-01	1.68	6																								1.0
24-03	24-01	0.51	60																								10.4
24-01	24-04	0.40		78																							18.4
24-06	24-04	1.00		3																							0.7
24-05	24-06	0.50	11																								1.7
24-07	24-06	0.50	11																								1.7
24-09	24-10	0.50	11																								1.7
24-10	24-11	0.50		11																							2.1
24-11	24-12	0.50		47																							11.1
24-12	JC T2 24.01*	0.70													4												0.9
24-04	24-13	0.42																									14.0
24-08	24-14	1.00	88																								4.0
24-15	24-13	0.15																									23.5
24-13	JC T2 24.01*	0.11																									46.3
24-16	24-15	4.00	2																								0.5
24-17	24-15	0.15																									146.1
24-18	24-17	0.15													151												21.8
24-19	24-17	0.70	20												18												5.0
24-14	24-18	1.00	1																								0.5
24-20	24-18	0.50	44																								10.4
24-21	24-18	0.18														95											82.3
25-01	24-21	0.32														83											122.3
24-22	24-21	1.0	20																								6.1
25-02	25-01	0.50		23																							7.2
25-03	25-01	0.50	52																								9.0
25-04	25-05	0.50	42																								9.0
25-05	25-06	0.50		23																							6.3
25-07	JC T2 25-01	0.62	26																								4.0

NOTE: * INDICATED STRUCTURE BEEN CONSTRUCTED IN CONTRACT 62302

REVISIONS		
NAME	DATE	
ADDENDUM 2	9/16/05	

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
 31ST STREET TO 71ST STREET
 NB EXPRESS LANE RECONSTRUCTION
 DRAINAGE SCHEDULE
 PROPOSED STORM SEWERS
 SCALE: 1" = N.T.S.
 DATE: 7/7/05
 DRAWN BY: MJO
 CHECKED BY: LPN



09/14/2005 02:50:03 PM